



VERIFICATION REPORT FOR “TAIBA N'DIAYE WIND POWER”

Document Prepared by “SustainCERT S.A.”

Report ID	VE-1023
Project title	Taiba N' Diaye Wind Power
Project ID	VCS- 2588
Verification period	01/08/2023 - 31/07/2024 (both days included)
Original date of issue	19/12/2024
Most recent date of issue	10/03/2025
Version	3.0
VCS Standard Version	VCS Standard Version 4.7 (VCS standard, v4.7)
Client	Parc Eolien Taiba N'Diaye S.A.U.
Prepared by	SustainCERT
Approved by	Indrapal Parmar
Work carried out by	Team Leader: Randolph Morales Local Expert: Namory Diakhate Technical Expert (TA1.2): Namory Diakhate Verifier: Randolph Morales Independent Reviewer (TA1.2): Muskan Chawla

Summary:

A description of the verification of the project:

The verification of the project titled “Taiba N’Diaye Wind Power”, VCS ID – 2588, has been undertaken by SustainCERT, with accordance to the relevant VCS standard, V4.7/^{1/}, VCS Program Guide, V4.4/^{2/} and relevant requirements of the ISO 14064-2 and ISO 14064-3, as well applicable criteria for consistent project operations, monitoring and reporting have been applied for verification.

The project “Taiba N’Diaye Wind Power” involves generation of electricity by wind power technology in Municipality of Taiba N’ Diaye, Tivaouane, Thies, Senegal. The project consists of 46 Vestas wind power turbines with a capacity of 3.45 MW each, totaling a capacity of 158.7 MW. The electricity generated by the project will be supplied to SENELEC (Société nationale d’électricité du Sénégal) grid system, the national electric company of Senegal. The project is a renewable energy generation activity that results in the reduction of greenhouse gas (GHG) emissions that are real, measurable, and verifiable and plays a beneficial role in the mitigation of climate change.

The Purpose and scope of verification:

Purpose: Verification service provided by SustainCERT for the project activity “Taiba N’Diaye Wind Power” is to perform independent periodic verification for the monitoring period 01/08/2023 to 31/07/2024 (including both days), first and last days inclusion verified from the emission reduction calculation sheet ^{/9/} and monthly invoices/^{14/}. The verification of the project is an independent review and ex-post determination by SustainCERT of the monitored reductions in GHG emissions that have occurred, against the VCS standard, V4.7/^{1/}, VCS Program Guide, V4.4/^{2/}, the Project baseline and host party criteria.

The scope of verification is to establish/verify that:

- The project activity has been implemented and operated as per the approved registered PD/^{5/}.
- All the physical features (technology, project equipment and monitoring and metering equipment) of the project are in place in accordance with registered PD/^{5/}.
- The monitoring report and other supporting documents provided are complete in accordance with the latest applicable version of VCS standard i.e., VCS standard, V4.7/^{1/}.
- The actual monitoring systems and procedures comply with the monitoring systems and procedures described in the monitoring plan, any registered monitoring plan, the approved methodology including applicable tool(s) and/or, where applicable, the approved standardized baseline.
- The data recorded and stored as per the monitoring methodology including applicable tool(s) and, where applicable, the standardized baseline.

The Monitoring Period:

The project activity “Taiba N’Diaye Wind Power” is undergoing 4th verification from 01/08/2023 to 31/07/2024 (both days included), under its crediting period from 09/12/2019 to 08/12/2029 (Ten years, Fixed).

The Method and Criteria used for Verification:

Desk Review: - Review of project information, monitoring plan specifically monitoring frequency, the metering equipment, calibration requirement, quality assurance and quality control system against the

registered PD, V2.1^{/5/} and applicable VCS standard^{/1/} and applied methodology “ACM0002- Grid connected electricity generation from renewable sources”, version 20.0^{/7/}, version of methodology inline to the PD^{/5/}.

Onsite audit:

-Interview with the relevant personnel to confirm the implementation of the project with paying particular attention to the operational and data collection procedures, in accordance with the registered PD^{/5/} and applied methodology^{/7/}.

- A detailed cross check of the information provided in the monitoring report^{/8/} against the relevant evidence such as relevant data sources, calibration records and other sources mentioned in Appendix 2 of the report.

- A detailed cross check of the calculations made for the estimation of GHG emissions.

- An evaluation of data management and the quality assurance and quality control system in the context of their influence on the generation and reporting of emissions reduction.

The number of findings raised during verification: A risk-based approach has been followed for the verification of the project. 02 CARs, 13 CLs and 00 FAR were raised during verification. All the issues raised were resolved successfully, details of which can be found in Appendix 3 of the report.

Any uncertainties associated with the verification: The assessment team thoroughly reviewed the monitoring report and the emission reduction calculation sheet against the relevant evidence and applicable VCS requirements, VCS standard V4.7^{/1/} and VCS guideline V4.4^{/2/}. It has been concluded that there are no more uncertainties associated with the project.

Summary of the verification conclusion

The review of monitoring report V3.0, emission reduction calculation sheet along with relevant supporting evidence and the interview with relevant personnel during an onsite audit on 12/11/2024^{/10/} have provided the assessment team with sufficient evidence to confirm to the applicable criteria and meet reasonable level of assurance. SustainCERT confirms the project activity ‘Taiba N’Diaye Wind Power has been successfully implemented in accordance with the registered PD^{/5/} and applied methodology “ACM0002, Version 20.0”^{/7/} meeting all the relevant VCS requirements. Based on the information seen and evaluated we confirm that the monitoring period 01/08/2023 to 31/07/2024 (including both the days) is in place and accounts to 215,839 tCO_{2e} of emission reductions by displacing 376,684MWh of electricity from fossil fuel dominating energy grid with electricity generated using wind energy system

CONTENTS

1	INTRODUCTION	6
1.1	Objective.....	6
1.2	Scope and Criteria	6
1.3	Level of Assurance.....	7
1.4	Summary Description of the Project	7
2	VERIFICATION PROCESS	8
2.1	Method and Criteria.....	8
2.2	Document Review	9
2.3	Interviews.....	10
2.4	Site Visits.....	12
2.5	Resolution of Findings	14
2.6	Eligibility for Validation Activities	14
3	VALIDATION FINDINGS	15
3.1	Methodology Deviations.....	15
3.2	Project Description Deviations.....	15
3.3	New Project Activity Instances in Grouped Projects.....	15
3.4	Baseline Reassessment	15
4	VERIFICATION FINDINGS.....	15
4.1	Project Details	15
4.2	Safeguards and Stakeholder Engagement	18
4.3	Accuracy of Reduction and Removal Calculations.....	27
4.4	Quality of Evidence to Determine Reductions and Removals.....	29
4.5	Non-Permanence Risk Analysis.....	34
5	VERIFICATION OPINION.....	34
5.1	Verification Summary	34
5.2	Verification Conclusion	35
5.3	Ex-ante vs Ex-post ERR Comparison	36
	APPENDIX 1: COMMERCIALLY SENSITIVE INFORMATION	37
	APPENDIX 2: TABLE OF REFERENCES	38
	APPENDIX 3: PROJECT FINDINGS.....	40

APPENDIX 4: COMPETENCY STATEMENT.....	54
APPENDIX 5: ABBREVIATIONS.....	57

1 INTRODUCTION

1.1 Objective

The Verification of the project titled “Taiba N’ Diaye Wind Power” VCS ID – 2588, has been undertaken by SustainCERT, as requested by Parc Eolien Taiba N’Diaye S.A.U (=project proponent) for the monitoring period 01/08/2023 to 31/07/2024 (including both the days). The verification of project activity is the 4th periodic verification for the crediting period 09/12/2019 to 09/12/2029 (fixed 10 years) which is verified from the VERRA Registry page ([Verra Search Page](#)). The purpose of the verification is to conduct the independent review of the project information and confirm:

- The project activity is implemented and operated in accordance with registered project description document, V2.1/^{5/}.
- All physical features (technology, project equipment, monitoring and metering equipment) are in place/^{8/}.
- The actual monitoring systems and procedures/^{8/} comply with the monitoring systems and procedures described in the monitoring plan/^{5/}, the approved methodology including applicable tool(s) and/or, where applicable, the approved standardized baseline/^{7/}.
- The data collection procedures, records and retention, are as per the monitoring methodology “ACM0002 – Grid connected electricity generation from renewable sources, Version 20.0”/^{7/} and registered project description document, V2.1/^{5/}.

The verification followed the requirements mentioned in the VCS standard, version 4.7/^{1/} and VCS guidelines, V4.4/^{2/} ensuring the quality and consistency of the report.

1.2 Scope and Criteria

The scope of verification for this project activity involves an independent and objective review and ex-post determination of the monitored reductions in GHG emissions, made by the project proponent in the monitoring report/^{8/}, emission reduction calculation sheet/^{9/} and other supporting evidence (as mentioned in Appendix 2 of the verification report) made available to the verification team for this monitoring period from 01/08/2023 to 31/07/2024, in accordance to:

- VCS standard, V4.7/^{1/}
- VCS guideline, V4.4/^{2/}

- Applied Methodology 'ACM0002 – Grid connected electricity generation from renewable sources, Version 20.0'^{7/}
- Other relevant rules and requirements, including host part requirements.

A risk-based approach has been followed for the verification of the project activity. Identifying and assessing the high-risk area and ensuring the reliability of the project's emission reductions generated.

The principles of accuracy, completeness, relevance, reliability and credibility were combined with a conservative approach to establish a traceable and transparent verification opinion. The verification considers both quantitative and qualitative information on emission reductions. The verification is not meant to provide any consultancy towards the client. However, stated requests for clarifications, corrective and/or forward actions may provide input for improvement of the monitoring activities.

1.3 Level of Assurance

The level of assurance achieved for the project verification falls under a reasonable level of assurance. The verification of the project activity is conducted by doing a thorough assessment of Monitoring report^{8/}, Registered PD^{5/}, emission reduction calculation sheet^{9/} and all the relevant documents mentioned in appendix 2 of the report.

Sufficient amount of evidence was gathered by the assessment team to reduce the risk associated with audit process. This means that there is some uncertainty arising from the use of sampling since it is possible that a material misstatement will be missed.

1.4 Summary Description of the Project

The project activity is a Wind Power Project by Parc Eolien Taiba N'Diaye S.A.U as PP, located in the Municipality of Taiba N' Diaye, Tivaouane, Thies, Senegal. The project activity consists of 46 Vestas wind power turbines with a capacity of 3.45 MW each, totaling a capacity of 158.7 MW.^{5/6/8/11/12/}

The project aims to generate cleaner electricity using wind power project and displace the amount of electricity generated using the fossil fuel-based power plant. SENELEC (Société nationale d'électricité du Sénégal) grid system, the national electric company of Senegal, this has been verified from PD^{5/}, Previous verification reports^{5/11/} and onsite audit^{10/}.

During current verification, an onsite audit for the project activity was conducted on 12/11/2024, where onsite implementation was checked, and interviews of the PP representatives were conducted to confirm the implementation of the project activity for current monitoring period. Furthermore, it was confirmed that the project involves supply of 376,684 MWh of electricity during the current monitoring period 01/08/2023 to 31/07/2024, leading to 215,839tCO_{2e} emission reductions. The information verified during onsite audit was found to be in line with the submitted monitoring plan^{/8/}, ER sheet^{/9/} and other documents mentioned in appendix 2 of the report.

The start date of the project activity is 09/12/2019^{/8/}, verified from the onsite audit^{/10/} and the same has been cross checked with previous verification report^{/11/} and onsite conducted during previous verification^{/11/}. The crediting period for the project activity is 09/19/2019 to 08/12/2029 (fixed, 10 years), as verified using previous verification report^{/11/} and the project page on VERRA.

Based on this, the assessment team confirms that the project activity “VCS-2588” is implemented and operational in accordance with applied methodology “ACM0002, v20.0”^{/7/}, Project Description Document^{/5/}, VCS standard^{/1/} and VCS guidelines^{/2/}. It has also been assessed and verified that emission reduction calculation for this monitoring period from 01/08/2023 to 31/07/2024^{/8/} has been done conservatively and found to be appropriate (details can be found in section 4 of this report). Thus, a reasonable level of assurance has been met.

2 VERIFICATION PROCESS

The Registered Project activity has been undergoing 4th Verification under Crediting period from 09/12/2019 to 08/12/2029 (fixed, 10 years), the approach adapted to ensure the quality and credibility of emission reduction is described in the following sections.

2.1 Method and Criteria

The method and criteria used for verification consist of following phases:

A risk-based approach has been applied for the process.

Desk review:

- To verify the completeness of the data and the information presented in the monitoring report^{/8/}, emission reduction calculation sheet^{/9/} and other evidence like calibration records, invoices and monthly reports, including all the other evidence mentioned in Appendix 2 of the report were strategically reviewed and risk assessment was undertaken.

- Project activity sources contributing to the leakage as well as project emissions are assessed.
- Evaluation of the data management and the quality assurance and quality control system in the context of their influence on the generation and reporting of emission reductions.

Onsite audit for the project was conducted on 12/11/2024 to:

- Interview of the project representatives and to confirm the implementation and operational status of the project with respect to the registered monitoring plan^{/5/}.
- Review the data flow for generating, aggregating and reporting the monitoring parameters,
- Confirm the correct implementation of procedures for operations and data collection,
- Cross-check the information provided in the MR documentation with other sources,
- Check the monitoring equipment against the requirements of the PD and the approved methodology, including calibrations, maintenance, etc.,
- Review the calculations and assumptions used to obtain the GHG data and ER,
- Identify if the quality control and quality assurance procedures are in place to prevent or correct errors or omissions in the reported parameters.

Further, details regarding the process of onsite audit have been mentioned in section 2.3 and 2.4 of the report. Resolution of all the issues and findings raised, and the final verification statement was issued.

2.2 Document Review

As part of verification of the project, the primary activity performed was the strategic review and risk assessment of the documents submitted using a dedicated protocol. A detailed review of MR^{/8/} and ER sheet^{/9/} was done to check:

- The completeness of the information with reference to the register PD^{/5/}.
- Review of project information, monitoring plan specifically monitoring frequency, the metering equipment calibration requirement, quality assurance and quality control system against the registered PD, V2.1 and applicable VCS standard^{/1/} and applied methodology “ACM0002”, version 20.0.
- A review of the QA/QC procedures were conducted to make sure the implementation is as per the register PD^{/5/}.

All the other evidence reviewed is mentioned in Appendix 2 of this report. The cross checks between information provided in the Monitoring report^{/8/}, VCS PD^{/5/} and information from sources other than those used, if available, the team's sectoral or local expertise and, if necessary, independent background investigations.

2.3 Interviews

In accordance with VCS standard, V4.7^{/1/}, site visit requirements, "A site visit that includes a visit to facilities and/or project areas shall be conducted at verification under the following circumstances: 1) The first verification of the project after validation; 2) Verifications that include project baseline reassessments; and 3) Verifications that assess a project description deviation where the deviation impacts the applicability of the methodology, additionality or the appropriateness of the baseline scenario." The project is currently undergoing 4th verification, and it was the first time for SustainCERT to conduct the verification of this project. Therefore, onsite audit was conducted during this verification on 12/11/2024^{/10/}. During the onsite audit for this verification, interview of the relevant project personnel and local stakeholders were conducted verifying the implementation and operational status of the project, the similar information was also cross verified using the evidence submitted by PP (as mentioned in Appendix 2 of the report). Detail of the personnel interviewed can be found in the table below:

Date of onsite Interview: 12/11/2024				
S.No	Name of the person	Affiliation	Details Discussed	Team member
1	Alioune Ba	Parc Eolien Taiba N'Diaye	Project implementation, Commissioning dates as per the requirements of VCS, Reliability and accuracy of readings are considered for emission reduction calculations, calibration procedure Monitoring, and measuring system. Collection of measurements Observations of established practices for verification of monitoring parameters, Electricity generation records (Monthly Energy Statements, Invoices) Emission reduction calculation, environmental concerns, entities involved, property rights, benefit sharing	Namory Diakhate
2.	Ousseynou Diedhiou	Parc Eolien Taiba N'Diaye	Grievance Mechanism. Project implementation, Employment opportunities, Electricity generation records	Namory Diakhate

			(Monthly Energy Statements, Invoices) calibration procedure Monitoring, and measuring system QA/QC procedures, labour and work rights, human rights, Cultural heritage	
3.	Amadou Sow	Parc Eolien Taiba N'Diaye	Grievance Mechanism. Project implementation, Employment opportunities, Electricity generation records (Monthly Energy Statements, Invoices) calibration procedure Monitoring, and measuring system QA/QC procedures, labour and work rights, human rights, Cultural heritage	Namory Diakhate
4	Elhadji Matar Sylla	Manager of Security Safety and Environment, Parc Eolien Taiba N'Diaye (Local Stakeholder)	Grievance Mechanism. Project implementation, Employment opportunities, Electricity generation records (Monthly Energy Statements, Invoices) calibration procedure Monitoring, and measuring system QA/QC procedures, labour and work rights, human rights, Cultural heritage	Namory Diakhate
5	Mor Kharma	Marie Local Municipality (Local Stakeholder)	Grievance Mechanism. Project implementation, Employment opportunities, Electricity generation records (Monthly Energy Statements, Invoices) calibration procedure Monitoring, and measuring system QA/QC procedures, labour and work rights, human rights, Cultural heritage	Namory Diakhate
6	Abdoulaye Dia	Youth Committee of Taiba N' Diaye (Local Stakeholder)	Grievance Mechanism. Project implementation, Employment opportunities, Electricity generation records (Monthly Energy Statements, Invoices) calibration procedure Monitoring, and measuring system QA/QC procedures, labour	Namory Diakhate

			and work rights, human rights, Cultural heritage	
--	--	--	---	--

The local stakeholders interviewed include individuals who gained employment through the development of the plant, as well as residents from the area surrounding the project activity. By the interview it was concluded that the local people were aware of the grievance mechanism and there were no negative comments from local stakeholder's side. Instead, the local people appreciated the development and job created by the project activity in that area. PP has also submitted Stakeholder grievance process details/^{25/} same details were also verified from onsite audit. Thus, a reasonable level of assurance was met.

2.4 Site Visits

As Discussed above, the physical site visit for the project was conducted for the current verification. Details and description of areas assessed can be found below:

Duration of the Audit: 12/11/2024			
S.No	Assessment Criteria	Means of Verification	Assessment Opinion
1	The assessment of the implementation and operation of the registered project activity	Registered PD/ ^{5/} and Validation report Interviews with PP/ ^{10/}	The information mentioned with reference to project implementation, capacity and commissioning in MR is found consistent with the documents and information received during interviews.
2	A review of information flows for generating, aggregating and reporting the monitoring parameters.	Monthly invoices/ ^{14/} and monthly Joint Meter Reading (JMR) reports / ^{13/} and emission reduction calculation sheet. Interviews with PP/ ^{10/}	The information related to flows for generating, aggregating and reporting the monitoring parameters mentioned in MR is found to be consistent with documents crosschecked and information received by interviews.

3	Interviews with relevant personnel to determine whether the operational and data collection procedures are implemented in accordance with the monitoring plan in the PD	Monthly Invoices/ ^{14/}	Monthly invoices are being cross checked. All the information related to operational and data collection is found to be inline with the PD/ ^{5/} and MR/ ^{8/} .
4	A check of the monitoring equipment including calibration performance and observations of monitoring practices against the requirements of the PD, the applied methodology including the tools applied	Calibration records/ ^{17/} Interviews with PP/ ^{10/}	Calibration records were verified and monitoring practices were verified with interview from PP, and it has been observed that all the practices are found to be in line with the PD.
6	A review on calculation of emission reductions	Monthly Invoices/ ^{14/} Monthly JMR reports/ ^{13/}	Values mentioned for ER calculation are found to be inline with the monthly invoices. Methods, formulae, and emission factors for calculating baseline emissions have been followed in accordance with the applied methodology/ ^{7/} .
7	An identification of quality control and quality assurance procedures in place to prevent or identify and correct any errors or omissions in the reported monitoring parameters	Monthly Invoices/ ^{14/} Monthly JMR reports/ ^{13/} Interview with PP	Methods, formulae, and emission factors for calculating baseline emissions have been followed in accordance with the applied methodology/ ^{7/} . All the QA/AC procedures were also verified on-site.

2.5 Resolution of Findings

As discussed above, a risk-based approach has been applied for the verification of the project activity. During the verification, assessment team identified the issues which could impact the accuracy and the credibility of the emission reduction claimed by the project, The details analysis of the issues raised the approach used to resolve these issues can be found in Appendix 3 of this report.

A corrective action request was raised if:

- Modifications to the implementation, operation, and monitoring of the registered project activity have not been sufficiently documented by the project participants.
- Mistakes have been made in applying assumptions, data, or calculations of emission reductions that will impact the number of emission reductions.

A clarification request was raised if:

- Information is insufficient or not clear enough to determine whether the applicable requirements have been met.

A Forward action request was raised if:

- If the monitoring and reporting require attention and/or adjustment for the next verification period.

During verification a total of 02 CARs, 13 CLs and 00 FAR were raised. The details of all the issues communicated to the PD can be found in the Appendix 3. The issues raised were closed successfully.

2.5.1 Forward Action Requests

The project activity is undergoing 4th Verification, monitoring period from 01/08/2023 to 31/07/2024. There are no FARs raised during the current verification period.

2.6 Eligibility for Validation Activities

There is no validation activity undertaken as a part of current verification.

3 VALIDATION FINDINGS

3.1 Methodology Deviations

There is no methodology deviation identified during the current monitoring period.

3.2 Project Description Deviations

There is no Project Description deviation identified during the current monitoring period

3.3 New Project Activity Instances in Grouped Projects

There are no new project activity instances added as the project activity is wind power project.

3.4 Baseline Reassessment

Did the project undergo baseline reassessment during the monitoring period?

☐ Yes

☒ No

The project activity has not undergone any baseline reassessment during the current monitoring period.

4 VERIFICATION FINDINGS

4.1 Project Details

The Project activity “Taiba N’Diaye Wind Power” is a wind power project located in the Municipality of Taiba N’ Diaye, Tivaouane, Thies, Senegal.. The project involves Generation of electricity using renewable energy and displacing the equal amount of energy generated by fossil fuels dominated grid. The installed capacity of the project is 158.7 MW. The project consists of 46 Vestas wind power turbines with a capacity of 3.45 MW each.

The Project Proponent for the project activity is Parc Eolien Taiba N’Diaye S.A.U and was interviewed during onsite audit, more details can be found from section 2.3 and 2.4 of the Verification report. Other entities are integral to the project. SENELEC, Senegal's national electricity company, operates the substation where the wind turbine generators are connected. Aera Group acts as a consultant, managing the monitoring report and emission reduction calculations for the verification process. These roles were confirmed during the onsite audit^{/10/} and through previous verification reports^{/11/}.

The start date of the project activity is 09/12/2019, the same has been verified during the onsite audit and also cross verified during the previous verifications^{/11/} of the project. The project activity is undergoing 4th verification from 01/08/2023 to 31/07/2024, and during this Monitoring period the project activity has delivered 376,684 MWh of electricity and reducing 215,839 tCO_{2e} emission reductions.

The details and calculations of the emission reductions have been verified and are found to be as per the guidelines of the applied methodology ACM0002, v 20.0^{/7/}, the version of methodology is online with PD^{/5/}, validation report and guidelines mentioned in VCS standard^{/1/}. The input values used for monitoring parameters were also cross checked against the monthly JMR reports^{/13/} and invoices^{/14/} provided by the PP to the assessment team. It has been verified that all the invoices are raised by PP. The required monitoring system is in place and operational, the same was verified during the onsite audit^{/10/}. The meters comply with appropriate quality standards applicable to the technology. The accuracy class of the meters installed for the project activity was verified on-site during previous verification and using photographic evidence^{/21/} during this verification.

During the onsite audit, it was concluded that the project is implemented as per the requirement of the registered VCS PD^{/5/}. During the current monitoring period, it was observed that no unforeseen incident or event evolved which can impact the operation of the project activity and this was also verified using Monthly maintenance reports^{/16/}, submitted by the PD. Although the project activity has undergone scheduled maintenance as per the onsite operation and maintenance protocols which is acceptable to the assessment team.

Monitoring Procedure:

During onsite audit^{/10/}, It has been verified that PP is responsible for ongoing operation of project activity and turbine supplier is responsible for maintenance of the Wind turbines. It was also confirmed that calibration of meter was done by the qualified personal inline with Interconnection agreement, further details related to calibration can be found in section 4.4 of the report.

Item	Evidence gathering activities, evidence checked, and assessment conclusion:
Audit history	The project activity is undergoing 4th Verification under a crediting period fixed for 10 years. The assessment team has verified that audit history using the Project webpage ^{/04/} , all previous verifications have been published under Verra. It has been concluded that the information present in section in 1.2 of MR is appropriate.

Double counting and participation under other GHG programs	The project activity is not registered under any other GHG and non-GHG program or registry. This has been confirmed by means of research on relevant applicable registries and available information in public domain and also a self-declaration towards the same has been provided by the PP/^{23/}. The assessment team has searched for similar projects having same nature, capacity and project proponent. The name of the owners mentions in the regulatory licenses are also matched and checked. It was concluded that no such projects having same location and geo-coordinates, technology or project/legal owners are registered in any of the various carbon schemes like CDM, GCC, and Gold Standard.
No double claiming with emissions trading programs or binding emission limits	The project activity has been thoroughly searched on the various websites of various emission trading programs. It has been found that the project is not part of any emission trading scheme. Also, a declaration has been provided by PP mentioning that the project is not part of any other scheme.
No double claiming with other forms of environmental credit	As discussed above the, the project has been thoroughly researched in all the currently active environmental schemes and found that the project is not registered with any other environmental credits. PP has also submitted a self-declaration stating that the project is not registered with any other registry/^{23/}. Therefore, it can be concluded that the project is not claiming credits with any other schemes. CL 04 was also raised regarding the same, the details for which can be found in Appendix 3 of the report.
Supply chain (scope 3) emissions double claiming	Not applicable as it a wind power project.
Sustainable development contributions	The project activity targets 3 of SDG goals: SDG 7 – Clean and Affordable energy: As the project activity is a wind power project, it generated clean energy. It has been verified by the means of evidence provided/^{13/} the project has generated 376,684 MWh of clean energy during this monitoring period.

	2. SDG 8 – Decent Work and economic growth: The project being a wind power project, it has generated employment opportunities for the local people. It has been verified during onsite audit/^{10/} and by the means of evidence provided/^{23/}, the project activity has provided employment opportunity to 27 of the personnel. 3. SDG 13- Climate action: As the project activity is Hydro Power project, generating clean energy which is replacing equal amount of energy from fossil fuel dominated grid, thus contributing positively to climate change. During the current MP, project has contributed to emission reductions of 215,839 tCO₂e. The assessment team has verified the details related to SDG goal, which is from to be appropriate.
Additional information relevant to the project	No commercially sensitive information has been excluded by the PP.

Based on the above information assessment team concludes:

1. There are no material discrepancies between project implementation and the project description provided in the registered PD/^{5/}.
2. The monitoring plan is implemented completely and the monitoring system (i.e., process and schedule for obtaining, recording, compiling, and analysing the monitored data and parameters) is appropriate.
3. There are no material discrepancies between the actual monitoring system, the monitoring plan set out in the project description, and the applied methodology/^{7/}.
4. The GHG emission reductions or removals generated by the project have not been included in an emissions trading program or any other mechanism that includes GHG allowance trading/^{23/}.

4.2 Safeguards and Stakeholder Engagement

4.2.1 Stakeholder Identification

The Project has undergone onsite audit/^{10/}, during current verification and it has been observed that there has been no change in the stakeholders since the time of validation.

Item	Evidence gathering activities, evidence checked, and assessment conclusion
Stakeholder identification	It has been observed and verified during onsite audit that the project activity is inline with the monitoring plan/ ^{5/} and there has been no new stakeholder identification done.
Legal or customary tenure/access rights	It has been observed and verified during onsite audit that the project activity is in line with the monitoring plan/^{5/} and there are no new legal or customary access right. CL 08 was raised and closed successfully during this verification, the details for which can be found in Appendix 3 of the report.
Stakeholder diversity and changes over time	It has been observed and verified during onsite audit that the project activity is in line with the monitoring plan/ ^{5/} and also stakeholders were interviewed during onsite audit (details of which are mentioned in section 2.3 of report) and it can be concluded that there is no change in stakeholder diversity over project lifetime till now.
Expected changes in well-being	It has been observed and verified during onsite audit that the project activity is in line with the monitoring plan/ ^{5/} and also stakeholders were interviewed during onsite audit (details of which are mentioned in section 2.3 of report) and it can be concluded that there is no expected change Wellbeing of stakeholder.
Location of stakeholders	It has been observed and verified during onsite audit that the project activity is in line with the monitoring plan/ ^{5/} and there is no change in the location of stakeholders.
Location of resources	It has been observed and verified during the onsite audit/ ^{10/} that the project activity is in line with the monitoring plan/ ^{5/} and no new stakeholder has been identified.

4.2.2 Stakeholder Consultation and Ongoing Communication

Item	Evidence gathering activities, evidence checked, and assessment conclusion
Ongoing consultation	During onsite audit/ ^{10/} , interviews with 3 local stakeholders were conducted, details of which can be found in section 2.3 and 2.4.

	During the interview it was concluded that PP has a direct communication channel via email and phone channels and stakeholders can also visit during office hours for any grievances. PD detailed Grievance procedure that is followed on-site in the monitoring report, the assessment team has verified the details mentioned and it is found to be in line with the PD/ ^{5/} .
Date(s) of stakeholder consultation	Stakeholder consultation was conducted on 22/12/2012 and 28/12/2012, it has been verified from the registered PD/ ^{5/} .
Communication of monitored results	Results of the original meeting were provided to the stakeholder and are also stored, during the current monitoring period there has been no new comments received.
Consultation records	During the current verification, one grievance was raised by members of the neighboring commune of Darou Khoudoss during a multi-stakeholder committee meeting on September 2, 2023. The grievance concerned the community investment plan and the perceived lack of widespread project benefits. It was verified through the Annual Environmental and Social Report/^{19/} that a response was sent to the Mayor of Darou Khoudoss to address the matter. The response outlined the terms and extent of the project's livelihood restoration plan, designed to benefit the impacted communities of Taiba N'Diaye. During the onsite audit/^{10/}, it was observed that stakeholders can raise grievances via email, phone, or in person during office hours, with site personnel available to assist. No grievances were reported that impacted the project's energy generation activities. Additionally, the PP submitted a detailed stakeholder grievance process, which was verified during the onsite audit/^{10/}.
Stakeholder input	During the onsite audit/ ^{10/} , interviews with 3 local stakeholders were conducted, details of which can be found in section 2.3 and 2.4. Based on the interview conducted, it has been concluded that all the procedures are implemented in line with registered monitoring plan/ ^{5/} and there is proper procedure in place for redressal of grievance received/ ^{25/} .

4.2.3 Free, Prior, and Informed Consent

Item	Evidence gathering activities, evidence checked, and assessment conclusion
------	--

Consent	During the current verification, an onsite audit/ ^{10/} was conducted and it has been verified that there was no conflict over the project resources. The same details were also verified from the previous verifications ^{11/} .
Outcome of FPIC discussion	There is no concern. Therefore, no FPIC required.

4.2.4 Grievance Redress Procedure

Item	Evidence gathering activities, evidence checked, and assessment conclusion
Grievance received and steps taken to resolve the grievance including the outcomes of the resolution	During the current verification, one grievance was raised by members of the neighboring commune of Darou Khoudoss during a multi-stakeholder committee meeting on September 2, 2023. The grievance concerned the community investment plan and the perceived lack of widespread project benefits. It was verified through the Annual Environmental and Social Report/^{19/} that a response was sent to the Mayor of Darou Khoudoss to address the matter. The response outlined the terms and extent of the project's livelihood restoration plan, designed to benefit the impacted communities of Taiba N'Diaye. During the onsite audit/^{10/}, it was observed that stakeholders can raise grievances via email, phone, or in person during office hours, with site personnel available to assist. No grievances were reported that impacted the project's energy generation activities. Additionally, the PP submitted a detailed stakeholder grievance process, which was verified during the onsite audit/^{10/}.
Grievance redress procedure	A formalized and official PETN Grievance Mechanism Procedure (GMP) is established to manage grievances arising from various project-related activities. The Grievance Mechanism Procedure was verified against the registered PD/ ^{5/} . It was observed during the onsite audit/ ^{10/} that stakeholders can raise grievances through email, phone, or in person during office hours, with site personnel available to assist. No comments or grievances from stakeholders have been observed during this monitoring period that impact the energy generation of the project activity.

4.2.5 Public Comments

Comments received	Actions taken by the project proponent	Evidence gathering activities, evidence checked, and assessment conclusion
One grievance was raised by members of the neighboring commune of Darou Khoudoss during a multi-stakeholder committee meeting on September 2, 2023. The grievance pertained to concerns from the members of the Darou Khoudoss Commune, who believe that the benefits of the project are not being shared equitably.	A letter of reply was sent to the Mayor of Darou Khoudoss, outlining the terms and extent of the project's livelihood restoration plan, as well as the Community Investment Plan (CIP), which is designed to benefit the impacted communities within Taiba N'Diaye.	During the onsite audit and through the Annual Environmental and Social Report/ ^{19/} , it was verified that a response was sent to the Mayor of Darou Khoudoss to address and resolve the grievance. Additionally, PETN will consider broadening its Community Investment Plan (CIP) to include more communes within the budget and to the extent that can be realistically implemented. It was further verified during the onsite audit/ ^{10/} that the Grievance Mechanism Procedure is active. Stakeholders can raise grievances via email, phone, or in person during office hours, with site personnel available to provide assistance.

4.2.6 Risks to Local Stakeholders and the Environment

4.2.6.1 Management Experience

Verified against the registered PD/^{5/}, the project was developed by Lekela, one of the largest African renewable energy companies, operating in Senegal, Egypt, and South Africa. Lekela specializes in power generation through renewable energy sources on utility, commercial, and industrial scales. The Taiba N'Diaye Wind Power management team includes professionals from various fields, with most of the team having been involved since the project's construction and commercial operation phases. This was verified during the onsite audit/^{10/} and through employment records provided by the PP/^{23/}.

4.2.6.2 Risk Assessment

Item	Evidence gathering activities, evidence checked, and assessment conclusion
Natural and human induced risks to	During the current verification, an onsite audit/ ^{10/} was conducted, interview with 3 of the stakeholders was conducted (details can be found in section 2.3 and 2.4 of the report), it has been observed that grievance

stakeholders' wellbeing	redressal procedure is in place, and there are no new comments received. Therefore, it has been concluded that there has been no risk to natural and human induced risks to stakeholders' wellbeing.
Risks to stakeholder participation	During the current verification, an onsite audit/ ^{10/} was conducted, interview with 3 of the stakeholders was conducted (details can be found in section 2.3 and 2.4 of the report), it has been observed that grievance redressal procedure is in place, and there are no new comments received. Therefore, it has been concluded that there has been no risk to participation.
Working conditions	During the current verification, an onsite audit/ ^{10/} was conducted, interview with 3 of the stakeholders was conducted (details can be found in section 2.3 and 2.4 of the report), both stakeholders interviewed received job due to development of project and it has been observed from the interview that working conditions are well balanced for people. Therefore, it can be concluded that working conditions are appropriate for the employees.
Safety of women and girls	During the current verification, an onsite audit/ ^{10/} was conducted, interview with 3 of the stakeholders was conducted (details can be found in section 2.3 and 2.4 of the report), and it was observed that project does not cause any harm to the society.
Safety of minority and marginalized groups, including children	During the current verification, an onsite audit/ ^{10/} was conducted, interview with 3 of the stakeholders was conducted (details can be found in section 2.3 and 2.4 of the report), and it was observed that project does not cause any harm to society.
Pollutants (air, noise, discharges to water, generation and release of hazardous materials and chemical pesticides and fertilizers)	The project activity is wind power project, hence a renewable project, hence does not cause any harm to the environment. However, PP has a monitoring system in place, it has been observed that all the environmental factors have been continuously monitored by Parc Eolien Taiba N'Diaye S.A.U. A detailed environment report (ESMP)/^{19/} has also been submitted by the PP, which has been verified by the assessment team. CL 09 has been raised and closed successfully during this verification.

4.2.7 Respect for Human Rights and Equity

4.2.7.1 Labor and Work

Item	Evidence gathering activities, evidence checked, and assessment conclusion
Discrimination	During the current verification, an onsite audit/ ¹⁰ / was conducted, interview with 3 of the stakeholders was conducted (details can be found in section 2.3 and 2.4 of the report), it was confirmed that there is no Discrimination and sexual harassment with any employee on site.
Sexual harassment	During the current verification, an onsite audit/ ¹⁰ / was conducted, interview with 3 of the stakeholders was conducted (details can be found in section 2.3 and 2.4 of the report), it was confirmed that there is no sexual harassment with any employee on site.
Gender equity in labor and work	During the current verification, an onsite audit/ ¹⁰ / was conducted, interview with 3 of the stakeholders was conducted (details can be found in section 2.3 and 2.4 of the report), it was confirmed that there was no gender discrimination on the project site..
Forced labor	During the current verification, an onsite audit/ ¹⁰ / was conducted, interview with 3 of the stakeholders was conducted (details can be found in section 2.3 and 2.4 of the report), it has been confirmed that there have been no cases of forced labor on the project site.
Child labor	During the current verification, an onsite audit/ ¹⁰ / was conducted, interview with 3 of the stakeholders was conducted (details can be found in section 2.3 and 2.4 of the report), it was confirmed that there was no child labor on the project site.
Human trafficking	During the current verification, an onsite audit/ ¹⁰ / was conducted, interview with 3 of the stakeholders was conducted (details can be found in section 2.3 and 2.4 of the report), it was confirmed that there was no Human trafficking on the project site.

4.2.7.2 Human Rights

Risks identified	Evidence gathering activities, evidence checked, and assessment conclusion
Human rights	During the current verification, an onsite audit/ ¹⁰ / was conducted, interview with 3 of the stakeholders was conducted (details can be found in section 2.3 and 2.4 of the report), it was confirmed that

there is no situation for violation towards human rights at the project site.

4.2.7.3 Indigenous Peoples and Cultural Heritage

Risks identified	Evidence gathering activities, evidence checked, and assessment conclusion
Preservation and protection of cultural heritage	During the current verification, an onsite audit/ ^{10/} was conducted, interview with 3 of the stakeholders was conducted (details can be found in section 2.3 and 2.4 of the report), it was confirmed that there was no harm to the cultural heritage at the project site. It was also confirmed by reviewing the feasibility report/ ^{28/} .

4.2.7.4 Property Rights

Risks identified	Evidence gathering activities, evidence checked, and assessment conclusion
Disputes over rights to territories and resources	During the current verification, an onsite audit/ ^{10/} was conducted, also a site visit was conducted during previous verification, it has been observed and confirmed that there has been no dispute over territories and resources project.
Respect for property rights	During the current verification, an onsite audit/ ^{10/} was conducted, and it was observed and confirmed that no disputes or issues related to property rights were raised CL 08 was raised and closed successfully during this verification

4.2.7.5 Benefit Sharing

Item	Evidence gathering activities, evidence checked, and assessment conclusion
Summary of the benefit sharing plan	During the current verification, an onsite audit/ ^{10/} was conducted. It was confirmed that both the PP and impacted stakeholders agreed on the financial compensation, and all compensation was made before the project launch.

Benefit sharing during the monitoring period	This was also discussed during the onsite audit/ ¹⁰ /, it has been observed that PP has lease agreements and the documents have been submitted to the VVB. This is not applicable during the current monitoring period as all compensation was made before the project launch.
--	---

4.2.8 Ecosystem Health

Item	Evidence gathering activities, evidence checked, and assessment conclusion
Impacts on biodiversity and ecosystems	It is a wind power project, Therefore, Parc Eolien Taiba N'Diaye S.A.U monitors the birds activity. As there was an onsite audit/ ¹⁰ / conducted during this verification, it was confirmed by proper assessment that no harm has been caused to the biodiversity.
Soil degradation and soil erosion	Not applicable as it is a wind power project. Hence, no risk identified.
Water consumption and stress	Not applicable as it is a wind power project. Hence, no risk identified.

4.2.8.1 Rare, Threatened, and Endangered species

Item	Evidence gathering activities, evidence checked, and assessment conclusion
Species or habitat	During the current verification, onsite audit/ ¹⁰ / was conducted and it was confirmed that there is no threat to species or habitat.
Areas needed for habitat connectivity	During the current verification, onsite audit/ ¹⁰ / was conducted and it was confirmed that there is no threat to Areas needed for habitat connectivity

	Evidence gathering activities, evidence checked, and assessment conclusion
Habitats for rare, threatened, and endangered species	During the current verification, onsite audit/ ¹⁰ / was conducted and it was confirmed that there is no threat to Rare, Threatened, and endangered species.

Areas for habitat connectivity	During the current verification, onsite audit ^{/10/} was conducted and it was confirmed that there is no threat to Areas needed for habitat connectivity
--------------------------------	---

4.2.8.2 Introduction of Species

In accordance with VCS standard, “Section 3.19.27(3) which does not apply to projects with a start date prior to 1 March 2024, pending further consultation”, therefore, the section is not applicable.

Species introduced	Evidence gathering activities, evidence checked, and assessment conclusion
Not applicable	

Existing invasive species	Evidence gathering activities, evidence checked, and assessment conclusion
Not applicable	

Evidence gathering activities, evidence checked, and assessment conclusion	
Invasive species	Not applicable

4.2.8.3 Ecosystem conversion

Item	Evidence gathering activities and evidence checked
Ecosystem conversion	Not applicable

4.3 Accuracy of Reduction and Removal Calculations

The assessment team has verified the values and formulas that are used for the calculation of emission reduction for this monitoring period from 01/08/2023 to 31/07/2024 (both days included). In details assessment of all these values can be found in section 4.4 of the report.

The equations and calculations used in the project report are in line with the applied methodology ‘ACM0002, V20.0’^{/7/}.

A detailed assessment of ex-ante values has been done in section 4.4 of the report.

The value used for the calculation of combine margin is found to be in line with the methodological tool 7, the value was validated during the validation of the project and is found to be in line with it since then as the project is undergoing 4th verification now.

The emission reductions are calculated as:

$$ER_y = BE_y - PE_y$$

Where,

ER_y = Total amount of GHG emission reductions

BE_y = Baseline emissions in year y (tCO_{2e} / y)

PE_y = Project emissions in year y (tCO₂ / y)

Now,

$$BE_y = EG_{PJ,y} \cdot EF_{grid,CM,y}$$

Where:

BE_y = Baseline emissions in year y (tCO₂ / y)

$EG_{PJ,y}$ = Quantity of net electricity generation that is produced and fed into the grid as a result of the implementation of the CDM project activity in year y (MWh / y)

$EF_{grid,CM,y}$ = Ex ante combined margin CO₂ emission factor for grid connected power generation in year y calculated using the CDM EF Tool (tCO₂ / MWh)

Now,

$$EG_{PJ,y} = EG_{facility,y}$$

$EG_{facility,y}$ = Quantity of net electricity generation supplied by the project plant/unit to the grid in year y (MWh / y)

For monitoring period from 01/08/2023 to 31/07/2024,

$$EG_{PJ,y} = 376,684 \text{ MWh}$$

$$EF_{grid,CM,y} = 0.573 \text{ tCO}_2\text{e/MWh}$$

Therefore, (Due to delay in calibration an error factor has been applied by the PP, details of which are mentioned in section 4.4 of this report.)

$$BE_y = 376,684 \cdot 0.573 = 215,839 \text{ tCO}_2\text{e}$$

$$PE_y = 0, \text{ in line with methodology}$$

$$\text{Now, as } ER_y = BE_y - PE_y$$

Therefore,

$$ER_y = 424,503 \text{ tCO}_2\text{e}$$

The assessment team has thoroughly verified the calculation done for the quantification of the emissions reduction for the project activity, under this monitoring period from 01/08/2023 to 31/07/2024 (both days included), it can be concluded that calculation done is in line with methodology^{/7/}, and accurate.

4.4 Quality of Evidence to Determine Reductions and Removals

The data and parameters recorded for the project are in compliance with the registered PD^{/5/} and the monitoring report. Assessment team has cross checked all the parameters that are used for the calculation of the emission reductions against the evidence such as invoices^{/14/}, monthly JMR reports^{/13/}, validation data sheet^{/26/} provided by the PP, it has been observed that all the sources provided are appropriate and can be accepted.

The monitoring done for all the parameters are inline with the applied methodology^{/7/}, thus, can be considered accurate and acceptable. Additionally, during this verification an onsite audit was done for the project activity on 12/11/2024^{/10/}, information was also cross checked by means of interview, therefore it has been concluded that mechanism is effective and reliable.

The meters comply with appropriate quality standards applicable to the used technology. The accuracy class of the meters installed for the project activity was verified through photographs^{/21/} and previous verification.

The data and parameters fixed (ex-ante):

S.No	Parameter	Value	Means of verification
1.	EF _{grid,CM,y} Combined margin CO ₂ emission factor in year y,	0.573 tCO ₂ / MWh	The value has been verified using the Reading Grid Data Calculations – Final validation ^{/26/} , registered PD ^{/5/} , validation report and previous verification. The value 0.573 tCO ₂ e/MWh is found to be appropriate.

The data and parameters monitored (ex-post):

Parameter: EG_{facility,y}, Total electricity produced by the Project Activity, including the electricity supplied to the grid and the electricity supplied to internal loads, in year y.

Means of verification	Measuring /Reading /Recording frequency	Continuous monitoring is done. This parameter is measured directly using electricity meters at the substation and reported to SENELEC by PETN on a monthly basis.
	Is measuring and reporting frequency in accordance with the monitoring plan and monitoring methodology? (Yes / No)	Yes, the monitoring frequency is in line with the monitoring plan ^{/5/} .
	Monitoring equipment	The energy meters of accuracy class 0.2s are installed ^{/21/} (details can be found in table below under section “calibration details”).
	Is accuracy of the monitoring equipment as stated in the monitoring plan? If the monitoring plan does not specify the accuracy of the monitoring equipment, does the accuracy of the monitoring equipment comply with local/national standards, or as per the manufacturer’s specification?	All the energy meters used are of accuracy class 0.2s. The accuracy of the monitoring equipment aligns with the requirements of the monitoring plan as outlined in the registered PD ^{/5/}
	Is the calibration of measuring equipment carried out by an accredited person or institution?	Yes, the calibration was performed by EnergieExpress which is a third-party company performing calibration and verification of meters in accordance with national legislation and intra-community regulations.

	Is(are) calibration(s) valid for the whole reporting period?	The meters are calibrated annually, as specified in the procedures outlined in the PD/^{5/}. However, during this monitoring period, a delay of 14 days in calibration was noted at the SENELEC substation. To address this, the PP applied an error factor of 0.2% to the affected values, ensuring the accuracy of the reported data despite the delay. This error factor is in line with the Application of Materiality, paragraph 304 of CDM Validation and Verification Standard (CDM-EB93-A08-STAN version 3.0) CL 13 was raised and closed successfully.
	How were the values in the monitoring report verified?	The values of the monitoring report were verified using invoices/^{14/} and JMR report generated monthly/^{13/}. Value obtained = 376,684 MWh
	If applicable, has the reported data been cross checked with other available data?	Yes, the report values have been crosschecked with invoices/^{14/} and JMR report generated monthly/^{13/}. CL 12 was raised and closed successfully.
	Does the data management ensure correct transfer of data and reporting of emission reductions and are necessary QA/QC processes in place?	Yes, the data ensure correct transfer of data and reporting of emission reduction management. QA/QC processes are in place.

	In case project participants have temporarily not monitored the parameter, has either deviation?	The meters are calibrated annually, as specified in the procedures outlined in the PD^{/5/}. However, during this monitoring period, a delay of 14 days in calibration was noted at the SENELEC substation. To address this, the PP applied an error factor of 0.2% to the affected values, ensuring the accuracy of the reported data despite the delay. This error factor is in line with the Application of Materiality, paragraph 304 of CDM Validation and Verification Standard (CDM-EB93-A08-STAN version 3.0) CL 13 was raised and closed successfully.
Findings	CL 12 and CL 13 were raised and closed successfully.	
Conclusion	The assessment team concluded that the parameter has been monitored continuously and it is in line with the registered monitored plan^{/5/} and applied methodology^{/7/}. Since 100% of data has been monitored and verified, the verification team can ascertain that the values used for the calculation of emission reduction are free from material errors.	

Calibration of the meters:

Meter Model	Serial No.	Accuracy class	Date of previous calibration	Date of latest calibration	Remark
Itron SL7000 (Main Meter)	84406427	0.2s	07/12/2022 valid until 06/12/2023	20/12/2023 valid until 21/12/2024	

ltron SL7000 (Back-up Meter)	84406426	0.2s	07/12/2022 valid until 06/12/2023	20/12/2023 valid until 21/12/2024	There was a 14-day delay in calibrating the meter, from the last valid calibration on 06/12/2023 to the next calibration on 20/12/2023. To ensure a conservative approach, the PP applied the maximum permissible error factor of $\pm 0.2\%$ to the net electricity supplied to the grid for December 2023, consistent with the meters' specified accuracy limits of 0.2% (0.2s), even though the delay lasted only 14 days. This approach aligns with the CDM Validation and Verification Standard (paragraph 304, CDM-EB93-A08-STAN, version 3.0).
---------------------------------------	----------	------	---	---	---

The meters are required to be calibrated annually, as specified in the PD^{/5/}. However, during this monitoring period, a 14-day calibration delay was observed in December 2023. To ensure a conservative approach, the PP applied the maximum permissible error factor of $\pm 0.2\%$ to the net electricity supplied to the grid for December 2023, consistent with the meters' specified accuracy limits of 0.2% (0.2s), even though the delay lasted only 14 days. This error factor and approach align with the CDM Validation and Verification Standard (paragraph 304, CDM-EB93-A08-STAN, version 3.0). Furthermore, this error factor and approach has been consistently applied in previous verifications^{/11/} whenever meter calibration delays were observed.

CL 12 and 13 were raised and closed successfully during this verification.

In accordance with the above details the verification team confirms that:

- A complete set of data for the monitoring period was available for the monitoring period and the verification of each monitoring parameter is elaborated under this of this report.
- The complete monitoring data is also presented in the corresponding ER sheet and final version of the monitoring report.
- The information provided in the monitoring report was cross checked with other sources, wherever appropriate and available, and such information is also included under this of this report.
- The calculations of baseline emissions as presented in the corresponding ER sheet of final Monitoring Report were checked and found to be consistent with the formulae and methods described in the registered monitoring plan^{/5/} and the applied methodology^{/7/}.
- All assumptions used in the emission calculations were found appropriate and therefore accepted.
- Appropriate emission factors and other reference values have been correctly applied.

CL03 and CL04 were raised, which was closed successfully, Details for which can be found in Appendix 3 of the report.

4.5 Non-Permanence Risk Analysis

The project activity is a wind power project. Therefore, it is not applicable.

5 VERIFICATION OPINION

5.1 Verification Summary

The project activity VCS – 2588, “Taiba N’ Diaye Wind Power” has undergone 4th verification with monitoring period from 01/08/2023 to 31/07/2024 (including both days). Parc Eolien Taiba N’Diaye S.A.U. is responsible for the collection, analysis, aggregation, preparation (conversion factors, assumptions, methodology, calculations) and presentation of activities and related GHG data in its public disclosures (including but not limited to monitoring report, emission reduction calculation sheet, submitted documents/ emails/ communications). Our responsibility of performing this work is to the management of Parc Eolien Taiba N’Diaye S.A.U and in accordance with terms of reference agreed with the Parc Eolien Taiba N’Diaye S.A.U in the master service agreement. The verification engagement is based on the assumption that the GHG data provided to us is complete, sufficient, true and free from material misstatements.

SustainCERT applies its own quality management system and compliance policies for quality control, in accordance with ISO/IEC 17029:2019 – Conformity Assessment Requirements for Validation and Verification bodies providing environmental information (ISO 14065:2020) and greenhouse gas audit (ISO 14064-3:2019) and certifications, and accordingly maintains a comprehensive system of quality control including documented policies and procedures regarding compliance with ethical requirements, professional standards and applicable legal & regulatory requirements.

We have complied with the VCS standard^{/1/} and other requirements mentioned, during the verification engagement and maintained independence. SustainCERT was not involved in the preparation of any statements or reports or data except for this Verification Statement and Report. SustainCERT maintains complete impartiality toward stakeholders interviewed during the verification process. SustainCERT did not provide any services to Parc Eolien Taiba N'Diaye S.A.U. and its subsidiaries and consultants in the scope of verification that could compromise the independence or impartiality of our work. SustainCERT disclaims any liability or co-responsibility for any decision a person or an entity would make based on this verification statement towards the issuance and utilization of VCU's hereby verified and certified. The verification was carried out during Oct 2024 – Dec 2024 by a team of qualified GHG auditors.

5.2 Verification Conclusion

The Verification of the project titled “Taiba N’ Diaye Wind Power” VCS ID – 2588, have been undertaken by SustainCERT, as requested by Parc Eolien Taiba N'Diaye S.A.U, project proponent for the project, monitoring period 01/08/2023 to 31/07/2024 (including both days) as reported in latest submitted version of monitoring report The project activity is implemented in accordance with the registered monitored plan in PD v2.1^{/5/}. It is our responsibility to express an independent verification statement on the reported GHG emission reductions from the project activity.

SustainCERT Verification approach was based on understanding the risk associated with reporting of GHG emission data and the controls in place to mitigate these. SustainCERT planned and performed the verification by obtaining evidence and other information and explanations that SustainCERT considered necessary to give reasonable assurance that reported GHG emission reductions are fairly stated.

In our opinion, the GHG emissions reductions reported for the project activity for the period 01/08/2023 to 31/07/2024 (including both days) are fairly stated in the latest submitted version of project monitoring report. The GHG emission reductions were calculated correctly based on the approved baseline and monitoring methodology ACM0002 Version 20.0 and the monitoring plan contained in the PD^{/5/}.

Verification period: From 01/08/2023 to 31/07/2024

Verified GHG emission reductions and carbon dioxide removals in the above verification period:

For projects that are not required to assess permanence risk, use the following table:

Vintage period	Baseline emissions (tCO ₂ e)	Project emissions (tCO ₂ e)	Leakage emissions (tCO ₂ e)	Reduction VCU (tCO ₂ e)	Removal VCU (tCO ₂ e)	Total VCUs (tCO ₂ e)
01/08/2023 to 31/12/2023	70,942	0	0	70,942	-	70,942
01/01/2024 to 31/07/2024	144,897	0	0	144,897		144,897
Total	215,839	0	0	215,839	-	215,839

5.3 Ex-ante vs Ex-post ERR Comparison

For all projects, state the estimated ex-ante GHG emission reductions and carbon dioxide removals and the achieved reductions and removals for this monitoring period. Report the percentage difference and justify the difference. The quantities of reductions and removals are the total quantities before any deductions for buffer credits.

Vintage period	Ex-ante estimated reductions/removals	Achieved reductions/removals	Percent difference	Explanation for the difference
01/08/2023 to 31/12/2023	107,390	70,942	-34%	The difference between the achieved and estimated energy is due to variations in wind speed. The Monthly Ambient Environmental Condition Report for this monitoring period shows that from August to December, the winds were relatively slow, while from January to May, the winds were stronger. Winds slowed again in June and July. During the onsite audit, it was cross-checked by interviewing the PP and its representatives that all turbines are functional.
01/01/2024 to 31/07/2024	150,346	144,897	-4%	
Total	257,735	215,839	-16	

APPENDIX 1: COMMERCIALLY SENSITIVE INFORMATION

NA

Section	Information	Justification	Assessment method and conclusion
<u>NA</u>			

APPENDIX 2: TABLE OF REFERENCES

S. No	Document Title	Version	Date
1.	VCS standard <i>VCS Program Details - Verra</i>	4.7	21/03/2024
2.	VCS guidelines https://verra.org/wp-content/uploads/2023/08/VCS-Program-Guide-v4.4.pdf	4.4	29/08/2023
3.	Validation and Verification Manual https://verra.org/wp-content/uploads/2018/03/VCS_Validation_Verification_Manual_v3.2.pdf	3.2	19/10/2016
4.	VCS Project Webpage, VCS ID - 2588 https://registry.verra.org/app/projectDetail/VCS/2588	-	-
5.	Joint Project Description and Monitoring Report https://registry.verra.org/app/projectDetail/VCS/2588	2.1	14/01/2022
6.	Joint Validation and Verification report (09/12/2019 – 31/07/2021) https://registry.verra.org/app/projectDetail/VCS/2588	2.1	15/01/2022
7.	Applied Methodology “ACM0002- Grid connected electricity generation from renewable sources” https://cdm.unfccc.int/UserManagement/FileStorage/AG07ZJQ3EXD42LT5YV9HR16M8KINPO	20.0	-
8.	Monitoring report (01/08/2023 to 31/07/2024)	5.0	07/03/2025
9.	Emission reduction calculation sheet		Corresponding to MR
10.	Onsite audit	-	12/11/2024
11.	2 nd Verification Report (01/08/2021 to 31/07/2022) 3 rd Verification Report (01/08/2022 to 31/07/2023)	- 01	24/02/2023 22/11/2023
12.	2 nd Monitoring report (01/08/2021 to 31/07/2022) 3 rd Monitoring report (01/08/2022 to 31/07/2023)	4 3	27/02/2023 06/11/2023
13.	Taiba N’ Diaye Wind Power Joint Meter Reading (JMR) report (monthly for entire monitoring period)	-	01/01/2023-31/07/2024
14.	Parc Eolien Taiba Ndiaye S.A.U invoices (monthly for entire monitoring period)	-	01/01/2023-31/07/2024

15.	Energy Consumed Senelec invoices (monthly for entire monitoring period)	-	01/01/2023-31/07/2024
16.	Vestas Monthly maintenance report (monthly for entire monitoring period)		01/01/2023-31/07/2024
17.	Meter Calibration certificates	-	07/12/2022 20/12/2023
18.	No Double counting declaration	-	26/11/2024
19.	Annual Environmental and Social Report		01/01/2023-31/12/2023
20.	Lease Agreements	-	
21.	Photographic evidence of meters		
22.	Contract Agreement between AERA Group and PETN	-	26/02/2021
23.	Employee List	-	-
24.	Updated Environmental and Social Impact Study for the Taiba N' Diaye Wind Farm project	-	02/2016
25.	Commissioning Certificates (Phase I, II, and III)		09/12/2019 06/11/2020 30/06/2021

APPENDIX 3: PROJECT FINDINGS

Rule	Assessment Question	Findings/Comments (CL 1)	Developer Response
VCS Standard, v4.7	Connection Details	Section 1.1 of MR: The PP shall provide clarification on the connection details of the power plant, specifically identifying the substation to which it is connected, along with the technical specifications of the transmission line. PP is requested to include this information accurately in the MR.	The project doesn't require any transmission line as the Tobene substation acts as the project substation as well as the grid connection point. Information provided in the MR section 1.1
	Rd 2	The PP revised section 1.1 of the MR to reflect the details of the transmission lines. Comment closed.	

Rule	Assessment Question	Findings/Comments (CL 2)	Developer Response
VCS Standard, v4.7	Entities Involved in the Project	Section 1.5 of MR: The PP shall provide the agreement between Aera Group and SENELEC for the project. Additionally, the PP must clarify the ownership of the carbon credits generated by the project.	See Aera-Senelec contract. As per contract PETN is the owner of the project activity.
	Rd 2	The PP submitted the agreement between Aera Group and SENELEC. The MR explicitly states that Aera Group serves as the Carbon Consultant and offtaker for the project activity, aligning with the agreement. Comment closed.	

Rule	Assessment Question	Findings/Comments (CL 3)	Developer Response
VCS Standard, v4.7	Start date of the project	Section 1.6 of MR: In accordance with VCS standard, v4.7, "The project start date of a non-AFOLU project is the date on which the project began generating GHG emission reductions or carbon dioxide removals." PP shall provide the evidence of the start date of the project in line to the VCS requirement.	See commissioning certificates (I, II, III)
	Rd 2	PP has submitted the commissioning certificates I, II, and III and the dates in the commissioning certificates are consistent with the MR. Comment closed.	

Rule	Assessment Question	Findings/Comments (CL 4)	Developer Response
VCS Standard, v4.5 Monitoring report template	Double counting	Section 1.10 of MR: In order to avoid the double counting of the credits, PP shall provide a declaration stating the credits generated under this monitoring period will not be used with any other GHG programs and environmental credits.	See PP no double counting declaration
	Rd 2	A sworn statement has been submitted by the PP confirming that credits generated during this monitoring period will not be used with any other GHG programs or environmental credits. Comment closed.	

Rule	Assessment Question	Findings/Comments (CL 5)	Developer Response
VCS Standard, v4.7 Monitoring report template	Current project contribution and contributions over the project lifetime	Section 1.12 of MR: SDG 8: The PP shall provide evidence regarding employment generated by the project during this monitoring period.	Se employees list
	Rd 2	The PP submitted the employee list, confirming that one person was employed during this monitoring period. This information aligns with the MR and the employment records. However, the PP must clarify the total number of jobs created over the project's lifetime, as the MR reports 23 jobs, whereas the employee records list 27 names. Additionally, the PP is requested to specify the number of permanent and temporary jobs created by the project activity. Finding remains open.	Please see "entry date" in the employees list, you can see that there is only one person hired in 2024 (02/01/2024). The total number of employees have been revised in the MR (27).
	Rd 3	PP updated the MR to accurately reflect the total number of jobs generated by the project. This information was cross-checked against the provided employee list. A total of 27 jobs were created by the project up until the end of this monitoring period, with one individual employed during the current monitoring period and the remaining positions filled in previous periods. Comment closed.	

Rule	Assessment Question	Findings/Comments (CL 6)	Developer Response
VCS Standard, v4.7 Monitoring report template	Public Comments	Section 2.1.1 of MR: Expected changes in well-being: PP shall provide evidence for the construction of a school, improvement of waste management and road quality as reported in the MR.	See ESMP report 2023
	Rd 2	PP has submitted its Annual Environmental and Social Report for January – December 2023 (ESMP 2023) detailing the activities it has performed for the well-being of the local stakeholder. Comment closed.	

Rule	Assessment Question	Findings/Comments (CL 7)	Developer Response
VCS Standard, v4.7 Monitoring report template	Public Comments	Section 2.1.2 of MR: In line with VCS standard 3.18.3 and 3.18.4, PP shall demonstrate the procedure for ongoing communication with local stakeholder. PP shall provide the procedure for ongoing communication with local stakeholders. PP shall provide evidence of the existence of the grievance mechanism in place (photo of the mail box, dedicate hotline)	No mail box. Phone number & email were added
	Rd 2	The PP has updated the MR to include details of the grievance mechanism, such as a dedicated hotline and email. Stakeholders	

Rule	Assessment Question	Findings/Comments (CL 7)	Developer Response
		without telephone or internet access are advised to submit grievances through designated representatives. The ESMP 2023 report demonstrates ongoing communication between local stakeholders and the project proponents. Comment closed.	

Rule	Assessment Question	Findings/Comments (CL 8)	Developer Response
VCS Standard, v4.7 Monitoring report template	Public Comments	Section 2.1.5 of MR 1. The PP shall submit evidence of all public comments received during the entire monitoring period. Additionally, the PP shall provide proof of the existence of a Grievance Mechanism that is visible and easily accessible to local stakeholders. 2. The PP is to submit evidence regarding ownership or lease agreement for the land where the wind turbine and underground transmission line is located. The PP shall submit the ownership title or lease agreement, specifying the duration for which the project can use the land for the transmission line. 3. PP shall submit the ESMP reinforcement and communication plan addressing the risk of accidents for people living in the area where wind turbines and underground cables are installed. 4. PP shall submit PGES to address risks of accidents and pollutants such as air, noise,	1. See ESMP report 2023 mentioning grievances received. Grievance forms are available at the work area level. The grievance register is in electronic format (see grievance register) 2. They have leases for the land where the power plant is located. With Senelec for the substation and with the state of Senegal for the turbines and the roads.(See lease agreements) 3. People were displaced in order to built and operates the power plant as per rehabilitation plan. Thus, this is not applicable

Rule	Assessment Question	Findings/Comments (CL 8)	Developer Response
		generation of waste, and release of hazardous materials and chemical pesticides and fertilizers.	4. see HSE statistics in ESMP report.
	Rd 2	1. PP has submitted the ESMP 2023 report, which includes comments, feedback, and grievances from that year. PP shall clarify if any additional comments or feedback were received up to July 31, 2024 (the end of the monitoring period). If so, PP should explain how they were addressed. Finding remains open. 2. PP has submitted the lease agreements for where the wind turbine and underground transmission line is located. This has also been verified from the validation report. Comment closed. 3. The ESMP reinforcement and communication plan was part of the validation and risks of accidents for people living in the area where wind turbines and underground cables are installed were properly addressed during the validation stage of the project. Comment closed. 4. PP submitted the ESMP 2023 report which shows the environmental incidents it has monitored during the monitoring period. Comment closed.	Revised in the MR. There was no comment received during 2024.
	Rd 3	1. The PP updated the MR to mention that no additional comments, feedback, and grievances during 2024. This was verified on-site during the site visit. Comment closed.	

Rule	Assessment Question	Findings/Comments (CL 9)	Developer Response
VCS Standard, v4.7 Monitoring report template	Ecosystem Health	Section 2.4 of MR: 1. PP shall provide evidence proving that the position and orientation of the wind turbines are parallel to the migratory axes, avoiding negative effects on migrating birds. 2. PP shall provide maintenance, and operational works done on the wind power plant that are outside the breeding periods of local species. 3. In addition to the wind power plant, the PP must clarify the impact of the power plant's transmission lines on soil degradation and soil erosion.	1. . The park is not located in a bird migration area. However, as mentioned in ESMP report, a “Avifauna expert continue the monthly monitoring of bird and bat flows in the Taiba Ndiaye wind farm project area. This involves monitoring birds at the 05 VP scattered throughout the project area so as to be able to observe birds and count them on the right-of-way of the turbine lines” 2. For the shutdown and maintenance report, this is a confidential document that Vestas as a service provider keeps confidential. However, the on-site verification clearly showed that there was no impact following interventions on either the species or the electricity production in general. 3. There is no transmission line at project’s site. See ESIA report “The low level of soil compaction in the project area, with its relatively gentle slopes, confirms that these soils are resistant to water erosion. In addition, the relatively extensive and permanent vegetation cover in many places

Rule	Assessment Question	Findings/Comments (CL 9)	Developer Response
			means that wind erosion is low, especially in the southern part of the project area.” (p.99)
	Rd 2	1. The ESMP 2023 report provides details on the monitoring of bird and bat flows within the project area. Monthly monitoring is conducted by an Avifauna expert to address any potential bird and bat mortality. Comment closed. 2. The PP submitted the confidential maintenance report covering the entire monitoring period. The report details the duration of each maintenance activity along with its category—environmental, utility, unscheduled, or manufacturer-induced. Additionally, the report specifies the amount of lost production associated with each maintenance activity. Ambient environmental conditions, such as wind speed, affecting the generation was also included in the report. Comment closed. 3. The PP submitted the Environmental and Social Impact Study (ESIA) for the Taiba N Diaye Wind Farm Project, stating that the power plant’s transmission line does not pose a threat to soil degradation or erosion. Comment closed.	

Rule	Assessment Question	Findings/Comments (CL 10)	Developer Response
VCS Standard, v4.7 Monitoring report template	Implementation Status of the Project Activity	Section 3.1 of MR The PP shall provide the records of scheduled maintenance, forced stoppages, and breakdown details of the power plant.	As explained above, the shutdown and maintenance report, is a confidential document that Vestas as a service provider keeps confidential. However, the on-site verification clearly showed that there was no impact following interventions on the electricity production (this can also be verified through the monthly production data provided in invoices, which shown that the plant operated continuously).
	Rd 2	The PP submitted the confidential maintenance report covering the entire monitoring period. The report details the duration of each maintenance activity along with its category—environmental, utility, unscheduled, or manufacturer-induced. Additionally, the report specifies the amount of lost production associated with each maintenance activity. Ambient environmental conditions, such as wind speed, affecting the generation was also included in the report. Comment closed.	

Rule	Assessment Question	Findings/Comments (CL 11)	Developer Response															
VCS Standard, v4.7 Monitoring report template	Electricity Generated and Supplied	Section 4.2 of MR: - The PP shall provide the revenue meter reading used for the calculation EGfacility,y as well as the invoices raised. - PP shall provide the evidence where the values of columns Check Prod (Column B) and Check Cons (Column E) were obtained.	- See production and consumption invoices. - All the values are coming from the joint meters readings signed by PETN & SENELEC, here is an example (for July 2024):  Relevé des indices des compteurs du Parc Eolien Taiba Ndiaye En présence de SENELEC et PETN un relevé a été réalisé au niveau des compteurs de facturation du poste Taiba. Les indices suivants ont été relevés à la date du 31/07/2024, à minuit. <table><tr><th></th><th>Compteur n°844064227</th><th>Compteur 844064228</th></tr><tr><td>Energie Active Import Totale</td><td>1671890</td><td>1671509</td></tr><tr><td>Energie Active Export Totale</td><td>5101</td><td>5102</td></tr><tr><td>Energie Réactive Import Totale</td><td>42903</td><td>42891</td></tr><tr><td>Energie Réactive Export Totale</td><td>1626749</td><td>1626419</td></tr></table>		Compteur n°844064227	Compteur 844064228	Energie Active Import Totale	1671890	1671509	Energie Active Export Totale	5101	5102	Energie Réactive Import Totale	42903	42891	Energie Réactive Export Totale	1626749	1626419
		Compteur n°844064227	Compteur 844064228															
Energie Active Import Totale	1671890	1671509																
Energie Active Export Totale	5101	5102																
Energie Réactive Import Totale	42903	42891																
Energie Réactive Export Totale	1626749	1626419																
Rd 2	- PP submitted scanned copies of the revenue meter readings used to calculate EGfacility,y, along with the related invoices. The submitted data matches the ER sheet. Comment closed. - The submitted files also include values for the "Check Prod" and "Check Cons" columns from the revenue meter readings. These values are consistent with the ER sheet. Comment closed.																	

Rule	Assessment Question	Findings/Comments (CL 12)	Developer Response
VCS Standard, v4.7 Monitoring report template	Calibration details	Section 4.2 of MR: - PP shall provide the calibration certificates / tests for all the meters installed during the current monitoring period. Section 4.3 of MR: - In Table 4 of MR: PP shall clarify and specify which of the two meters used in the PP is the main meter and the back-up meter.	.1. See calibration certificates 2022 & 2023. 2. Information already provided : Serial ID: 84406427 (main) - 84406426 (back-up) .
	Rd 2	- PP submitted the calibration certificates for this monitoring period. The details in the certificates align with the dates reported in the MR. Comment closed. - PP updated the MR to specify the main meter and the backup meter. This information is consistent with the submitted calibration certificates. Comment closed.	

Rule	Assessment Question	Findings/Comments (CL 13)	Developer Response
VCS Standard, v4.7 Monitoring report template	Emission Reduction Calculation	Emission Reduction File: PP shall clarify why the calculation of Net EG for December 2023 (CELL H26) is not consistent with other months in the ER sheet.	Because as per verification reports 2022 & 2023, previous meters' calibration was done on 7 december 2022 and last verification was done on 20 december 2023. Thus, to remain conservative an error factor based on meters' precision (0.2s) was applied due to the delay in verification (19 days of delay).
	Rd 2	PP shall clarify how the 19-day delay was calculated. Based on the previous verification, the calibration was valid until 06/12/2023, while the subsequent calibration occurred on 20/12/2023. This period spans only 14 days. To maintain conservativeness, the maximum permissible error of the instrument (0.2%) was applied in accordance with the CDM validation and verification standard.	Yes just typing error
	Rd 3	PP clarified that the 19 days delay is just in Round 1 response is a clerical error, and the correct date between the calibration of the meter is just 14 days. Comment closed.	

Rule	Assessment Question	Findings/Comments (CAR 1)	Developer Response																									
VCS Standard, v4.7 Monitoring report template	VCS Monitoring Report Template 5.4 GHG Emission Reductions and Carbon Dioxide Removals	With reference of the instruction of Monitoring Report v4.4 template, the tables in section 5.4 is to provide summary for the project crediting period and not just for the claimed monitoring period i.e., MP01 – MP 04. PP is requested to add data for MP1 to MP3 in the table.	Revised in MR. But for the Ex-Ante / Ex-post comparison table it is clearly stated that it is only for the MP: <i>For all projects, state the estimated ex-ante GHG emission reductions and carbon dioxide removals and the achieved reductions and removals for the monitoring period. Report the percentage difference and explain any difference. The quantities of reductions and removals are the total quantities before any deductions for buffer credits.</i> <table><tr><th>Vintage period</th><th>Ex ante estimated reductions/removals</th><th>Achieved reductions/removals</th><th>Percent difference</th><th>Explanation for the difference</th></tr><tr><td>DD-MMM-YYYY to 31-Dec-YYYY</td><td></td><td></td><td></td><td></td></tr><tr><td>01-Jan-YYYY to 31-Dec-YYYY</td><td></td><td></td><td></td><td></td></tr><tr><td>...</td><td></td><td></td><td></td><td></td></tr><tr><td>01-Jan-YYYY to DD-MMM-YYYY</td><td></td><td></td><td></td><td></td></tr></table>	Vintage period	Ex ante estimated reductions/removals	Achieved reductions/removals	Percent difference	Explanation for the difference	DD-MMM-YYYY to 31-Dec-YYYY					01-Jan-YYYY to 31-Dec-YYYY					...					01-Jan-YYYY to DD-MMM-YYYY				
	Vintage period	Ex ante estimated reductions/removals	Achieved reductions/removals	Percent difference	Explanation for the difference																							
DD-MMM-YYYY to 31-Dec-YYYY																												
01-Jan-YYYY to 31-Dec-YYYY																												
...																												
01-Jan-YYYY to DD-MMM-YYYY																												
	Rd 2	The PP updated the MR to include a summary of the project crediting period in Table 1 of Section 5.4. No revisions were made to Table 2 of Section 5.4, as it aligns with the monitoring template. Comment closed.																										

Rule	Assessment Question	Findings/Comments (CAR 2)	Developer Response
VCS Standard, v4.7 Monitoring	VCS Monitoring Report Template	Following Monitoring Template v4.4 instruction under section 1.12, “Evidence of the project’s SD contributions shall be provided as appendices to this report”. In the monitoring report; no appendices are provided.	Evidence for SDG 8 is provided. Other SDGs are based on calculation and not a single document.

Rule	Assessment Question	Findings/Comments (CAR 2)	Developer Response
report template	Rd 2	PP updated the MR to include evidence for SDG 8 in the Appendix section. Additional evidence for other SDGs has been submitted to the VVB for verification. Comment closed.	

APPENDIX 4: COMPETENCY STATEMENT

COMPETENCY STATEMENT	
Name	Randulph Morales
Years of Experience	1+
QUALIFYING ROLES	
Team Leader	No
Auditor	Yes
Country Expert	Yes, CE Region 1 (English) / CE Region 6 (Filipino)
Technical Expert	No
Financial Expert	No
Independent Reviewer	No
APPROVAL	
Approved by	Head of Quality and Compliance, SustainCERT
Date	04/08/2023

COMPETENCY STATEMENT	
Name	Namory Diakhate
Years of Experience	-
QUALIFYING ROLES	
Team Leader	No
Auditor	Yes
Country Expert	Yes, CE Region 1 (English) / CE Region 6 (Wolof)
Technical Expert	Yes (1.1, 1.2)
Financial Expert	No

Independent Reviewer	No
APPROVAL	
Approved by	Head of Quality and Compliance, SustainCERT
Date	07/10/2024

COMPETENCY STATEMENT	
Name	Muskan Chawla
Years of Experience	2+
QUALIFYING ROLES	
Team Leader	Yes
Auditor	Yes
Country Expert	Yes, CE Region 1 (English) / CE Region 6 (Hindi)
Technical Expert	Yes (1.1, 1.2)
Financial Expert	No
Independent Reviewer	Yes
APPROVAL	
Approved by	Head of Quality and Compliance, SustainCERT
Date	05/09/2023

COMPETENCY STATEMENT	
Name	Indrapal Parmar
Years of Experience	15+
QUALIFYING ROLES	
Team Leader	Yes
Auditor	Yes
Country Expert	Yes, CE region 1 (English) / CE Region 6 (Hindi)

Technical Expert	Yes (1.1, 1.2, 1.6)
Financial Expert	Yes
Independent Reviewer	Yes
APPROVAL	
Approved by	Head of Quality and Compliance, SustainCERT
Date	15/07/2022

APPENDIX 5: ABBREVIATIONS

CAR	Corrective Action Request
CL	Clarification Request
CO ₂	Carbon dioxide
FAR	Forward Action Request
GHG	Green House Gas
MR	Monitoring report
MWh	Mega watt hour
PD	Project description
PETN	Parc Eolian Taiba N'Diaye
PP	Project Proponent
SENELEC	Société nationale d'électricité du Sénégal
UNFCCC	United Nation Framework Convention on Climate Change
VCS	Verified Carbon standard
WPP	Wind Power Project