



VCS VERIFICATION REPORT

JILIN TONGYU TONGFA WIND POWER PROJECT

(VCS PROJECT ID: 276)



Document Prepared By

Shenzhen CTI International Certification Co., Ltd

Project Title	Jilin Tongyu Tongfa Wind Power Project
Version	1.1
Report ID	CTINB-2022-0519-1

Report Title	VCS Verification Report of Jilin Tongyu Tongfa Wind Power Project
Client	Longyuan (Beijing) Carbon Asset Management Technology Co., Ltd.
Pages	38
Date of Issue	14-Jun-2022
Prepared By	Shenzhen CTI International Certification Co., Ltd
Contact	Address: F8-A CTI Building, No.4 LiuXianSan Road, Xin'an Street, Bao'an District, 518101, Shen Zhen, China Tel: +86 10 65580012 Email: linshunrong@cti-cert.com Website: http://www.cti-cert.org
Approved By	Zhou Lu 
Work Carried Out By	Team Leader: Zhang Lei Team Member: Zhang Wenting Technical Reviewer: Lin Shunrong

Summary:

Shenzhen CTI International Certification Co., Ltd (CTI) has performed the verification of the emission reductions reported for the project activity "Jilin Tongyu Tongfa Wind Power Project" (VCS Project ID:276) for the monitoring period 25/04/2012-05/12/2017 within the 1st VCS crediting period 06/12/2007-05/12/2017, to review and determine the monitored reductions in GHG emissions that have occurred as a result of the project activity. These emission reductions are claimed as Verified Carbon Units (VCU) under the VCS Standard Version 4.2.

The verification was performed on the basis of VCS Standard Version 4.2 for the VCS projects, as well as criteria given to provide for consistent project operations, monitoring and reporting. The verification was conducted by means of document review, follow-up interviews and site inspections, and the resolution of outstanding issues. The verification team identified two CLs, no CAR and no FAR were raised in this monitoring period.

In CTI's opinion, the GHG emission reductions reported for the project in the monitoring report (version 02 dated 07/06/2022) are fairly stated. The GHG emission reductions of the period from 25/04/2012-

05/12/2017 within the 1st VCS crediting period were calculated correctly on the basis of approved methodology ACM0002 “Consolidated baseline methodology for grid-connected electricity generation from renewable sources” (version 6), the monitoring plan contained in the registered VCS PD (i.e. registered CDM PDD version 4.1 dated 20/01/2009) for the 1st VCS crediting period 06/12/2007-05/12/2017.

CTI does not assume any responsibility towards the issuance and utilization of the VCUs hereby verified and certified. Request for issuance of VCUs shall be made by the project proponent to an approved VCS Program Registry based on the requirements set out under the most recent version of the VCS Program Guidelines clause on VCS Registration.

The verification of reported emission reductions is based on the information made available to CTI and the engagement conditions detailed in this report. CTI cannot be held liable by any party for decisions made or not made based on this report.

Hence, CTI is able to certify that the emission reductions from the “Jilin Tongyu Tongfa Wind Power Project” during this monitoring period from 25/04/2012-05/12/2017 amount to 716,004 tCO₂e.

CONTENTS

1	Introduction	6
1.1	Objective	6
1.2	Scope and Criteria	6
1.3	Level of Assurance	7
1.4	Summary Description of the Project	7
2	Verification Process	8
2.1	Method and Criteria	8
2.2	Document Review	8
2.3	Interviews	9
2.4	Site Inspections	10
2.5	Resolution of Findings	11
2.6	Eligibility for Validation Activities	11
3	Validation Findings	12
3.1	Participation under Other GHG Programs	12
3.2	Methodology Deviations	12
3.3	Project Description Deviations	12
3.4	Grouped Project	13
4	Verification Findings	13
4.1	Project Implementation Status	13
4.2	Safeguards	19
4.3	AFOLU-Specific Safeguards	20

4.4	Accuracy of GHG Emission Reduction and Removal Calculations	20
4.5	Quality of Evidence to Determine GHG Emission Reductions and Removals	28
4.6	Non-Permanence Risk Analysis	28
5	Verification conclusion	29
	APPENDIX A: Abbreviations	31
	APPENDIX B: references	32
	APPENDIX C: Competence of team members and technical reviewers	35
	APPENDIX D: Corrective Action Requests, clarification requests and Forward Action Requests	38

1 INTRODUCTION

Longyuan (Beijing) Carbon Asset Management Technology Co., Ltd. has commissioned Shenzhen CTI International Certification Co., Ltd (CTI) to carry out the verification and certification of emission reductions reported for the “Jilin Tongyu Tongfa Wind Power Project” (the Project) for the monitoring period 25/04/2012-05/12/2017. This report contains the findings from the verification and includes a verification statement for the verified carbon units.

1.1 Objective

Verification is the periodic independent review and ex-post determination by an accredited verification body of the monitored reductions in GHG emissions that have occurred as a result of the registered VCS project activity during a defined verification period.

A verification statement is the written assurance by a verification body that, during a specific period in time, a project activity achieved the emission reductions as verified.

The objective of this verification was to verify and provide a verification statement of emission reductions reported for the “Jilin Tongyu Tongfa Wind Power Project” for the period 25/04/2012-05/12/2017.

1.2 Scope and Criteria

The scope of the verification is:

- To verify that actual monitoring systems and procedures are in compliance with the monitoring systems and procedures described in the monitoring plan;
- To evaluate the GHG emission reduction data and express a conclusion with a reasonable level of assurance about whether the reported GHG emissions reduction data is free from material misstatement;
- To verify that reported GHG emissions data is sufficiently supported by evidence.

The criteria of the verification are:

- VCS Program Guide (version 4.1)/42/
- VCS Standard (version 4.2)/41/ and other relevant requirements defined by Verra;
- The approved methodology ACM0002 (version 6)/45/ applied by the project.

The verification shall ensure that reported emission reductions are complete and accurate in order to be verified.

1.3 Level of Assurance

The verification report expresses a conclusion with a reasonable level of assurance about whether the reported GHG emissions reduction data is free from material misstatement. As per the para 3.9.1 of the VCS Standard Version 4.2, the project size categorization belongs to 'Project' as the expected annual emission reductions is 249,920 tCO₂e lower than 300,000 tCO₂e. Therefore, according to the requirement of para 4.1.8 (4) of VCS standard Version 4.2 "The threshold for materiality with respect to the aggregate of errors, omissions and misrepresentations relative to the total reported GHG emission reductions and/or removals shall be five percent for projects and one percent for large projects.", CTI applied a materiality threshold of 5% with respect to omission or misstatements concerning reported quantities of the project activity.

1.4 Summary Description of the Project

Sectoral Scope and Project Type

According to the VCS Program Guide (version 4.1)/42/ and Annex A of the Kyoto Protocol, the project is applicable under the following activity categories:

- Sectoral Scope: 1. Energy (Renewable/non-renewable)
- Project Type: wind power project

Project Background

The project is located in Tongyu County, Baicheng, Jilin Province of China. The site location's geographical coordinates are east longitude of 122°02'-123°30' and north latitude of 44°13'-45°16'. The project activity was registered as a CDM project with Ref.2068 on 26/01/2009 with the crediting period starting from 26/01/2009. The project has been registered as VCS project with Ref. VCS 276 under VCS Standard Version 2007.1 with the start date 06/12/2007 when the commencement of operations activities started as confirmed by checking the daily operation records/7/, the VCS monitoring report and verification report for the period of 06/12/2007-25/01/2009 /28//29/.

The amount of 130,457 tCO₂e VCUs have been issued for the monitoring period 06/12/2007-25/01/2009 within the 1st VCS crediting period. GHG emission reductions have been applied for CDM for CERs within the 1st CDM crediting period, total 492,784 tCO₂e CERs have been issued for the monitoring periods 26/01/2009-24/07/2009, 25/07/2009-24/06/2010, 25/06/2010-24/06/2011, 25/06/2011-24/04/2012.

The installed capacity of the project is 100.3MW equipped with 118 sets of wind generator in type of Gamesa58-850KW, with unit capacity of 850kW, manufactured by GAMESA Wind (Tianjin) Co.,

Ltd. The electricity generated by the project activity is supplied to China Northeast Power Grid, and the project is estimated to deliver 249,920 tCO₂e emission reduction annually.

2 VERIFICATION PROCESS

2.1 Method and Criteria

The verification was performed through means of the following three phases in accordance with the requirement of the registered VCS PD (i.e. registered CDM PDD version 4.1 dated 20/01/2009) and monitoring plan contained in the registered VCS PD, the applied methodology, and the VCS Standard (version 4.2) and other relevant VCS requirements:

- A desk review of the monitoring report and all support documents;
- Follow-up interviews with project stakeholders and site inspection;
- The resolution of outstanding issues and the issuance of the verification report and statement.

The following sections outline each step in more detail.

The verification of the emission reductions has assessed all factors and issues that constitute the basis for emission reductions from the project. These include:

- The emission reduction calculations and the relevant data records;
- The calibration and maintenance records for the monitoring instruments;
- The management systems to support the project operation and monitoring.

2.2 Document Review

Based on the requirements of competency, experience and qualified sectoral scopes, CTI appointed a verification team in accordance with CTI's internal procedures.

Function	Name	Technical competence	Task Performance*
Team Leader	Zhang Lei	1.1,1.2, 4.1,13.1	☒ DR ☒ SV ☒ RP ☐ TR
Team Member	Zhang Wenting	1.2	☒ DR ☒ SV ☒ RP ☐ TR
Technical Reviewer	Lin Shunrong	1.2, 14.1, 15.1	☒ DR ☐ SV ☐ RP ☒ TR

*DR=Document review; SV=Site visit; RP=Reporting; TR=Technical review

In addition to the VER/VCU monitoring report/1/, the registered VCS PD /12/, emission reduction calculation spreadsheet/2/, the following documents also were assessed as a part of the verification audit:

- The VCS validation report /27/;
- The previous VER/VCU monitoring report/28/ and verification report/29/, and previous CDM/CER monitoring reports /31/and verification reports/32/;
- Baseline and monitoring methodology ACM0002 (version 6) applied by the project/45/;
- Relevant decisions, clarifications and guidance from the Verra/41/-/44/; and
- Other information and references relevant to the project activity.

During the desk review, CTI has applied standard auditing techniques to assess the quality of information provided. The following activities were performed:

- A review of the data and information presented to verify their completeness;
- A review of the monitoring plan and monitoring methodology, paying particular attention to the frequency of measurements, the quality of metering equipment including calibration requirements, and the quality assurance and quality control procedures; and

An evaluation of data management and the quality assurance and quality control system in the context of their influence on the generation and reporting of emission reductions.

2.3 Interviews

On 25/05/2022, CTI visited the project proponent Jilin Longyuan Wind Power Co., Ltd. to perform on-site assessment. The key personnel of the project were interviewed or assisted the verification team /45/. Main topics of the interview cover implementation of the project construction, applicability of selected methodology, implementation of project monitoring, emission reduction calculation, etc.

The key personnel interviewed /46/ are summarized in the table below:

Interviewed personnel	Role	Organization	Subject
Ms. Chen Youchegn	Station Manager	Jilin Longyuan Wind Power Co., Ltd.	Operation of the project activity; Implementation of the monitor plan of the project activity; Data collection and data achievement; Calibration of meters and equipment maintenance; The complaint by local stakeholders; The stakeholder consultation during the operation of the project activity. Project's sustainable development contributions
Ms. Jiangbing	Operator	Jilin Longyuan Wind Power Co., Ltd.	
Ms. Lipeng	Operator	Jilin Longyuan Wind Power Co., Ltd.	
Ms. Wang Xiaogui	Local resident	Local Village	The impact of the project activity; The complaint by local stakeholders; The stakeholder consultation during the operation of the project activity; Project's sustainable development contributions.
Ms. Yang Zhijie			
Ms. Ning Xiaoyong	Staff	Local Environment Protection Bureau	
Ms. Xueqiang	Project Manager	Longyuan (Beijing) Carbon Asset Management Technology Co., Ltd.	Data collection and ER calculation.

2.4 Site Inspections

During the on-site assessment, CTI has applied standard auditing techniques to assess the quality of information provided. The following aspects of the project activity have been verified:

- An assessment of the implementation and operation of the registered project activity is as per the registered VCS PD of the project activity;
- A review of information flows for generating, aggregating and reporting the monitoring parameters; and
- Interviews with relevant personnel to determine whether the operational and data collection procedures are implemented in accordance with the monitoring plan;
- A cross-check between information provided in the monitoring report and data from other sources such as plant logbooks and the electricity receipts;
- A check of the monitoring equipment including calibration performance and observations of monitoring practices against the requirements of the registered VCS PD;
- A review of calculations and assumptions made in determining the GHG data and emission reductions; and

- An identification that quality control and quality assurance procedures in place to prevent or identify and correct any errors or omissions in the reported monitoring parameters.

In addition, all parameters required by the monitoring methodology ACM0002 (version 6), and the management system were assessed during the site visit.

2.5 Resolution of Findings

A corrective action request (CAR) shall be raised, where:

- i. Non-conformities with the monitoring plan or methodology are found in monitoring and reporting, or if the evidence provided to prove conformity is insufficient;
- ii. Mistakes have been made in applying assumptions, data or calculations of emission reductions which will impair the estimate of emission reductions;
- iii. Issues identified in a FAR during validation to be verified during verification have not been resolved by the project proponents.

A clarification request (CL) shall be raised if information is insufficient or not clear enough to determine whether the applicable VCS requirements have been met.

The verification team identified 2 CLs and no CAR in this monitoring period. The CLs were satisfactorily addressed by the project proponents in the updated monitoring report version 02 dated 07/06/2022 (refer to Appendix D for further details).

2.5.1 Forward Action Requests

A forward action request (FAR) is issued for actions if the monitoring and reporting require attention and/or adjustment for the next monitoring period.

CTI confirmed that there was no FAR identified in previous verification/29/, and no FAR was raised during this verification.

2.6 Eligibility for Validation Activities

The project has been validated by DNV Certification AS under the CDM rules and registered as CDM project on 26/01/2009, and was registered as VCS project through the GAP validation by DNV Certification AS under VCS standard version 2007.1.

CTI was accredited in Sectoral Scope 1 on validation and verification and thus is eligible for verification activities on the project. By checking the UNFCCC website, the VCS pipeline and the previous verification reports/26//27/, it is confirmed the verification for this monitoring period 25/04/2012-05/12/2017 which is no more than consecutive 6 years is the first verification

undertaken by CTI. Therefore, the verification undertaken by CTI is in line with the requirement for VVB stipulated in Section 4.1.20 of VCS standard version 4.2.

3 VALIDATION FINDINGS

3.1 Participation under Other GHG Programs

The project has been registered as a CDM project on 26/01/2009 under the UNFCCC with Ref. 2068 with the crediting period starting from 26/01/2009. By checking the UNFCCC website (<https://cdm.unfccc.int/Projects/DB/DNV-CUK1218468288.41/view>), it is confirmed that total 492,784tCO₂e of CERs have been issued for the monitoring periods 26/01/2009-24/07/2009, 25/07/2009-24/06/2010, 25/06/2010-24/06/2011, 25/06/2011-24/04/2012 within the 1st CDM crediting period.

3.2 Methodology Deviations

The validation process /17/ has assessed all factors and issues that constitute the basis for emission reductions from the project according to the applicable CDM methodology ACM0002 (version 6) /45/. There was not any methodology deviation applied to this project. Details refer to section 4.1.

3.3 Project Description Deviations

By checking the registered VCS PD, the previous VCS monitoring report with the monitoring period 06/12/2007-25/01/2009, the previous CDM verification reports with the monitoring period 26/01/2009-24/07/2009, 25/07/2009-24/06/2010, 25/06/2010-24/06/2011, 25/06/2011-24/04/2012, documentation of the project's confirmation of the commissioning and start of operation of the wind turbine/35/, and through the site visit interview with project owner, it is confirmed that the project started official operation on 06/12/2007 which is the project start date according to the requirement of VCS. A deviation was identified for the crediting period of the Project. The project is registered as VCS project under VCS version 2007.1 and completed validation before 19/03/2020. As per VCS requirement, it remains eligible to apply the crediting period requirements under VCS Version 3 which shall be a maximum of ten years and may be renewed at most twice. Therefore, the first renewable crediting period of the Project under VCS is updated from 06/12/2007-25/01/2009 to 06/12/2007-05/12/2017, which lasts for 10 years.

As per VCS requirement, the project did not conduct the validation of crediting period renewal within the two years after the end of the first VCS crediting period. Thus, the crediting period of the project ends on 05/12/2017.

CTI confirms that the project is fully implemented in accordance with the project description, and no any project description deviations. Details refer to section 4.1.

3.4 Grouped Project

The project was not a grouped project; hence this clause is not applicable.

4 VERIFICATION FINDINGS

This section summarizes the findings from the verification of the emission reductions reported for the “Jilin Tongyu Tongfa Wind Power Project” for the monitoring period 25/04/2012-05/12/2017.

4.1 Project Implementation Status

Project Implementation in accordance with the registered project design document

The project is a wind power grid-connected plant and locates Tongyu County, Baicheng, Jilin Province of China. The geographical coordinates are verified by GPS system as east longitude of 122° 02' -123° 30' and north latitude of 44° 13' -45° 16'. The total installed capacity is 100.3MW equipped with 118 sets of wind generator in type of Gamesa58-850KW, with unit capacity of 850kW. It was confirmed by checking the operation logs/7/, the previous VCS/CDM monitoring reports, verification reports /28/-/32/ and documentation of the project's confirmation of the commissioning and start of operation of the wind turbine/35/, the date of 20/11/2007 indicated in the previous CDM verification report was the date of trial operation of the first wind turbine, the date of official operation was 06/12/2007 (i.e. the start of the first crediting period of the VCS) and date of operation of all wind turbines is 23/11/2018. The actual implementation of the project during this verification period was verified in terms of nameplates of wind turbines /33/. The details of the turbines with respect to their installation and capacity have been verified to be consistent with description indicated in the registered VCS PD.

The electricity generated by the project activity is supplied to China Northeast Power Grid, which can be confirmed by the Power purchase agreement (PPA) signed between Jilin Longyuan Wind Power Co., Ltd. and Jilin Electric Power Co., Ltd. /3/. All the monitoring system in operation period is consistent with the description in monitoring plan contained in the registered VCS PD. The control system at the power plant is automated and assures continuous operation, including

monitoring on malfunction of equipment. By checking the daily operation and maintenance records/7/ and via on-site visit, CTI can confirm that no serious malfunction happened and the plant was under a normal operation as expected in this monitoring period.

On-site training for the related procedures including, recording and reporting was verified to be in place/6/ and their implementation was confirmed by interview with the key operators/46/ and observing the operation.

CTI confirms that the project implementation is in accordance with the project description contained in registered VCS PD. Furthermore, through visual inspection and document review, it is confirmed that all physical features of the project activity including data collection systems and storage systems have been implemented in accordance with the monitoring plan.

CL 01 was raised for lacking the information of the construction date, which has been successfully closed, Refer to Appendix D for details.

Compliance of monitoring plan with monitoring methodology

CTI is able to confirm that the monitoring plan contained in the VCS PD is in accordance with the approved methodology applied by the project activity, i.e. ACM0002 (version 6).

Compliance of monitoring with the monitoring plan

The monitoring has been carried out in accordance with the monitoring plan contained in the VCS PD/12/, CTI confirms that all parameters stated in the monitoring plan are monitored and reported appropriately. All parameters required to be monitored by the monitoring plan as per the monitoring methodology ACM0002 (version 6) and the management system were assessed during the site visit. The monitoring report lists each parameter required by the monitoring plan and the information flow (i.e. from data generation, recording, aggregation, calculation and reporting) for these parameters is provided. The information flow for each parameter is further verified in the following sections.

Parameters fixed ex ante

“Data and parameters fixed ex ante” in the MR are checked against the registered VCS PD. The parameter EF_y is the combined emission factor of the grid, which was determined ex-ante at the validation stage and has been fixed during the first crediting period. CTI verified and confirms that the emission factor used in the monitoring report is in compliance with the VCS PD.

Parameters monitored

CTI conducted document review and performed on-site assessment with project stakeholders to:

- A review of information flows for generating, aggregating and reporting the monitoring parameters;

- Determine whether the operational and data collection procedures are implemented in accordance with the registered monitoring plan;
- A cross-check between information provided in the monitoring report and data from other sources such as plant logbooks and electricity receipts;
- An identification that quality control and quality assurance procedures in place to prevent or identify and correct any errors or omissions in the reported monitoring parameters.

According to the monitoring plan, the parameters to be monitored is as below:

EG_y Electricity supplied by the project activity to the grid

Monitored parameters EG_y

By site inspection and checking the monitoring plan contained in the registered VCS PD and previous verification reports, CTI confirmed that the parameter is the net amount of electricity delivered to the grid by the project, which is the difference between the electricity delivered to the grid by the project and the electricity imported from the grid. The electricity delivered to the grid by the project and the electricity imported from the grid are continuously measured by key meter M1 and backup meter M2. Both meters are bi-directional and located at the outlet of the on-site 220KV main transformer of the project. The meter readings of electricity exports and imports were continuously measured, daily read, monthly recorded and archived electronically.

The verification team had on-site checked the location of the meters against the diagram of power connection system /4/ and found them to be consistent and installed in accordance with the approved monitoring plan. All the monitoring facilities and system have been verified by CTI during on-site visit.

By checking operation log /7/ and via on-site visit, it is confirmed that both meters were working well during this monitoring period. Via the on-site interview and by checking the daily operation and maintenance records/7/, monthly reading records and electricity receipts confirmed by both the grid company and the project/9/, it is confirmed by the verification team that the cut-off time of electricity transaction is at 24:00 of 24th of each month /8/. The electricity measured by M1 was recorded by the designated persons of the project proponent and the Grid daily, and then is aggregated monthly on 24th of each month/8/. The electricity sales receipts/9/ issued by the grid company have been used for verifying the records of the electricity delivered to the grid by the project and the electricity imported from the grid.

Monitoring equipment and calibration

The documents review was carried out. Particular attention was paid to the frequency of measurements, the quality of the monitoring equipment including calibration performance and observations of monitoring practices against the requirements of the registered VCS PD and

the methodology ACM0002(version 6) and corresponding tool(s), and the quality assurance and quality control procedures.

All monitoring meters have been calibrated annually as per the monitoring plan covering this monitoring period. The relevant information of the calibration is listed as below:

Meters	Type	SN	Accuracy class	Calibration Date	Validity	Calibration Entity
M1	ZMD402C T44.0257 S2	86688100	0.2S	02/03/2012 28/02/2013 27/02/2014 24/02/2015 22/02/2016 20/02/2017	01/03/2013 27/02/2014 26/02/2015 23/02/2016 21/02/2017 19/02/2018	Metering Centre of State Grid Jilin Electric Power Co.
M2	ZMD402C T44.0257 S2	86688095	0.2S	02/03/2012 28/02/2013 27/02/2014 24/02/2015 22/02/2016 20/02/2017	01/03/2013 27/02/2014 26/02/2015 23/02/2016 21/02/2017 19/02/2018	

Calibration records and accreditation certificates/13//14/have been verified by the verification team. The actual accuracy of meters M1 and M2 is verified to be 0.2S, which is consistent with the requirement in the monitoring plan (accuracy degree is 0.2S) contained in the registered VCS PD and in compliance with the Technical administrative code of electric energy metering /16/. The calibration frequency of meters is annual, which is consistent with the monitoring plan. Based on the site visit and by checking the calibration reports, CTI confirms that:

- All meters have been installed in accordance with the monitoring plan;
- The meters' accuracy is in line with the requirement of the monitoring plan;
- The calibration frequency of the meters is annual, which is in line with the monitoring plan. And the calibrations are verified to be valid for the whole reporting period.

CL 02 was raised for lacking the type of key meter and backup meter, which has been successfully closed, Refer to Appendix D for details.

Data management and control

Jilin Longyuan Wind Power Co., Ltd. is responsible for operation and routine maintenance of power plant under the project activity. The quality assurance and quality control procedures have been addressed in the project management and monitoring manual/5/, including the organization structure with the responsibilities, personnel competencies, monitoring procedures and monitoring management. By interview with the staff/46/ and check records /7//8/ during on-site visit, it can be confirmed that the monitoring management system is implemented following the project management and monitoring manual.

All monitoring devices have been calibrated and maintained periodically to ensure the accuracy of measurement. Calibration records of instruments used in measurements were made available during the verification visit and found to be valid for the entire period of the verification. Competence and training records of in-plant personnel engaged in measurement of plant parameters were presented during verification and found to be in order.

As the above and document review, verification team considers that the project activity operated properly in the way complying with the implementation plan and monitoring plan contained in the VCS PD and the monitoring was performed in a transparent and comprehensive manner during this monitoring period.

By checking the UNFCCC website (<https://cdm.unfccc.int/Projects/DB/DNV-CUK1218468288.41/view>), it is confirmed that emission reductions within the monitoring periods 26/01/2009-24/07/2009, 25/07/2009-24/06/2010, 25/06/2010-24/06/2011, 25/06/2011-24/04/2012 have been issued as CERs within the 1st CDM crediting period 26/01/2009-25/01/2016.

Therefore, it is concluded the monitoring periods of the project activity is consecutive and no double counting issuance has occurred for this verified monitoring period 25/04/2012-05/12/2017 under both VCS and CDM programmes. Via the on-site interview, the project proponent confirmed the emission reductions for this verified period are only requested for VCUs issuance.

The verification team has also checked other GHGs programs and forms of credit such as exchange platform of Chinese Certified Emission Reduction(CCER) projects, Gold Standard, EU ETS, IREC, China ETS and based on the interview with the project proponent, during this monitoring period, it is confirmed that except CDM and VCS scheme:

- No evidence showing that the project has participated or been rejected under any other GHG programs since validation or previous verification
- There is no observation that the project has received or sought any other emission trading program and form of environmental credit, or has become eligible to do so since validation or previous verification

The project is completely voluntary CDM and VCS project, not included in an emissions trading program or any other mechanism that includes GHG allowance trading. Although the national emission trading scheme has been launched since 16/07/2021, it only covers the high-emission and energy intensive industries that emit at least 26,000 tons of CO₂e/year as per Measures for the Administration of Carbon Emission Trading/20/ including thermal power generation, petrochemical, chemical, building materials, iron and steel, etc. By checking the business license/15/of the project proponent, it is confirmed that the PP is qualified in business scope of renewable energy investment, thus is not included the mandatory emission control scheme and there is no emission cap enforced for the PP by further checking the compulsive company list under China ETS in public information/21/.

Moreover, it is confirmed by CTI the project is not registered as a CCER project in China, the emission reductions generated by the project activity are not eligible for transaction under China ETS as per the regulation/20/. Also, CCER mechanism has been suspended by Chinese government since 2017/22/, the project activity will not and is not allowed to registered under CCER mechanism. Thus, the assessment team concluded that the project activity not involved on other emissions trading programs and other binding limits.

The statement of no double counting/23/ submitted by PP was checked by the verification team and confirmed to be correct in terms of the regulations and database of CCER and China ETS.

Via the on-site inspection, and through the interviews with the project proponent, local villagers and official from local environment bureau, and by checking the evidences provided by the project proponent, the verification team agrees on the following points regarding to the promotion of sustainability development by the project activity:

- SDG 7, Indicator 7.2 Renewable energy supplied to the power grid.
The project provides clean and renewable energy through making use of wind power, displacing fossil fuel power in China Northeast Power Grid. During this monitoring period, 650,915.700 MWh of net electricity generated by wind energy was delivered to the China Northeast Power Grid. It is verified by checking the daily and monthly reading records/8/ and via on-site inspection. This contributes to increasing the share of clean energy consumption of China's "Action Plan for Carbon Dioxide Peaking Before 2030"/36/.
- SDG 8, Indicator 8.5 Numbers of job opportunities provided by implementation of the project.
Through interviews with project proponents, employees and local villagers, verification of employee rosters, per capita wage statements provided by PP, partial labour contracts and statistics published by the national statistics data on disposable income per capita from 2012-2017/24/-/26/, it was confirmed that project activities provided 97 permanent employment opportunities for local residents and provides higher salary from 83,278 RMB/year in 2012 to 143,634 RMB/year in 2017 above the national average line level of 24,565 RMB/year in 2012 and 36,396 RMB/year in 2017. Hence, the contribution to this SDG has been confirmed and the provisions for monitoring and reporting this goal is verified as reasonable. This also contributes to one of the China's actions for promoting sustainable developing, "Increase labor force participation rate through implementation of the classification policy. Vigorously enforce the Law on Promotion of Employment" ;
- SDG 13, Indicator Tonnes of greenhouse gas emissions avoided or removed.
As verified by on-site inspection, and via checking the emission reduction calculation sheet/2/ and the daily and monthly reading records/8/, 716,004tCO₂e GHG emission reductions are generated by the project activity during this monitoring period. This contributes to achieve one of China's stated sustainable development priorities "Actively adapt to climate change and strengthen resistance capacity to climate risks in agriculture, forestry, water resources and other key fields, as well as cities, coastal regions and ecologically vulnerable areas"/38/.

Meanwhile, by checking the approved VCS and CDM monitoring reports for the previous monitoring, it is confirmed the project contributions with all impacts for the previous monitoring period from 06/12/2007 to 24/04/2012 were not included in VCS monitoring report or reported in Sustainable Development Contribution Report, thus should not be calculated in the cumulative impact. Therefore, the cumulative impacts in project lifetime are same as the one in this monitoring period.

In conclusion, Verification Team was able to confirm that the project implementation is in accordance with the project description contained in the VCS PD. All required equipments and procedures are available and implemented in an appropriate manner. All necessary monitoring instruments are installed and operated. The project is completely operational and the same has been confirmed on-site. Neither mistakes nor malfunction on main meters have been observed during this monitoring period.

4.2 Safeguards

4.2.1 No Net Harm

Via on-site inspection and checking the EIA summary and conclusion provided in the approved VCS PD, it is confirmed that the impact caused by the project activity on the surrounding ecosystem and wastewater, noise, solid waste and atmosphere etc. is very little, there would be no net harm caused due to the project activity. Appropriate mitigation measures have been undertaken by the project proponent to avoid the potential impacts during the construction and operation. The EIA of the project are approved by the government.

Also, no potential environment or social economic matter was found during the site visit. It is verified by interviewing with project proponent, staff and local villagers and checking the staff roster and monthly payroll/24/, the Explanation of the employment offered by the project /25/ and the average salary provided by the project/26/, that the project has contributed to the local employment and improved income levels by providing job opportunities and offering permanent employees wages well above urban disposable income per capita. As stated by the plant staff during the on-site interviews, they have gained knowledge and skills in the regular training organised by the project proponent, so it can be judged that the project has, to some extent, improved the marketability of the employees as well as the possibility of lifelong learning for them. As verified in Section 4.1 above, 650,915.700 MWh of clean energy was supplied by the project activity to local area and 716,004 tCO₂e GHG emission reductions were generated. These contributions achieve the China 's stated sustainable development priorities in respects to increasing labor force participation rate, increasing the share of clean energy consumption and strengthening resistance capacity to climate risks/38/. Therefore, the implementation of the project activity is beneficial to local social economic environment.

4.2.2 Local Stakeholder Consultation

The local stakeholder consultation meeting was held in Tongyu County 26/07/2006. 8 participants attended the meeting including local government, local environmental protection bureau, local Development and Reform Bureau, local agricultural power bureau, and Wafangdian Village in Huanren County.

By checking the the summary of comments/10/ and the validation report for VCS registered PD/27/, it is confirmed that the stakeholder meeting showed that the proposed project receives strong support from the local community. They all believe the proposed project will promote local economic development and agree with the project development and construction.

For continuous communication with local stakeholders, the project owner carried out questionnaire survey for the local stakeholders to collect the relevant comments and suggestions every two years, e.g., in June 2014, July 2016 and May 2018 during this monitoring period. Via checking the results of the questionnaire/11/, it is confirmed by the verification team that no comments were received. Through interviewing with staff from local environmental protection bureau and local residents during the site visit, it is confirmed by the verification team that during the implementation stage of this monitoring period, local authority has conducted spot checks on the implementation of the project periodically as per the request from the local governments' regulations, no negative comments and issues from the local stakeholders during this monitoring period were identified and the project passed all the periodic spot checks by local government.

All such conclusion has been verified through site visit and checking VCS PD.

4.3 AFOLU-Specific Safeguards

For non-AFOLU projects, this section is not required.

4.4 Accuracy of GHG Emission Reduction and Removal Calculations

CTI confirms that appropriate methods and formulae for calculating baseline emissions, project emissions and leakage have been followed, and the assumptions, emission factors and default values that are applied in the calculation have been justified.

According to the applied methodology, the emission reductions are determined as the difference between the baseline emissions, project emissions and leakage:

$$ER_y = BE_y - PE_y - L_y$$

Baseline emissions

Baseline emissions are determined as multiplying quantity of net electricity supplied to the grid by the project during year y (EG_y) by the validated ex-ante fixed grid emission factor (EF_y).

$$BE_y = EG_y \times EF_y$$

Baseline emission factor (EF_y)

EF_y is the grid emission factor of the which has been verified ex-ante in the validation stage in the VCS PD as 1.1000 tCO₂e/MWh.

The net electricity supplied to the grid by the project (EG_y)

As per the Section 4.1 above, EG_y is determined as the differences between electricity exported to and imported from the grid.

The verification team has checked the monthly reading records, electricity receipts, and emission reduction calculation sheet, and confirmed the data and calculation applied are correct, complete and transparent. The reading records and EG_y calculation are summarized in Table 1 as follow:

Table 1 The net electricity supplied to the grid by the Project (EG_y)

Period	Electricity delivered to the grid by the project			Electricity Imported from the grid by the project			EG _y
	Monthly recording data from M1(MWh)	Sales Receipt (MWh)	Conservative quantity	Monthly recording data from M1 (MWh)	Sales Receipt (MWh)	Conservative quantity	
	A	B	C=min(A,B)	D	E	F=max(D,F)	G=C-F
25/04/2012-24/05/2012	9,820.000	9,820.000	9,820.000	42.530	42.530	42.530	9,777.470
25/05/2012-24/06/2012	5,000.000	5,000.000	5,000.000	202.600	202.600	202.600	4,797.400
25/06/2012-24/07/2012	7,640.000	7,640.000	7,640.000	96.043	96.043	96.043	7,543.957
25/07/2012-24/08/2012	8,590.000	8,590.000	8,590.000	102.960	102.960	102.960	8,487.040
25/08/2012t-24/09/2012	5,330.000	5,330.000	5,330.000	109.190	109.190	109.190	5,220.810
25/09/2012~24/10/2012	11,240.000	11,240.000	11,240.000	75.425	75.425	75.425	11,164.575
25/10/2012~24/11/2012	12,600.000	12,600.000	12,600.000	71.676	71.676	71.676	12,528.324
25/11/2012~24/12/2012	11,930.000	11,930.000	11,930.000	175.481	175.481	175.481	11,754.519
25/12/2012~31/12/2012	1,939.677	8,590.000	1,939.677	69.729	69.729	69.729	1,869.948
25/04/2012-31/12/2012	74,089.677	80,740.000	74,089.677	945.634	945.634	945.634	73,144.043
01/01/2013~24/01/2013	6,650.323	8,590.000	6,650.323	239.072	239.072	239.072	6,411.251
25/01/2013~24/02/2013	11,220.000	11,220.000	11,220.000	83.054	83.054	83.054	11,136.946

25/02/2013~24/03/2013	17,630.000	17,630.000	17,630.000	45.725	45.725	45.725	17,584.275
25/03/2013~24/04/2013	20,420.000	20,420.000	20,420.000	43.639	43.639	43.639	20,376.361
25/04/2013~24/05/2013	19,180.000	19,180.000	19,180.000	303.860	303.860	303.860	18,876.140
25/05/2013~24/06/2013	14,150.000	14,150.000	14,150.000	69.406	69.406	69.406	14,080.594
25/06/2013~24/07/2013	8,470.000	8,470.000	8,470.000	120.622	120.622	120.622	8,349.378
25/07/2013~24/08/2013	6,760.000	6,760.000	6,760.000	85.219	85.219	85.219	6,674.781
25/08/2013~24/09/2013	11,820.000	11,820.000	11,820.000	89.998	89.998	89.998	11,730.002
25/09/2013~24/10/2013	11,970.000	11,970.000	11,970.000	80.362	80.362	80.362	11,889.638
25/10/2013~24/11/2013	11,480.000	11,480.000	11,480.000	48.418	48.418	48.418	11,431.582
25/11/2013~24/12/2013	9,970.000	9,970.000	9,970.000	130.680	130.680	130.680	9,839.320
25/12/2013~31/12/2013	1,684.516	7,460.000	1,684.516	32.167	32.167	32.167	1,652.349
01/01/2013-31/12/2013	151,404.839	159,120.000	151,404.839	1,372.222	1,372.222	1,372.222	150,032.617
01/01/2014~24/01/2014	5,775.484	7,460.000	5,775.484	110.287	110.287	110.287	5,665.197
25/01/2014~24/02/2014	5,150.000	5,150.000	5,150.000	169.356	169.356	169.356	4,980.644
25/02/2014~24/03/2014	11,020.000	11,020.000	11,020.000	110.167	110.167	110.167	10,909.833
25/03/2014~24/04/2014	12,520.000	12,520.000	12,520.000	53.539	53.539	53.539	12,466.461
25/04/2014~24/05/2014	10,560.000	10,560.000	10,560.000	90.922	90.922	90.922	10,469.078
25/05/2014~24/06/2014	9,200.000	9,200.000	9,200.000	98.076	98.076	98.076	9,101.924
25/06/2014~24/07/2014	10,750.000	10,750.000	10,750.000	93.588	93.588	93.588	10,656.412
25/07/2014~24/08/2014	4,070.000	4,070.000	4,070.000	162.545	162.545	162.545	3,907.455
25/08/2014~24/09/2014	7,850.000	7,850.000	7,850.000	92.083	92.083	92.083	7,757.917
25/09/2014~24/10/2014	8,740.000	8,740.000	8,740.000	95.621	95.621	95.621	8,644.379

25/10/2014~24/11/2014	10,750.000	10,750.000	10,750.000	73.946	73.946	73.946	10,676.054
25/11/2014~24/12/2014	12,050.000	12,050.000	12,050.000	136.541	136.541	136.541	11,913.459
25/12/2014~31/12/2014	1,772.581	7,850.000	1,772.581	35.428	35.428	35.428	1,737.153
01/01/2014-31/12/2014	110,208.065	117,970.000	110,208.065	1,322.099	1,322.099	1,322.099	108,885.966
01/01/2015~24/01/2015	6,077.419	7,850.000	6,077.419	121.467	121.467	121.467	5,955.952
25/01/2015~24/02/2015	7,100.000	7,100.000	7,100.000	48.286	48.286	48.286	7,051.714
25/02/2015~24/03/2015	9,600.000	9,600.000	9,600.000	48.286	48.286	48.286	9,551.714
25/03/2015~24/04/2015	17,790.000	17,790.000	17,790.000	30.809	30.809	30.809	17,759.191
25/04/2015~24/05/2015	13,030.000	13,030.000	13,030.000	57.684	57.684	57.684	12,972.316
25/05/2015~24/06/2015	8,190.000	8,190.000	8,190.000	75.029	75.029	75.029	8,114.971
25/06/2015~24/07/2015	3,860.000	3,860.000	3,860.000	109.560	109.560	109.560	3,750.440
25/07/2015~24/08/2015	3,770.000	3,770.000	3,770.000	121.836	121.836	121.836	3,648.164
25/08/2015~24/09/2015	5,440.000	5,440.000	5,440.000	83.450	83.450	83.450	5,356.550
25/09/2015~24/10/2015	12,680.000	12,680.000	12,680.000	43.560	43.560	43.560	12,636.440
25/10/2015~24/11/2015	11,760.000	11,760.000	11,760.000	114.814	114.814	114.814	11,645.186
25/11/2015~24/12/2015	6,440.000	6,440.000	6,440.000	186.886	186.886	186.886	6,253.114
25/12/2015~31/12/2015	1,833.548	8,120.000	1,833.548	27.851	27.851	27.851	1,805.697
01/01/2015-31/12/2015	107,570.968	115,630.000	107,570.968	1,069.518	1,069.518	1,069.518	106,501.449
01/01/2016~24/01/2016	6,286.452	8,120.000	6,286.452	95.490	95.490	95.490	6,190.962
25/01/2016~24/02/2016	6,850.000	6,850.000	6,850.000	101.402	101.402	101.402	6,748.598
25/02/2016~24/03/2016	9,290.000	9,290.000	9,290.000	49.421	49.421	49.421	9,240.579
25/03/2016~24/04/2016	17,660.000	17,660.000	17,660.000	44.748	44.748	44.748	17,615.252

25/04/2016~24/05/2016	12,930.000	12,930.000	12,930.000	48.576	48.576	48.576	12,881.424
25/05/2016~24/06/2016	9,520.000	9,520.000	9,520.000	87.569	87.569	87.569	9,432.431
25/06/2016~24/07/2016	7,770.000	7,770.000	7,770.000	88.123	88.123	88.123	7,681.877
25/07/2016~24/08/2016	3,730.000	3,730.000	3,730.000	83.292	83.292	83.292	3,646.708
25/08/2016~24/09/2016	5,940.000	5,940.000	5,940.000	128.093	128.093	128.093	5,811.907
25/09/2016~24/10/2016	7,890.000	7,890.000	7,890.000	83.741	83.741	83.741	7,806.259
25/10/2016~24/11/2016	9,950.000	9,950.000	9,950.000	104.016	104.016	104.016	9,845.984
25/11/2016~24/12/2016	10,190.000	10,190.000	10,190.000	102.010	102.010	102.010	10,087.990
25/12/2016~31/12/2016	1,406.774	6,230.000	1,406.774	27.541	27.541	27.541	1,379.233
01/01/2016-31/12/2016	109,413.226	116,070.000	109,413.226	1,044.022	1,044.022	1,044.022	108,369.204
01/01/2017~24/01/2017	4,823.226	6,230.000	4,823.226	94.427	94.427	94.427	4,728.798
25/01/2017~24/02/2017	5,990.000	5,990.000	5,990.000	40.471	40.471	40.471	5,949.529
25/02/2017~24/03/2017	12,470.000	12,470.000	12,470.000	96.703	96.703	96.703	12,373.297
25/03/2017~24/04/2017	13,040.000	13,040.000	13,040.000	40.207	40.207	40.207	12,999.793
25/04/2017~24/05/2017	16,130.000	16,130.000	16,130.000	36.643	36.643	36.643	16,093.357
25/05/2017~24/06/2017	9,260.000	9,260.000	9,260.000	76.507	76.507	76.507	9,183.493
25/06/2017~24/07/2017	6,100.000	6,100.000	6,100.000	176.220	176.220	176.220	5,923.780
25/07/2017~24/08/2017	3,040.000	3,040.000	3,040.000	111.487	111.487	111.487	2,928.513
25/08/2017~24/09/2017	9,410.000	9,410.000	9,410.000	53.566	53.566	53.566	9,356.434
25/09/2017~24/10/2017	9,560.000	9,560.000	9,560.000	78.778	78.778	78.778	9,481.222
25/10/2017~24/11/2017	12,540.000	12,540.000	12,540.000	38.993	38.993	38.993	12,501.007
25/11/2017~05/12/2017	2,577.667	7,030.000	2,577.667	114.470	114.470	114.470	2,463.197

01/01/2017-05/12/2017	104,940.892	110,800.000	104,940.892	958.472	958.472	958.472	103,982.421
Total	657,627.667	700,330.000	657,627.667	6,711.967	6,711.967	6,711.967	650,915.700

*Note:

1. The monthly electricity is obtained from the meter reading data at 24:00 on the 24th of each month and checked with the electricity receipts issued by the grid company.
2. Electricity data for the periods 25/12-31/12 2012-2016 and 01/01-24/01 2013-2017 and 25/11/2017-05/12/2017 were obtained from the daily reading records and cross-checked with the electricity confirmation certificates issued by the grid company/9/

The corresponding baseline emission reductions during this monitoring period is calculated as:

Year	EG _y (MWh)	EF _y (tCO ₂ /MWh)	BE _y (tCO ₂)
25/04/2012-31/12/2012	73,144.043	1.1000	80,458
01/01/2013-31/12/2013	150,032.617	1.1000	165,035
01/01/2014-31/12/2014	108,885.966	1.1000	119,774
01/01/2015-31/12/2015	106,501.449	1.1000	117,151
01/01/2016-31/12/2016	108,369.204	1.1000	119,206
01/01/2017-05/12/2017	103,982.421	1.1000	114,380
Total	650,915.700	-	716,004

Project emissions

As statement in the registered VCS PD, for the wind power activities, the project emissions from the project is zero. Hence, PE_y during the monitoring period from Jilin Tongyu Tongfa Wind Power Project is zero.

Leakages

Leakage does not need to be accounted for this project as per the monitoring methodology ACM0002 (version 6).

Emission reductions

The emission reductions for this monitoring period were calculated as:

Monitoring period	GHG emission reductions or removals (tCO ₂ e)
25/04/2012-31/12/2012	80,458
01/01/2013-31/12/2013	165,035
01/01/2014-31/12/2014	119,774
01/01/2015-31/12/2015	117,151
01/01/2016-31/12/2016	119,206
01/01/2017-05/12/2017	114,380
Total ERs claimed (in 2,051 days)	716,004

Comparison of actual emission reductions or net anthropogenic GHG removals by sinks with estimates in registered CDM-PDD

The emission reductions claimed are 716,004 tCO₂e in this monitoring period (i.e. 2,051 days). Compared with expected emission reductions 1,404,345 tCO₂e (calculated as 249,920tCO₂/365d*2,051d), the reported emission reductions in this monitoring period are 49.02% less than the expected in the registered VCS PD. By verifying the average wind speed of the project for each year tested from 2012-2017/39/, the feasibility study report/34/ and the description of the reduction in electricity generation/40/, the average wind speeds at the project site from 2012-2017 were 5.94m/s, 6.05m/s, 5.37m/s, 5.51m/s, 5.27m/s and 5.95m/s respectively, all well below the design wind speed of 7.23m/s in the feasibility study report, while the project was also affected by grid restrictions and CTI therefore confirmed that the reduction in power generation during this monitoring period was reasonable.

Therefore, CTI verified the input data for calculating emission reductions and the calculating process, and confirmed the result were complete and transparent.

4.5 Quality of Evidence to Determine GHG Emission Reductions and Removals

All necessary documentations are collected, referenced and aggregated, which is easily accessible in hard-copy or electronic format. Measurements are performed by calibrated equipment, and the key data can also be cross-checked via other sources, such as records, receipts and inventory data. No assumptions are used that have any material influence on reported emission reductions.

CTI concludes that during this monitoring period, the evidences for determination of emission reductions are sufficient and reasonable, and the calculation of emission reductions is reliable.

4.6 Non-Permanence Risk Analysis

The project is not AFOLU project, and thus non-permanence risk analysis is not applicable for the project.

5 VERIFICATION CONCLUSION

Shenzhen CTI International Certification Co., Ltd (CTI) has performed the verification of the emission reductions that have been reported for the project activity “Jilin Tongyu Tongfa Wind Power Project” in China (VCS Project ID: 276) for the period 25/04/2012-05/12/2017.

The verification is based on the baseline and monitoring methodology ACM0002 (version 6), the VCS PD. The verification consisted of the following three phases: i) desk review of the project design and the baseline and monitoring plan; ii) follow-up interviews with project stakeholders; iii) resolution of outstanding issues and the issuance of the final verification and certification report.

The project proponents are responsible for the collection, calculation and determination of the GHG data in accordance with the monitoring plan and the reporting of GHG emission reductions on the basis set out within the project monitoring report.

Our verification approach was based on the requirements as defined under the applicable VCS Standard Version 4.2 and relevant UNFCCC requirements. Our approach is risk-based, drawing on an understanding of the risks associated with reporting GHG emissions data and the controls in place to mitigate these. The verification can confirm that:

- the project is implemented and operated as per the registered VCS PD ;
- the monitoring plan is as per the applied methodology;
- the monitoring complies with the monitoring plan;
- the monitoring report and other supporting documents provided are complete and verifiable and in accordance with the applicable VCS Standard Version 4.2 and CDM requirements;
- the installed equipment being essential for generating emission reduction runs reliably and is calibrated appropriately;
- the monitoring system is in place and generates GHG emission reductions data;
- the GHG emission reductions are calculated without material misstatements.

It is CTI's responsibility to provide an independent verification statement on the reported GHG emission reductions for the project. Based on an understanding of the risks associated with reporting of GHG emission data and the controls in place to mitigate these, CTI planned and performed our work to obtain the information and explanations that we considered necessary to provide reasonable assurance that reported GHG emission reductions are fairly stated.

CTI does not assume any responsibility towards the issuance and utilization of the VCUs hereby verified and certified. Request for issuance of VCUs shall be made by the project proponent to an

approved VCS Program Registry based on the requirements set out under the most recent version of the VCS Program Guidelines clause on VCS Registration.

The verification of reported emission reductions is based on the information made available to CTI and the engagement conditions detailed in this report. CTI cannot be held liable by any party for decisions made or not made based on this report.


In CTI's opinion the GHG emissions reductions of the "Jilin Tongyu Tongfa Wind Power Project" for the period 25/04/2012-05/12/2017 are fairly stated in the monitoring report (version 02 dated 07/06/2022). The GHG emission reductions were calculated correctly on the basis of the approved methodology ACM0002 (version 6) and the monitoring plan contained in the registered VCS PD.

CTI can confirm that the GHG emission reductions are calculated without material misstatements. Based on the evidence and information that are considered necessary to guarantee that GHG emission reductions are appropriately calculated, CTI confirms the following statement:

Reporting period: 25/04/2012-05/12/2017

Verified GHG emission reductions and removals in the above verification period:

<i>Period</i>	Baseline emissions or removals (tCO₂e)	Project emissions or removals (tCO₂e)	Leakage emissions (tCO₂e)	Net GHG emission reductions or removals (tCO₂e)
25/04/2012-31/12/2012	80,458	0	0	80,458
01/01/2013-31/12/2013	165,035	0	0	165,035
01/01/2014-31/12/2014	119,774	0	0	119,774
01/01/2015-31/12/2015	117,151	0	0	117,151
01/01/2016-31/12/2016	119,206	0	0	119,206
01/01/2017-05/12/2017	114,380	0	0	114,380
Total	716,004	0	0	716,004



Mr.Zhang Lei

Technical Leader

14-Jun-2022



Ms. Lin Shunrong

Team Reviewer

14-Jun-2022

APPENDIX A: ABBREVIATIONS

CAR	Corrective Action Request
CCER	Chinese Certified Emission Reduction
CER	Certified Emission Reduction(s)
CL	Clarification request
CO ₂	Carbon Dioxide
CO ₂ e	Carbon Dioxide Equivalent
CTI	Shenzhen CTI International Certification Co., Ltd
DOE	Designated Operational Entity
EF	Emission Factor
ER	Emission Reduction
EU ETS	EU Emissions Trading Scheme
FAR	Forward Action Request
FSR	Feasibility Study Report
GHG	Greenhouse Gas(es)
IREC	International Renewable Energy Certificates
MP	MONITORING REPORT
MR	Monitoring Report
PD	Project Description
PP	Project Proponent
SN	Serial Number
VCS	Verified Carbon Standard
VCU	Verified Carbon Unit

APPENDIX B: REFERENCES

Documentation used to verify the information provided by the project proponents

/1/	Longyuan (Beijing) Carbon Asset Management Technology Co., Ltd.: VER/VCU Monitoring Report for Jilin Tongyu Tongfa Wind Power Project, V01 dated 20/04/2022, version 02 dated 07/06/2022
/2/	Longyuan (Beijing) Carbon Asset Management Technology Co., Ltd.: Emission reduction calculation spreadsheet for Jilin Tongyu Tongfa Wind Power Project, version 02 dated 07/06/2022
/3/	Jilin Longyuan Wind Power Co., Ltd. and Jilin Electric Power Co., Ltd.: Power Purchase Agreement for Jilin Electric Power Co., Ltd.
/4/	Jilin Longyuan Wind Power Co., Ltd.: Diagram of power connection system
/5/	Jilin Longyuan Wind Power Co., Ltd.: VER monitoring manual and management procedure.
/6/	Jilin Longyuan Wind Power Co., Ltd.: Records of training for on-site staff.
/7/	Jilin Longyuan Wind Power Co., Ltd.: Daily operation and maintenance records.
/8/	Jilin Longyuan Wind Power Co., Ltd.: Daily and monthly reading records of Jilin Tongyu Tongfa Wind Power Project from 25/04/2012-05/12/2017
/9/	Jilin Electric Power Co., Ltd.: Monthly electricity sale receipts from 25/04/2012-05/12/2017 and certificate of confirmation of electricity issued by the grid company from the period of 25/12-31/12 of 2012-2016, 01/01-24/01 of 2013-2017 and 01/12/2017-05/12/2017
/10/	Meeting memo of the stakeholder consultation and the participants' signature form, 26/07/2006
/11/	Questionnaires for local stakeholders
/12/	Jilin Longyuan Wind Power Co., Ltd.: Registered VCS PD (version 4.1 dated 20/01/2009)
/13/	Jilin Provincial Bureau of Quality and Technical Supervision: Accreditation certificate of Metering Centre of State Grid Jilin Electric Power Co., issued on 31/12/2013, valid up to 30/12/2017

/14/	Metering Centre of State Grid Jilin Electric Power Co.: Calibration certificates for meters M1 and M2 covering this monitoring period
/15/	Business license of Jilin Longyuan Wind Power Co., Ltd.
/16/	State Economic and Trade Commission: Technical administrative code of electric energy metering (DL/T 448-2000)
/17/	UNFCCC, http://cdm.unfccc.int
/18/	Gold Standard, http://www.goldstandard.org/
/19/	China CCER Exchange Info-platform, http://cdm.ccchina.org.cn/ccer.aspx
/20/	Measures for the Administration of Carbon Emission Trading, issued by Ministry of Ecology and Environment of China, dated 31/12/2020
/21/	Enforced company list in China cap & trade scheme, issued by Ministry of Ecology and Environment of China
/22/	Announcement of the National Development and Reform Commission, Code 2 in 2017, issued by National Development and Reform Commission, dated 03/14/2017
/23/	Jilin Longyuan Wind Power Co., Ltd.: Statement of no double counting
/24/	Jilin Longyuan Wind Power Co., Ltd.: Staff roster
/25/	Jilin Longyuan Wind Power Co., Ltd.:Explanatory material on the number of people employed and the average salary provided by the project.
/26/	Statistical Bulletin on National Economic and Social Development by Year: http://www.stats.gov.cn/search/
/27/	DNV Certification AS: VCS Validation Report
/28/	VER/VCU Monitoring Report for Jilin Tongyu Tongfa Wind Power Project of previous monitoring period 06/12/2007-25/01/2009
/29/	DNV Certification AS: VCS Verification Report for Jilin Tongyu Tongfa Wind Power Project of previous monitoring period 06/12/2007-25/01/2009
/30/	DNV Certification AS: CDM Validation Report, Revision NO. 02 , dated 25/02/2007
/31/	CDM/CER Monitoring Reports for Jilin Tongyu Tongfa Wind Power Project of previous CDM monitoring periods 26/01/2009-24/07/2009, 25/07/2009-24/06/2010, 25/06/2010-24/06/2011, 25/06/2011-24/04/2012
/32/	CDM Verification Reports for Jilin Tongyu Tongfa Wind Power Project of previous monitoring period 26/01/2009-24/07/2009, 25/07/2009-24/06/2010, 25/06/2010-

	24/06/2011, 25/06/2011-24/04/2012
/33/	GAMESA Wind (Tianjin) Co., Ltd: Nameplates of the equipment
/34/	Feasibility Study Report of Jilin Tongyu Tongfa Wind Power Project
/35/	Jilin Longyuan Wind Power Co., Ltd.: A note on the start time of wind turbine operation
/36/	Co-signed by the GAMESA Wind (Tianjin) Co., Ltd and Jilin Longyuan Wind Power Co., Ltd.: Wind Turbines Purchase Agreement, dated 20/04/2007
/37/	Action Plan for Carbon Dioxide Peaking Before 2030 published by the State Council on 24/10/2021
/38/	China's National Programme to Address Climate Change published by the State Council on 28/03/2008
/39/	Jilin Longyuan Wind Power Co., Ltd.: Average Wind Speed Statistics of 2012-2017
/40/	Jilin Longyuan Wind Power Co., Ltd.: A note on the reduction in power generation from the project.

Methodologies, tools and other guidance

/41/	Verified Carbon Standard: VCS Standard, version 4.2
/42/	Verified Carbon Standard: VCS Program Guide, version 4.1
/43/	Verified Carbon Standard: VCS Sectoral Scopes http://v-c-s.org/node/448
/44/	Verified Carbon Standard: Registration and Issuance Process, version 4.1
/45/	UNFCCC EB: Approved methodology, ACM0002 , version 6

Persons interviewed

/46/	Ms. Chen Youchegn, Station Manager, Jilin Longyuan Wind Power Co., Ltd. Ms. Jiangbing, Operator, Jilin Longyuan Wind Power Co., Ltd. Ms. Lipeng, Operator, Jilin Longyuan Wind Power Co., Ltd. Ms. Wang Xiaogui, Local resident, Local Village Ms. Yang Zhijie, Local resident, Local Village Ms. Ning Xiaoyong, Staff, Local Environment Protection Bureau Ms. Xueqiang, Project Manager, Longyuan (Beijing) Carbon Asset Management Technology Co., Ltd.
------	---

APPENDIX C: COMPETENCE OF TEAM MEMBERS AND TECHNICAL REVIEWERS

Mr. Lei ZHANG

Satisfies the requirements of competence management system of CTI Certification, and is hereby appointed as:

Qualification						
Status	GHG Auditor	Validator	Verifier	Team Leader	Technical Reviewer	Technical Expert
Date	√	√	√	√	√	√

Scope	Technical Area
SS 1: Energy industries (renewable/non-renewable sources)	TA 1.1: Thermal energy generation
	TA 1.2: Energy generation from renewable energy sources
SS 4: Manufacturing industries	TA 4.1: Cement and lime production
SS 13: Waste handling and disposal	TA 13.1: Solid waste and wastewater

This appointment is valid for 3 years from its date of approval below and is bound by internal requirements of management system of the Certification Body of CTI.

Approved by:

Wu Lin

Wu LIN

Technical Competent Manager

Shenzhen, 01/01/2021

Ms. Wenting ZHANG

Satisfies the requirements of competence management system of CTI Certification, and is hereby appointed as:


Qualification					
GHG Auditor	Validator	Verifier	Team Leader	Technical Reviewer	Technical Expert
√	-	-	-	-	-

Scope	Technical Area
SS 1: Energy industries (renewable/non-renewable sources)	TA 1.2: Energy generation from renewable energy sources

This appointment is valid for 3 years from its date of approval below and is bound by internal requirements of management system of the Certification Body of CTI.

Approved by:

Wu LIN



Technical Competent Manager

Shenzhen, 01/03/2022

Ms. Shunrong LIN

Satisfies the requirements of competence management system of CTI Certification, and is hereby appointed as:

Qualification						
Status	GHG Auditor	Validator	Verifier	Team Leader	Technical Reviewer	Technical Expert
Date	√	√	√	√	√	√

Scope	Technical Area
SS 1: Energy industries (renewable/non-renewable sources)	TA 1.2: Energy generation from renewable energy sources
SS 14: Afforestation and reforestation	TA 14.1: Afforestation and reforestation
SS 15: Agriculture	TA 15.1: Agriculture

This appointment is valid for 3 years from its date of approval below and is bound by internal requirements of management system of the Certification Body of CTI.

Approved by:

Wu Lin

Wu LIN

Technical Competent Manager

Shenzhen, 01/01/2021

APPENDIX D: CORRECTIVE ACTION REQUESTS, CLARIFICATION REQUESTS AND FORWARD ACTION REQUESTS

Table 1: Corrective Action Requests

CAR ID	Corrective Action Request	Response by Project Proponent	Verification Team Assessment
NA	NA	NA	NA

Table 2: Clarification Requests

CL ID	Clarification Request	Response by Project Proponent	Verification Team Assessment
CL 01	It is requested to clarify the information of construction date.	The information of construction date had been updated in the MR.	OK. It has been revised and verified by CTI by checking updated MR. Therefore, CL 01 is closed.
CL 02	It is requested to clarify the type of key meter and backup meter.	The type of key meter and check meter had been updated in the MR.	OK. It has been revised and verified by CTI by checking updated MR. Therefore, CL 02 is closed.

Table 3: Forward Action Requests

FAR ID	Forward Action Request	Response by Project Proponent	Verification Team Assessment
NA	NA	NA	NA