



VERIFICATION REPORT FOR "BLITTA – TOGO SOLAR POWER PLANT"



Report ID	VE-1014
Project title	Blitta – Togo Solar Power Plant
Project ID	3298
Verification period	01/01/2023 to 31/12/2023
Original date of issue	07-11-2024
Most recent date of issue	07-11-2024
Version	1
VCS Standard Version	VCS Standard Version 4.7 ^{1/}
Client	Climate Partner GmbH
Prepared by	SustainCERT S.A.
Approved by	Shivraj Sharma

	Director, Validation and Verification Services
Work carried out by	Team Leader: Indrapal Parmar(TA-1.2) Technical Area Expert: Indrapal Parmar and Durando NDONGSOK Local Auditor & Expert: Durando NDONGSOK Auditor: Manika Mongia Independent Reviewer: Muskan Chawla (TA-1.2)

Summary:

A description of the verification of the project:

The Verification of the project titled Blitta – Togo Solar Power Plant VCS ID – 3298, have been undertaken by SustainCERT, with accordance to the relevant VCS standard, V4.7^{/1/}, VCS Program Guide, V4.4^{/2/} Relevant requirements of the ISO 14064-2 and ISO 14064-3, as well as applicable criteria for consistent project operations, monitoring and reporting has been applied for verification.

The project “Blitta – Togo Solar Power Plant” mainly involves the operation of solar photovoltaic plant located in Blitta-Losso village. The plant operates in 2 phases i.e. Phase 1 - 50 MW commissioned on 12/06/2021 and Phase 2- 20MW commissioned on 05/02/ 2024 as verified on site^{/8/}. 77,751 MWh of electricity is generated by the plant with the average of 6,481.26 MWh/month of electricity produced by the project activity and reduced 44,551 tCO2e for the current monitoring period.

The primary purpose of the project is to supply reliable, clean electricity to the national grid substituting grid electricity and to cut down GHG emissions from baseline fossil fuel intensive grid mix. Apart from emission reductions, the project's benefits comprise, among others, improvement of energy self- sufficiency of the country and creation of local employment.

The project is a renewable energy generation activity that results in the reduction of greenhouse gas (GHG) emissions that are real, measurable, and verifiable and plays a beneficial role in the mitigation of climate change.

Purpose and scope of verification:

Verification service provided by SustainCERT for the project activity VCS ID- 3298 is to perform independent periodic verification for the monitoring period 01/01/2023—31/12/2023. First and last days inclusion verified from the emission reduction calculation sheet and monthly invoices^{/21/}. The verification of the project is an independent review and ex-post determination by SustainCERT of the monitored reductions in GHG emissions that have occurred, against the VCS standard, V4.7^{/1/}, VCS Program Guide, V4.4^{/2/}, the Project baseline and host party criteria.

The scope of verification is to establish/verify that:

- The project activity has been implemented and operated as per the approved registered PDD^{/4/}.
- All the physical features (technology, project equipment and monitoring and metering equipment^{/19/20/}) of the project are in place in accordance with registered PDD^{/4/}.
- The monitoring report^{/6/} and other supporting documents provided are complete in accordance with the latest applicable version of VCS standard^{/1/}.
- The actual monitoring systems and procedures comply with the monitoring systems and procedures described in the registered monitoring plan, the approved methodology^{/5/} including applicable tool(s) and/or, where applicable, the approved standardized baseline.
- The data recorded and stored as per the monitoring methodology^{/5/} including applicable tool(s) and, where applicable, the standardized baseline.

The Monitoring Period:

The project activity “Blitta – Togo Solar Power Plant” is undergoing 2nd verification from 01/01/2023—31/12/2023 (both days included)^{/6/7/21/}, under its 7 years, twice renewable crediting period from 12/06/2021 to 11/06/2028.

The Method and Criteria used for Verification:

Desk Review:

Review of project information, monitoring plan specifically monitoring frequency, the metering equipment calibration^{/18/} requirement, quality assurance and quality control system against the registered Joint PDD, V7.0^{/4/} and applicable VCS standard^{/1/} and applied CDM Methodology^{/5/} ACM0002: Grid-connected electricity generation from renewable sources Version 20.0

Onsite audit:

Interview with the relevant personnel to confirm the implementation of the project with paying particular attention to the operational and data collection procedures, in accordance with the registered PDD^{/4/}, Version 7.0 and the applied methodology.

A detailed cross check of the information provided in the monitoring report^{/6/} against the relevant evidence on site^{/8/} was carried out for the measuring equipment.

A detailed cross check of the calculations made for the estimation of greenhouse gas emissions^{/7/10/}.

An evaluation of data management and the quality assurance and quality control system in the context of their influence on the generation and reporting of emissions reduction.

The number of findings raised during verification:

A risk-based approach has been followed for the verification of the project. During verification, 06 CARs, 11 CL and 00 FAR were raised during verification.

All CL and CARs raised were resolved successfully, details for which can be found in appendix 4 of the report.

Any uncertainties associated with the verification:

The assessment team thoroughly reviewed the monitoring report and the emission reduction calculation sheet against the relevant evidence and applicable VCS requirements, VCS standard V4.7^{/1/} and VCS guideline V4.4^{/2/}. It has been concluded that there are no uncertainties associated with the project.

Summary of the verification conclusion:

The review of monitoring report v3.0^{/6/}, emission reduction calculation^{/7/} sheet along with relevant supporting evidence and the interview with relevant personnel during on site audit have provided the assessment team with sufficient evidence to confirm to the applicable criteria. The SustainCERT confirms the project activity “Blitta – Togo Solar Power Plant” have been successfully implemented in accordance with the registered PDD^{/4/}, V7.0 and applied CDM Methodology^{/5/} ACM0002: Grid-connected electricity generation from renewable sources Version 20.0 meeting all the relevant VCS requirements. SustainCERT confirms that the monitoring period 01/01/2023—31/12/2023 (including both the days) in its implementation is calculated to generate 44,551 tCO₂e of emission reductions by displacing 77,751.00 MWh of electricity from fossil fuel-fired power plants^{/6/}

CONTENTS

1	INTRODUCTION	7
1.1	Objective	7
1.2	Scope and Criteria	7
1.3	Level of Assurance.....	8
1.4	Summary Description of the Project	8
2	VERIFICATION PROCESS	9
2.1	Method and Criteria.....	9
2.2	Document Review	10
2.3	Interviews	11
2.4	Site Visits	13
2.5	Resolution of Findings	16
2.6	Eligibility for Validation Activities	16
3	VALIDATION FINDINGS	17
3.1	Methodology Deviations.....	17
3.2	Project Description Deviations.....	17
3.3	New Project Activity Instances in Grouped Projects.....	17
3.4	Baseline Reassessment	17
4	VERIFICATION FINDINGS.....	17
4.1	Project Details	17
4.2	Safeguards and Stakeholder Engagement	20
4.3	Accuracy of Reduction and Removal Calculations.....	28
4.4	Quality of Evidence to Determine Reductions and Removals.....	30
4.5	Non-Permanence Risk Analysis.....	35
5	VERIFICATION OPINION.....	35
5.1	Verification Summary	35
5.2	Verification Conclusion	36
5.3	Ex-ante vs Ex-post ERR Comparison	37
	APPENDIX 1: COMMERCIALY SENSITIVE INFORMATION	38
	APPENDIX 2: TABLE OF REFERENCE.....	39

APPENDIX 3: ABBREVIATIONS	41
APPENDIX 4: PROJECT FINDINGS	42
APPENDIX 5: COMPETENCE OF TEAM MEMBERS AND TECHNICAL REVIEWERS.....	64

1 INTRODUCTION

1.1 Objective

The Verification of the project titled “Blitta – Togo Solar Power Plant ” VCS ID – 3298, have been undertaken by SustainCERT, as requested by ClimatePartner GmbH project proponent for the monitoring period 01/01/2023—31/12/2023 (including both the days). The verification of project activity is the 2nd periodic verification for the crediting period 01/01/-2023—31/12/2023. The purpose of the verification is to conduct the independent review of the project information and confirm:

- The project activity is implemented in accordance with registered PDD document, V7.0^{/4/}.
- All physical features (technology, project equipment and metering equipment)^{/18/19/} are in place.
- The actual monitoring systems and procedures comply with the monitoring systems and procedures described in the monitoring plan, the approved methodology^{/5/} including applicable tool(s) and/or, where applicable, the approved standardized baseline.
- The data collection procedures and records are as per the monitoring methodology^{/5/} ACM0002: Grid-connected electricity generation from renewable sources v 20.0

The verification followed the requirements mentioned in the VCS standard, version 4.7^{/1/} and VCS guidelines, V4.4^{/2/} ensuring the quality and consistency of the report.

.

1.2 Scope and Criteria

The scope of verification for this project activity involves assessing the claims made by the project proponent in the monitoring report^{/6/}, emission reduction calculation sheet and other supporting evidence (as mentioned in appendix 2) made available to the verifier for this monitoring period from 01/01/2023—31/12/2023, in accordance with:

- VCS standard, V4.7^{/1/}
- VCS program guideline, V4.4^{/2/}
- CDM Methodology^{/5/} from Sectoral Scope 1 – ACM0002: Grid-connected electricity generation from renewable sources Version 20.0
- Registered PDD^{/4/}

- Other relevant rules and requirements, including host part requirements.

A risk-based approach has been followed for the verification of the project activity. Identifying and assessing the high-risk area and ensuring the reliability of the project's emission reductions generated.

The principles of accuracy, completeness, relevance, reliability and credibility were combined with a conservative approach to establish a traceable and transparent verification opinion. The verification considers both quantitative and qualitative information on emission reductions. The verification is not meant to provide any consultancy towards the client. However, stated requests for clarifications, corrective and/or forward actions may provide input for improvement of the monitoring activities.

.

1.3 Level of Assurance

The verification of the project activity is conducted by doing a thorough assessment of Monitoring report^{6/}, Registered PDD^{4/} emission reduction calculation sheet^{7/} and all the relevant documents mentioned technical documents^{19/}, Calibration^{18/} and commissioning certificate^{12/}, DGR^{10/}, power purchase agreement^{20/}, monthly invoices^{21/} (as mentioned in appendix 2) of the report.

The level of assurance achieved for the project verification falls under a reasonable level of assurance. A reasonable level of assurance is a high level of assurance regarding material misstatement, but not an absolute one.

Enough evidence were gathered by the assessment team during onsite visit to reduce the risk associated with the audit process.

.

1.4 Summary Description of the Project

The project "Blitta – Togo Solar Power Plant " mainly involves the operation of two solar photovoltaic plant located in Blitta-Losso village. The plant operates in 2 phases i.e. Phase 1 - 50 MW commissioned on 12/06/2021 which is crosschecked onsite visit and with previous verification report^{24/} and Phase 2- 20MW commissioned on 05/02/2024 as verified on site^{8/} and commissioning certificate^{12/}. 77,751.00 MWh of electricity is generated by the plant with the average of 6,481.26 MWh/month of electricity produced by the project activity and reduced 44,551 tCO₂e for the current monitoring period.

The primary purpose of the project is to supply reliable, clean electricity to hundreds of thousands of homes and businesses in the country via the national grid substituting grid electricity and to cut down GHG emissions from baseline fossil fuel intensive grid mix. The same has been verified during onsite visit^{/8/} The commissioning certificate^{/12/}, monthly energy generation statement^{/10/21/} are reviewed by the assessment team and are found to be appropriate. The verification team has conducted site visit and verified the actual photographs of the project equipment's and monitoring arrangements. The project activity was found to be implemented as it has been defined in the MR in line with registered PDD^{/4/} and same was verified during onsite visit^{/8/}

Onsite audit^{/8/} for the project activity was conducted on 01/08/2024 and Interviews of the PP along with its representatives were conducted onsite to confirm the implementation of the project activity. Furthermore, it was confirmed that the project involves supply of 77,751.00 MWh of electricity during the current monitoring period 01/01/2023 to 31/12/2023, leading to 44,551 tCO₂e emission reductions. The information verified onsite was found to be in line with the submitted monitoring plan^{/6/}, ER sheet^{/7/} and other documents mentioned in the appendix 2 of the report.

The start date of the project activity is 12/06/2021, verified from the onsite audit from the commissioning of phase 1 of the project^{/8/} and the same has been cross checked with Validation report ^{/22/} and previous verification report. The crediting period for the project activity is 12/06/2021 to 11/06/2028. (renewable, 7 years), as verified using previous verification report^{/24/} and the project page on VERRA^{/3/}.

Based on this, the assessment team confirms that the project activity "VCS-3298" is implemented and operational in accordance with applied methodology "ACM0002 Version 20.0"^{/5/}, Project Description Document^{/4/}, VCS standard^{/1/} and VCS guidelines^{/2/}. It has also been assessed and verified that emission reduction calculation for this monitoring period from 01/01/2023 to 31/12/2023^{/6/} has been done conservatively and found to be appropriate (details can be found in section 4 of this report). Thus, a reasonable level of assurance has been met

2 VERIFICATION PROCESS

The Registered Project activity has been undergoing 2nd Verification under its renewable crediting period (7 years), the approach adapted to ensure the quality and credibility of emission reduction is described in the following sections.

2.1 Method and Criteria

The method and criteria used for verification consist of the following phases.

A risk-based approach has been applied for the process.

Desk review:

A document review of the monitoring report^{/6/} emission reduction calculation sheet^{/7/} and other evidence like electricity generation reading^{/10/} and invoice^{/21/}, commissioning certificate^{/12/}, O & M Chart^{/13/}, meter calibration certificate^{/18/}, DGR^{/10/} documents were strategically reviewed, and risk assessment was undertaken. QA/QC procedures and other relevant documents mentioned in appendix 2 of the report are verified.

Onsite Visit:

- An onsite audit^{/8/} for the project was conducted on 01/08/2024.
- Interview of the project representatives and to confirm the implementation and operational status of the project with respect to the registered monitoring plan^{/4/}.
- Review the data flow for generating, aggregating and reporting the monitoring parameters,
- Confirm the correct implementation of procedures for operations and data collection,
- Cross-check the information provided in the MR documentation with other sources,
- Check the monitoring equipment against the requirements of the PD and the approved methodology, including calibrations, maintenance, etc.,
- Review the calculations and assumptions used to obtain the GHG data and ER,
- Identify if the quality control and quality assurance procedures are in place to prevent or correct errors or omissions in the reported parameters.

Further, details regarding the process of onsite audit have been mentioned in section 2.3 and 2.4 of the report. Resolution of all the issues and findings raised, and the final verification statement was issued.

2.2 Document Review

As part of verification of the project, the primary activity performed was the strategic review and risk assessment of the documents submitted using a dedicated protocol. A detailed review of MR^{/6/} and ER sheet^{/7/} was done to check:

The completeness of the information with reference to the register PDD^{/4/}.

Review of project information, monitoring plan specifically monitoring frequency, the metering equipment calibration requirement, quality assurance and quality control system against the registered PDD, V7.0 and applicable VCS standard^{/1/} and applied methodology “ACM002 Version 20.0”^{/5/}.

A review of the QA/QC procedures were conducted to make sure the implementation is as per the register PDD^{/4/}.

All the other evidence reviewed are mentioned in Appendix 2 of this report. The cross checks between information provided in the Monitoring report^{/6/}, VCS PDD^{/4/} and information from sources other than those used, if available, the team’s sectoral or local expertise and, if necessary, independent background investigations

2.3 Interviews

In accordance with VCS standard, V4.7^{/1/}, site visit requirements, “A site visit that includes a visit to facilities and/or project areas shall be conducted at verification under the following circumstances: 1) The first verification of the project after validation; 2) Verifications that include project baseline reassessments; and 3) Verifications that assess a project description deviation where the deviation impacts the applicability of the methodology, additionality or the appropriateness of the baseline scenario.” The project was currently undergoing 2nd verification and it was the first time for SustainCERT to conduct the verification of this project. Therefore, a site visit was conducted during this verification on 01/08/2024^{/8/}. During the on-site audit interview of the relevant project personnel were conducted verifying the implementation and operational status of the project, the similar information was also cross verified using the evidence submitted by PP (as mentioned in appendix 2 of the report). Details of the personnel interviewed can be found in the table below.

This site visit was carried out to do the following:

1. Assess the design/operation of the Project.
2. Interview personnel regarding the Project operation and data collection procedures.
3. Cross check reported information with evidence observed on site.

Table 1: Personnel/Stakeholders Interviewed

S.No	Interviewee Name	Role and responsibility	Topic discussed
------	------------------	-------------------------	-----------------

1	Hervé Rioux	Site Director	Project implementation, Commissioning dates, Reliability and accuracy of readings are considered for emission reduction calculations, calibration procedure Monitoring, and measuring system. Collection of measurements Observations of established practices for verification of monitoring parameters, Electricity generation records (Monthly Energy Statements, Invoices) Emission reduction calculation, environmental concerns, entities involved, property rights, benefit sharing
2	Raouf Damtare	QHSE Manager	Stakeholder consultation, environmental aspect of project, grievance mechanism, employee wellbeing, ecosystem health, commissioning of project
3	Amavi Emefa Yao	Social Impact Manager	
4	Thierno Okongou	HSE for 20MW site (replacing the HSE for	

		50MW that was not available)	
5	Mr. Pramod Reddy SUNKIREDDY	Responsible for Site Monitoring	Stakeholder consultation, environmental aspect of project, grievance mechanism, employee wellbeing, ecosystem health, commissioning of project
6	Mr KOUSSANTA Bougoundjoma	Director of high School Lyc'ee de Blitta Carrefour (Stakeholder)	Stakeholder consultation, environmental aspect of project, grievance mechanism, employee wellbeing, ecosystem health, commissioning of project, Sustainable development goals
7.	M.MOUSSA Djorkpa	Director of NGO CARD (stakeholder)	stakeholder consultation, environmental aspect of project, grievance mechanism, employee wellbeing, ecosystem health, commissioning of project, Sustainable development goals

The local stakeholder interviewed are the local people. It was mentioned to assessment team by the local people that one borehole was constructed in the village Blitta Gare. Interviewee further added reforestation of 120ha has been done by AMEA

By the interview it was concluded that the local people were aware of the grievance mechanism and there were no negative comments from local stakeholder's side. Instead, the local people appreciated the development and job created by the project. During the onsite visit it was observed that grievance mechanism was well in place and no negative comments were received from the local stakeholder. Appendix 6 has the photographs of the onsite visit. Thus, a reasonable level of assurance was met.

2.4 Site Visits

As Discussed above, the physical site visit for the project was conducted for the current verification. Details and description of areas assessed can be found below:

Date of the Audit: 01/08/2024

S.No	Activity performed	Source for Cross Verification	Assessment Opinion
1	The assessment of the implementation and operation of the registered project activity	Registered PDD ^{/4/} and Validation and verification report Interviews with PP ^{/8/}	The information mentioned with reference to project implementation, capacity and commissioning in MR is found consistent with the documents and information seen onsite.
2	A review of information flows for generating, aggregating and reporting the monitoring parameters.	DGR ^{/10/} and monthly invoices ^{/21/} Interviews with PP ^{/10/}	The information related to flows for generating, aggregating and reporting the monitoring parameters mentioned in MR. electricity records as per DGR is lesser than the electricity invoice. CL#9 to clarify the difference was raised and resolved. PP has added relevant justification under section 4.2 this is found to be inline with the information on-site received by interviews.
3	Interviews with relevant personnel to determine whether the operational and data collection procedures are implemented in accordance with the monitoring plan in the PD	DGR ^{/10/} and HS audit reports ^{/16/}	HS Audit reports and DGR are being cross checked. All the information related to operational and data collection is found to be inline with the PDD ^{/4/} and MR ^{/6/} .

4	A check of the monitoring equipment including calibration performance and observations of monitoring practices against the requirements of the PDD, the applied methodology including the tools applied	Calibration records ^{/18/} Interviews with PP ^{/8/}	Calibration records were verified, and monitoring practices were verified with interview from PP, and it has been observed calibration takes place annually, last calibration was delayed by 33 days hence that was accounted while calculating ERs for the monitoring period under verification as per the practice in line with the PDD ^{/4/} more details can be found in section 4 of the report.
6	A review on calculation of emission reductions	DGR ^{/10/}	Values mentioned for ER calculation are found to be in line with the DGR and delay in calibration of the meter is already accounted in calculation. Methods, formulae, and emission factors for calculating baseline emissions have been followed in accordance with the applied methodology ^{/5/} .
7	An identification of quality control and quality assurance procedures in place to prevent or identify and correct any errors or omissions in the reported monitoring parameters	DGR ^{/10/}	Methods, formulae, and emission factors for calculating baseline emissions have been followed in accordance with the applied methodology ^{/5/} . All the QA/AC procedures were also verified on-site.

The onsite audit for the plant was conducted and all the documents were crosschecked (enlisted in appendix 2) and team interacted with the personnel and the stakeholders. Outcome of the site visit was recorded in onsite visit report along with photographic evidence. ^{/8/}

The assessment team has verified all the primary supporting related to operations, quality, and generation of data during the monitoring period like invoices raised by PP, calibration details, interview with onsite persons etc. The photographs were only used as means of secondary cross check of the information verified from Primary sources. The information regarding project capacity commission and monitoring system are also cross checked with previous reports^{/24/}. Thus, a reasonable level of assurance is achieved.

2.5 Resolution of Findings

As discussed above, a risk-based approach has been applied for the verification of the project activity. During the verification, assessment team identified the issues which could impact the accuracy, and the credibility of the emission reduction claimed by the project, The details analysis of the issues raised the approach used to resolve these issues can be found in Appendix 4 of this report.

A corrective action request was raised if:

Modifications to the implementation, operation, and monitoring of the registered project activity have not been sufficiently documented by the project participants.

Mistakes have been made in applying assumptions, data, or calculations of emission reductions that will impact the number of emission reductions.

A clarification request was raised if:

information is insufficient or not clear enough to determine whether the applicable requirements have been met.

A Forward action request was raised if:

if the monitoring and reporting require attention and/or adjustment for the next verification period.

During verification a total of 06 CARs, 11 CLs. The details of all the issues communicated to the PD can be found in Appendix 4. The issues raised were closed successfully. 00 FARs is raised for next verification.

2.5.1 Forward Action Requests

No FAR is raised for the current monitoring period

2.6 Eligibility for Validation Activities

There is no validation activity undertaken as a part of current verification.

3 VALIDATION FINDINGS

NA, no such activity performed.

3.1 Methodology Deviations

There is no methodology deviation identified during the current monitoring period.

3.2 Project Description Deviations

No project description deviations have been applied to the grouped project activity during the reported monitoring period.

3.3 New Project Activity Instances in Grouped Projects

The project is not a group project.

3.4 Baseline Reassessment

Did the project undergo baseline reassessment during the monitoring period?

☐ Yes

☒ No

4 VERIFICATION FINDINGS

4.1 Project Details

The Project Implementation was checked in the following manner:

The project activity involves operation of Solar power project of 70 MW in the Blitta-Losso village, part of the Blitta canton. The project is operational in 2 phases. First phase of the project is of 50MW capacity and was commissioned on 12/06/ 2021^{124/8/}. Second phase of the project is of 20 MW which was commissioned on 05/02/2024^{12/} as verified onsite and from commissioning certificates. During the onsite visit, it is found that the project is running satisfactorily as per the plan mentioned in PD. The commissioning certificates of the project activity and generation records are verified by the verification team and during onsite visit. The project activity is undergoing 2nd verification from 01/01/2023 to 31/12/2023, and during this Monitoring period the project activity has delivered 77,751.00 MWh of electricity and reducing 44,551 tCO₂e emission reductions.

The details and calculations of the emission reductions have been verified and are found to be as per the guidelines of the applied methodology ACM0002, v 20.0^{/5/}, the version of methodology is online with PDD^{/4/}, previous verification report and guidelines mentioned in VCS standard^{/1/}. The input values used for monitoring parameters were also cross checked against the DGR^{/10/} provided by the PP to the assessment team. It has been verified that all the DGR and values are same across the documents. The required monitoring system is in place and operational, the same was verified during the onsite audit^{/8/}. The accuracy class of the meters installed for the project activity was verified on-site^{/8/} and using photographic evidence submitted^{/8/}.

During the on-site audit, it was concluded that the project is implemented as per monitoring plan^{/6/}. During the current monitoring period, it was observed that no unforeseen incident or event evolved which can impact the operation of the project activity and this was also verified using DGR reports^{/10/} and HS Audit reports^{/16/}, submitted by the Project proponent.

Element 6 – FZCO is other entity involved in the project and is responsible for analysis, aggregation, preparation (conversion factors, assumptions, methodology, calculations) and presentation of activities and related GHG data in its public disclosures (including but not limited to monitoring report, emission reduction calculation sheet, submitted documents/ emails/ communications) and same has been verified onsite^{/8/}

Monitoring Procedure:

During on-site audit^{/8/}, It has been verified that PP is responsible for Ongoing operation of project activity It was also confirmed that calibration of meter was done by the qualified personal inline with meter manufacture specification, further details related to calibration can be found in section 4.4 of the report.

Item	Evidence gathering activities, evidence checked, and assessment conclusion:
Audit history	The project activity is undergoing 2nd Verification under its twice renewable crediting period. The assessment team has verified that audit history using the Project webpage ^{/3/} , all the previous verification has been published under Verra. It has been concluded that the information present in section in 1.2 of MR is appropriate
Double counting and participation under other GHG programs	The project activity is not registered under any other GHG and non-GHG program or registry. This has been confirmed by means of research on relevant applicable registries and available information in public domain and through declaration from the Project Owner.

	The assessment team has searched for similar projects having the same nature, capacity and project proponent as well as legal owner. The name of the owners mentioned in the regulatory licenses are also matched and checked. It was concluded that no such projects having same location and geo-coordinates, technology or project/legal owners are registered in various carbon schemes like CDM, GCC, and Gold Standard. CL #2 was raised and closed upon document verification by VVB. ^{/14/}
No double claiming with emissions trading programs or binding emission limits	The project activity has been thoroughly searched on the various websites of various emission trading programs and or ETS programs running in various counties, using nature, capacity and project proponent as well as legal owner as the search option.
No double claiming with other forms of environmental credit	As discussed above the, the project has been thoroughly searched in the currently active environment schemes and found that the project is not registered with any other environmental credits. Therefore, it can be concluded that the project is not claiming any credits from other programs/schemes.
Supply chain (scope 3) emissions double claiming	The project activity aims at operation of solar power plants and does not result in any Scope 3 emissions in its supply chain^{/14/}.
Sustainable development contributions	As claimed in section 1.12 of the monitoring report^{/6/}, the project is claiming positive impact for the following: SDG 8 - 13 jobs in total were created during the operation solar power plant. VVB has verified the O & M chart ^{/13/}. SDG 7 impact is 77,751.00^{/10/} MWh of renewable energy delivered to national grid during this second monitoring period^{/20/}. Documents have been verified and found appropriate for the SDG 7. SDG 3 impact is implemented activities to increase Number of patients visiting the constructed clinic per year. PP has submitted monthly patient visit records in response to CL#4. Documents have been verified during onsite visit and found appropriate for SDG 3^{/11/}

	SDG 4 impact is impact is implemented activities to increase Number of students going to primary school annually. VVB has reviewed the datasheet of students enrolled in school and photographic evidence of project CSR activities against CL#5 and CL#4 and found appropriate for SDG 4^{/11/}. SDG 13 impact is claimed through the emission reduction calculated by the project implementation which is 44,551 tonnes of carbon dioxide avoided into the atmosphere during this second monitoring period.
Additional information relevant to the project	No commercially sensitive information has been excluded by the PP.

4.2 Safeguards and Stakeholder Engagement

4.2.1 Stakeholder Identification

PP has confirmed that no comments have been received from the local stakeholders during the reported monitoring period. Local stakeholder consultation has been carried out for the project activity at the time of the project validation and found appropriate.

The Verification team confirms that the local stakeholder consultation conducted meets the requirements as provided. ^{/22/}

PP has also provided for a continuous stakeholder engagement record for the project activity in appendix 3 of the MR. During the reported monitoring period (01/01/2023—31/12/2023), no major comments were received from local stakeholders.

Item	Evidence gathering activities, evidence checked, and assessment conclusion
Stakeholder identification	It has been observed and verified during on-site audit that the project activity is in line with the monitoring plan ^{/6/} and there has been no new stakeholder identification done.
Legal or customary tenure/access rights	It has been observed and verified during on-site audit that the project activity is in line with the monitoring plan ^{/6/} and there are no new legal or customary access right.

Stakeholder diversity and changes over time	It has been observed and verified during on-site audit that the project activity is in line with the monitoring plan ^{/6/} and also personnel and stakeholders were interviewed during onsite audit (details of which are mentioned in section 2.3 of report) and it can be concluded that there is no change in stakeholder diversity over project lifetime till now.
Expected changes in well-being	It has been observed and verified during on-site audit that the project activity is in line with the monitoring plan ^{/6/} and also stakeholders were interviewed during onsite audit (details of which are mentioned in section 2.3 of report) and it can be concluded that there is no expected change Wellbeing of stakeholder.
Location of stakeholders	It has been observed and verified during on-site audit that the project activity is in line with the monitoring plan ^{/6/} and there is no change in the location of stakeholders.
Location of resources	It has been observed and verified during on-site audit that the project activity is in line with the monitoring plan ^{/6/} and no change in location of resources.

4.2.2 Stakeholder Consultation and Ongoing Communication

Item	Evidence gathering activities, evidence checked, and assessment conclusion
Ongoing consultation	During onsite audit^{/8/}, interviews with personnel and local stakeholders were conducted, details of which can be found in section 2.3 and 2.4. During the interview it was concluded that PP has a direct communication channel and stakeholders can visit during office hours for any grievances. PD has a detailed Grievance procedure that is followed on-site, the assessment team has verified the details mentioned onsite and it is found to be in line with the PDD^{/5/}. It has been observed that there have been no major comment/ grievances received from stakeholders during this MP.
Date(s) of stakeholder consultation	Stakeholder consultation was conducted on 05/07/2022 and, it has been verified from the registered PDD ^{/5/} .
Communication of monitored results	Results of the original meeting were provided and are also stored, during the current monitoring period there has been no new major

	comments received as verified onsite and from stakeholder engagement log under appendix 3 of the MR.
Consultation records	There have been no new major comments received during the current monitoring period, this has been verified by the details checked during onsite audit, All comments/ complaints are registered by PP using a stakeholder engagement logs.
Stakeholder input	During Onsite audit ^{/8/} , interviews with local stakeholders were conducted, details of which can be found in section 2.3 and 2.4. Based on the interview conducted, it has been concluded that all the procedures are implemented in line with registered monitoring plan ^{/6/} and there is proper procedure in place for stakeholder engagement logs.

4.2.3 Free, Prior, and Informed Consent

Item	Evidence gathering activities, evidence checked, and assessment conclusion
Consent	As per ESIA report ^{/15/} , none of the different stakeholders rejected the project. During this monitoring period, there was no unresolved conflict, and this was verified during on-site project audit through personnel and stakeholders' interviews.
Outcome of FPIC discussion	There is no concern. Therefore, no FPIC required.

4.2.4 Grievance Redress Procedure

Item	Evidence gathering activities, evidence checked, and assessment conclusion
Grievance received and steps taken to resolve the grievance including the outcomes of the resolution	During onsite audit ^{/8/} , interviews with personnel and local stakeholders were conducted, details of which can be found in section 2.3 and 2.4. During the interview it was concluded that the grievance mechanism is publicized at the site gate, at the Local Community Chief's Offices, and at the Project Company's website. All information about grievance procedures and grievance registers kept on site in English, but grievances forms can be filled in French.

	PD has a detailed Grievance procedure that is followed on-site, the assessment team has verified the details mentioned onsite and it is found to be in line with the PDD ^{/5/} . It has been observed that there have been no comment/ grievances received from stakeholders during this MP.
Grievance redress procedure	It has been observed that there have been no major grievances received during this monitoring period, therefore, not applicable.

4.2.5 Public Comments

Comments received	Actions taken by the project proponent	Evidence gathering activities, evidence checked, and assessment conclusion
No comments were received.	No action were taken as no comments were recieved	The assessment team has verified the solar power plant records and interviewed various personnel to confirm if any comments were received. Furthermore, positive feedback was received as the project has provided job opportunity to the local people and because of plant local areas have access to clean energy, this was verified by interviewing personnel and stakeholders more details can be found under section 2.3 and 2.4 of the report.

4.2.6 Risks to Local Stakeholders and the Environment

4.2.6.1 Management Experience

Separate team has been designated to carry out various process in the project activity verification team has verified roles and responsibilities^{/13/} of the project personnel.

The management structure has 3 levels-

1. Solar Plant manager
2. VCS Project Manager
3. VCS Staff

As confirmed during the site visit, VCS project manager is responsible for data monitoring and management associated with the project activity. Annual trainings^{/17/} is provided to local operation staff and VCS designated staff. During onsite^{/8/} visit, verification team has verified relevant project experience of the project proponent.

4.2.6.2 Risk Assessment

Item	Evidence gathering activities, evidence checked, and assessment conclusion
Natural and human induced risks to stakeholders' wellbeing	During the onsite visit ^{/8/} interview with of the personnel and stakeholders was conducted. No risk due to nature or human to stakeholder wellbeing is identified.
Risks to stakeholder participation	During the current verification, onsite audit ^{/8/} was conducted, interview with of the personnel and stakeholders was conducted, it has been observed that grievance redressal procedure is in place, and there are no new comments received. Therefore, it has been concluded that there has been no risk to participation
Working conditions	During the current verification, an onsite audit ^{/8/} was conducted, interview with of the stakeholders and personnel was conducted, stakeholders interviewed received job due to development of project and it has been observed from the interview that working conditions are well balanced for people. Therefore, it can be concluded that working conditions are appropriate for the employees, ESIA ^{/15/} report has been submitted by PP.
Safety of women and girls	During the current verification, an onsite audit ^{/8/} was conducted, an interview with several stakeholders and personnel was conducted, and it was observed that the project does not cause any harm to women and girls, EIA ^{/15/} report has been submitted. Moreover, all women working on site have their own safety kits. Also, the code of conduct with zero tolerance of any kind of discrimination and specifying to address GBVH was made available to ensure safety at workplace.
Safety of minority and marginalized groups, including children	During the current verification, onsite audit ^{/8/} was conducted, interview with the stakeholders and project personnel was conducted, and it was observed that project does not cause any harm to minority, marginalized groups including children.

Pollutants (air, noise, discharges to water, generation and release of hazardous materials and chemical pesticides and fertilizers)	Site visit was conducted, and it was confirmed during interview with personnel that dry cleaning of PV panels is done. The project activity is Solar power project, hence a renewable project, hence does not cause any harm to the environment, however, PP has a monitoring system in place. CL#7 was raised and successfully resolved where PP submitted a comprehensive waste and wastewater management plan which is developed outlining the procedures for effective waste management ^{/23/} . A detailed environmental impact assessment ^{/15/} report has also been submitted by the PP, which has been verified by the assessment team.
---	--

4.2.7 Respect for Human Rights and Equity

4.2.7.1 Labor and Work

Item	Evidence gathering activities, evidence checked, and assessment conclusion
Discrimination	During the current verification, onsite audit ^{/8/} was conducted, interview with of the stakeholders was conducted it was confirmed that there is no Discrimination with any employee on site.
Sexual harassment	During the current verification, onsite audit ^{/8/} was conducted, interview with of the stakeholders was conducted it was confirmed that there is no sexual harassment with any employee on site.
Gender equity in labor and work	During the current verification, onsite audit ^{/8/} was conducted, interview with of the personnel and stakeholders was conducted and it has been observed that women and men are both part of the team. The PP has provided the organization and management chart and details regarding employment of both genders has been confirmed. The project also created indirect jobs where women are also employed ^{/13/} .
Forced labor	During the current verification, onsite audit ^{/8/} was conducted, interview with of the personnel and stakeholders was conducted and it has been confirmed that there is no case of forced labor.
Child labor	During the current verification, onsite audit ^{/8/} was conducted, interview with of the personnel and stakeholders was conducted and it has been confirmed that there is no case of Child labor.

Human trafficking	During the current verification, onsite audit ^{/8/} was conducted, interview with of the personnel and stakeholders was conducted and it has been confirmed that there is no case of Human trafficking.
-------------------	--

4.2.7.2 Human Rights

Risks identified	Evidence gathering activities, evidence checked, and assessment conclusion
Human Rights	During the current verification, onsite audit^{/8/} was conducted, interview with of the personnel and stakeholders was conducted and it has been confirmed there has been no situation related to violation of human rights at the project site. This has also been verified from previous verification^{/24/}

4.2.7.3 Indigenous Peoples and Cultural Heritage

Risks identified	Evidence gathering activities, evidence checked, and assessment conclusion
Preservation and protection of cultural heritage	During the current verification, an on-site audit^{/8/} was conducted, interview with the stakeholders was conducted it was confirmed that there was no harm to the cultural heritage at the project site. It was also confirmed by reviewing the ESIA report^{/15/}

4.2.7.4 Property Rights

Risks identified	Evidence gathering activities, evidence checked, and assessment conclusion
Disputes over rights to territories and resources	During the current verification, an on-site audit^{/8/} was conducted, interview with the stakeholders was conducted it has been observed and confirmed that there has been no dispute over territories and resources project.
Respect for property rights	During the current verification, an on-site audit^{/8/} was conducted it was observed and confirmed that the project site land owned by Government.

4.2.7.5 Benefit Sharing

Item	Evidence gathering activities, evidence checked, and assessment conclusion
Summary of the benefit sharing plan	During the current verification, an on-site audit ^{8/} was conducted, interview with the stakeholders was conducted and it has been confirmed that there is no benefit sharing as it's a solar power plant project.
Benefit sharing during the monitoring period	As per discussion during the on-site audit, it is confirmed that benefit sharing is not applicable here.

4.2.8 Ecosystem Health

Item	Evidence gathering activities, evidence checked, and assessment conclusion
Impacts on biodiversity and ecosystems	The project activity is Solar power project, hence a renewable project, hence does not cause any harm to the biodiversity and environment, however, PP has a monitoring system in place
Soil degradation and soil erosion	As this is a solar power plant there has been no risk identified to soil. ESIA ^{15/} report has also been submitted for the project.
Water consumption and stress	As this is solar power plant there has been no risk identified to water consumption. ESIA ^{15/} report has also been submitted for the project

4.2.8.1 Rare, Threatened, and Endangered species

Item	Evidence gathering activities, evidence checked, and assessment conclusion
Species or habitat	As this is a solar power plant there has been no risk to endangered species. ESIA ^{15/} report has also been submitted for the project. Therefore, it can be concluded that there is no threat to Rare, Threatened and endangered species.

Evidence gathering activities, evidence checked, and assessment conclusion
--

Habitats for rare, threatened, and endangered species	Not applicable, As this project involves operation of solar power plant
Areas for habitat connectivity	Not applicable, As this project involves operation of solar power plant

4.2.8.2 Introduction of Species

N/A. The nature of the project implementation is through construction and operation of solar power plant. As per the Environmental impact study, project activity does not involve introduction of species in its implementation

Species introduced	Evidence gathering activities, evidence checked, and assessment conclusion
Not applicable	Not applicable, As this project involves operation of solar power plant

Existing invasive species	Evidence gathering activities, evidence checked, and assessment conclusion
Not applicable	Not applicable, As this project involves construction and operation of solar power plant

Evidence gathering activities, evidence checked, and assessment conclusion	
Invasive species	Not applicable, As this project involves construction and operation of solar plant

4.2.8.3 Ecosystem conversion

Item	Evidence gathering activities and evidence checked
Ecosystem conversion	Not applicable, as the project is Solar power project.

4.3 Accuracy of Reduction and Removal Calculations

The assessment team has verified the values and formulas that are used for the calculation of emission reduction for this monitoring period from 01/01/2023 to 31/12/2023 (both days included). In details assessment of all these values can be found in section 4.4 of the report.

The equations and calculations used in the project report are in line with the applied methodology^{/5/} 'ACM0002 Version 20.0.

A detailed assessment of ex-ante values has been done in section 4.4 of the report.

The monitoring period for which GHG emission reductions were achieved spans 01/01/2023 to 31/12/2023. Baseline emissions are calculated according to §4.1 methodological approach as the product of (i) the quantity of net electricity generation that is produced and fed into the grid as a result of the implementation of the project activity in year y ($EG_{facility,y}$ = Exports , in MWh/yr) and (ii) the combined margin CO2 emission factor for grid connected power generation in year y ($EF_{grid,CM,y}$):

$$BE_y = EGPJ_{,y} \times EF_{grid,y}$$

Where:

BE_y , Baseline emissions in year y (t CO2)

$EGPJ_{,y}$, Quantity of net electricity generation that is produced and fed into the grid as a result of the implementation of the CDM project activity in year y (MWh)

$EF_{grid,CM,y}$, Combined margin CO2 emission factor for grid connected power generation in year y calculated using the latest version of the "Tool to calculate the emission factor for an electricity system" (t CO2/MWh)

$EGPJ_{,y}$ = $EG_{facility,y}$ i.e. the quantity of net electricity generation supplied by the project plant to the grid, as monitored and displayed below on a monthly basis.

$$EF_{grid,CM,y} = 0.573 \text{ tCO}_2/\text{MWh}$$

During this second monitoring period, at solar power plant, the project reduced GHG emissions by 44,551 tCO_{2e} .

No project emissions are considered as the project activity only involves renewable electricity generation from the solar power plants. Hence, according to ACM0002 $PE_y = 0$

As stated in the applicable methodology^{/5/}, no leakage emissions are considered, therefore $LE_y = 0$

The assessment team has thoroughly verified the calculation done for the quantification of the emissions reduction for the project activity, under this monitoring period from 01/01/2023 to 31/12/2023 (both days included),

Calibration frequency and energy meter specifications is verified through calibration certificates^{/18/} and further verified through monthly generation records^{/10/} and found consistent. Responsibility of calibration and maintenance of energy meters is solely under control of AMEA Togo Solar; this is verified through the PPA.^{/20/}

Calibration frequency for Energy meters yearly as per manufacturer's specification. During the on onsite visit ^{/8/} VVB has verified the calibration records submitted by PP and registered PDD that there was delay in the calibration of the meter by 33 day and the error of 0.297% which is above the maximum permissible error $\pm 0.2\%$ for 0.2S class meters ^{/18/} has been accounted as per 'CDM validation and verification standard for project activities', 366(a) & (b) and now all the meters were found to be in line with the claims made by PP. The installation and working conditions of the meters were checked during the site visit, calibration certificates and were found to be satisfactory. Calibration certificates ^{/18/} are verified and confirmed that accuracy of monitoring instruments is valid ^{/10/} for the entire range. Hence, the calibration frequency is in line with the monitoring plan as outlined in the registered PDD ^{/4/}.

CL#10 was raised and successfully closed upon of meter calibration certificate and ER sheet submitted by Project proponent.

It can be concluded that the calculation done is in line with methodology and is accurate achieving appropriate conservative approach.

4.4 Quality of Evidence to Determine Reductions and Removals

The data and parameters recorded for the project are in compliance with the registered PDD ^{/4/} and the monitoring report. Assessment team has cross checked all the parameters that are used for the calculation of the emission reductions against the evidence such as invoices ^{/21/} and DGR report ^{/10/}, provided by the PP, it has been observed that all the sources provided are appropriate and can be accepted.

The monitoring done for all the parameters are in line with the applied methodology ^{/5/}, thus, can be considered accurate and acceptable. Additionally, during this verification an on-site audit was done for the project activity on 01/08/2024 ^{/8/}, information was also cross checked by means of interview, therefore it has been concluded that mechanism is effective and reliable.

The meters comply with appropriate quality standards applicable to the used technology. The accuracy class of the meters installed for the project activity was verified through on-site ^{/8/}.

The transfer of carbon rights and other supporting documents related to quality and maintenance were checked by the verification team during the onsite audit assessment to confirm the authenticity of the documents and to check the correctness of the calculation.

Verification team has reviewed carbon rights documents and confirms that carbon rights are solely owned by AMEA Solar Togo SAU ^{/25/}

The verification team can confirm that sufficient evidence is available for the whole monitoring period and the same is verifiable. During data analysis, it is clarified by PP operational solar power plant is maintained since commissioned and the relevant records have been verified by local expert. Verifier team evaluated the approach chosen by PP to be acceptable from the conservativeness principle as well while still meeting the requirement of the applied methodology^{/5/}.

The data and parameters fixed (ex-ante):

S.No	Parameter	Value	Means of verification
1.	EFgrid, Combined margin CO2 emission factor for grid connected power generation in year y	0.573 tCO2 / MWh	The value has been verified using the validation ^{/22/} Report, registered PDD ^{/4/} , verification report ^{/24/} The value 0.573 tCO2e/MWh is found to be appropriate.

The data and parameters monitored (ex-post):

Parameter: EGfacility,y, Total electricity produced by the Project Activity, including the electricity supplied to the grid and the electricity supplied to internal loads, in year y.

Means of verification	Measuring /Reading /Recording frequency	Continuous monitoring is done. DGR Report ^{/10/} are verified VVB
	Is measuring and reporting frequency in accordance with the monitoring plan and monitoring methodology? (Yes / No)	Yes, the monitoring frequency is in line with the monitoring plan ^{/6/} .
	Monitoring equipment	The energy meters of accuracy class 0.2s are installed ^{/18/} . Details can be found in calibration details.
	Is accuracy of the monitoring equipment as stated in the monitoring plan? If the monitoring plan does not specify the accuracy of the monitoring equipment, does the accuracy of the monitoring equipment comply with local/national standards, or as per the manufacturer's specification?	The accuracy of the monitoring requirement is as per the monitoring plan ^{/6/} .

		VVB team has checked the monthly electricity generation records of energy meters. PP has already addressed the correction in the ER calculation due to delay in annual calibration in the ER spreadsheet ^{/7/} and the same has been verified by VVB and is found accurate.
	Is the calibration of measuring equipment carried out by an accredited person or institution?	Calibration of the meters will be carried annually as per manufacturer specification. During onsite ^{/8/} visit all the meters were in line of the requirements stated in registered PDD ^{/4/}
	Is(are) calibration(s) valid for the whole reporting period?	While reviewing the registered validation verification report, it was observed that the assessment team has verified the calibration records. However, during the current i.e., 2nd verification, the PP provided supporting evidence of Calibration Certificate ^{/18/} . PP confirmed that there was delay in calibration of meters by 33 days and the error of 0.297% which is above the maximum permissible error $\pm 0.2\%$ for 0.2S class meters has already been accounted for ER calculation. VVB verified and confirmed that accuracy of monitoring instruments is now valid for the entire reporting period ^{/8/}
	How were the values in the monitoring report verified?	The values of the monitoring report were verified using DGR report ^{/10/} . Average net electricity generated ^{/10/} . value obtained is 6,481.26 MWh/month.

	If applicable, has the reported data been cross checked with other available data?	Yes, the report values have been crosschecked with DGR report ^{/10/} .
	Does the data management ensure correct transfer of data and reporting of emission reductions and are necessary QA/QC processes in place?	Yes, the data ensure correct transfer of data and reporting of emission reduction management. QA/QC processes are in place.
	In case project participants have temporarily not monitored the parameter, has either deviation?	N/A
Findings	CL#10 was raised and closed successfully.	
Conclusion	The assessment team concluded that the parameter has been monitored continuously and it line with the registered monitored plan^{/6/} and applied methodology^{/5/} Since 100% of data has been monitored and verified, the verification team can ascertain that the values used for the calculation of emission reduction are free from material errors.	

Calibration of meter-

S.No.	Meter Description	Serial Number	Accuracy Class	Make	2022 calibration	2023 calibration
1	Power Trafo.1 Main	56198213	0.2S	Landis+Gyr	25/10/2022	26/11/2023
2	Power Trafo.1 Check	56198214	0.2S	Landis+Gyr	25/10/2022	26/11/2023
3	Power Trafo.2 Main	56198215	0.2S	Landis+Gyr	25/10/2022	26/11/2023
4	Power Trafo.2 Check	56198216	0.2S	Landis+Gyr	25/10/2022	26/11/2023
5	Blitta feeder Main	56198203	0.2S	Landis+Gyr	25/10/2022	26/11/2023

6	Blitta feeder Check	56198217	0.2S	Landis+Gyr	25/10/2022	26/11/2023
7	Auxiliary Trafo. Main	56198221	0.2S	Landis+Gyr	25/10/2022	26/11/2023
8	Auxiliary Trafo. Check	56198222	0.2S	Landis+Gyr	25/10/2022	26/11/2023

In accordance with the manufacture specification as verified guidelines, meter calibration is required annually.

In accordance with Monitoring report a registered monitoring plan the calibration of the meter is under the control of AMEA SOLAR TOGO SAU, this has also been verified form PPA for the project. However, as the re-calibration is required annually, it has been observed the last test of the meter was performed on 26/11/2023, The calibration of the meters took place on 25-October-2022 in the previous year which was valid till 24 October 2023 whereas in 2023 calibration was done on 26-November-2023 this caused the delay of 33 days. the calibration error for this period is accurately accounted in the ER calculation as per 'CDM validation and verification standard for project activities', 366(a) & (b).

In accordance with the above details the verification team confirms that:

1. A complete set of data for the monitoring period was available for the monitoring period and the verification of each monitoring parameter is elaborated under this of this report.
2. The complete monitoring data is also presented in the corresponding ER sheet^{/7/} and the final monitoring report^{/6/}.
3. The information provided in the monitoring report was cross checked with other sources, wherever appropriate and available, and such information is also included under this of this report.
4. The calculations of baseline emissions as presented in the corresponding ER sheet^{/7/} of final Monitoring Report^{/6/} were checked and found to be consistent with the formulae and methods described in the registered monitoring plan and the applied methodology^{/5/}.
5. All assumptions used in the emission calculations were found appropriate and therefore justified.
6. Appropriate emission factors and other reference values have been correctly applied.

The assessment team has verified the DGR (Daily generation report) document to conclude that the plant had a breakdown of 416 hours and 53 minutes and resulted in the loss of 969.18 MWh of energy. The same was confirmed onsite by interviewing the PP and its representatives. The reason for these breakdowns were due grid failure, transformer issues and shuts downs and grid availability. It was confirmed apart from this the project was working fine and has generated 77,751.10 MW throughout the monitoring period.

4.5 Non-Permanence Risk Analysis

The project activity is a Solar power project. Therefore, It is not applicable.

5 VERIFICATION OPINION

5.1 Verification Summary

The project activity VCS ID – 3298, “Blitta – Togo Solar Power Plant ” has undergone 2nd verification with monitoring period from 01/01/2023 to 31/12/2023 (including both days). AMEA SOLAR TOGO SAU is responsible for the overall site management. Element 6 – FZCO is responsible for analysis, aggregation, preparation (conversion factors, assumptions, methodology, calculations) and presentation of activities and related GHG data in its public disclosures (including but not limited to monitoring report, emission reduction calculation sheet, submitted documents/ emails/ communications). The verification engagement is based on the assumption that the GHG data provided to us is complete, sufficient, true and free from material misstatements.

SustainCERT applies its own quality management system and compliance policies for quality control, in accordance with ISO/IEC 17029:2019 – Conformity Assessment Requirements for Validation and Verification bodies providing environmental information (ISO 14065:2020) and greenhouse gas audit (ISO 14064-3:2019) and certifications, and accordingly maintains a comprehensive system of quality control including documented policies and procedures regarding compliance with ethical requirements, professional standards and applicable legal & regulatory requirements.

We have complied with the VCS standard v 4.7^{/1/} and other requirements mentioned, during the verification engagement and maintained independence. SustainCERT was not involved in the preparation of any statements or reports or data except for this Verification Statement and Report. SustainCERT maintains complete impartiality toward stakeholders interviewed during the verification process. SustainCERT did not provide any service PP's company and its subsidiaries in the scope of verification that could compromise the independence or impartiality of our work. SustainCERT disclaims any liability or co-responsibility for any decision a person or an entity would make based on this verification statement towards the issuance and utilization of VCUs hereby verified and certified. The verification was carried out during July 2024 – October 2024 by a team of qualified GHG auditors.

5.2 Verification Conclusion

The Verification of the project titled “Blitta – Togo Solar Power Plant ” VCS ID – 3298, have been undertaken by SustainCERT, as requested by ClimatePartner GmbH project proponent for the project, monitoring period 01/01/2023 to 31/12/2023 (including both days) as reported in latest submitted version of monitoring report The project activity is implemented in accordance with the registered monitored plan in PDD v07^{/4/}. It is our responsibility to express an independent verification statement on the reported GHG emission reductions from the project activity.

SustainCERT Verification approach was based on understanding the risk associated with reporting of GHG emission data and the controls in place to mitigate these. SustainCERT planned and performed the verification by obtaining evidence and other information and explanations that SustainCERT considered necessary to give reasonable assurance that reported GHG emission reductions are fairly stated.

In our opinion, the GHG emissions reductions reported for the project activity for the period 01/01/2023 to 31/12/2023 (including both days) are fairly stated in the latest submitted version of project monitoring report^{/6/}. The GHG emission reductions were calculated correctly based on the approved baseline and monitoring methodology^{/5/} ACM0002 Version 20.0 and the monitoring plan contained in the PDD^{/4/}.

Verification period: From 01/01/2023 to 31/12/2023

Verified GHG emission reductions and carbon dioxide removals in the above verification period:

Vintage period	Baseline emissions (tCO ₂ e)	Project emissions (tCO ₂ e)	Leakage emissions (tCO ₂ e)	Reduction VCUs (tCO ₂ e)	Removal VCUs (tCO ₂ e)	Total VCUs (tCO ₂ e)
01-Jan-2023 to 31-Dec-2023	44,551	-	-	44,551	-	44,551
Total	44,551	-	-	44,551	-	44,551

:

5.3 Ex-ante vs Ex-post ERR Comparison

Vintage period	Ex-ante estimated reductions/removals	Achieved reductions/removals	Percent difference	Explanation for the difference
01-Jan-2023 to 31-Dec-2023	70,468	44,551	-36.77%	The ex-ante emissions were calculated based on 70 MW. The current monitoring period accounts for 50 MW only as 20 MW phase is commissioned on 05 Feb 2024. The same has been verified during the onsite visit ^{8/} by the project verifier.
Total	70,468	44,551	-36.77%	

APPENDIX 1: COMMERCIALLY SENSITIVE INFORMATION

NA

<i>Section</i>	<i>Information</i>	<i>Justification</i>	<i>Assessment method and conclusion</i>
<u>NA</u>			

APPENDIX 2: TABLE OF REFERENCE

S. No	Document Title	Version	Date
1.	VCS standard https://verra.org/documents/vcs-standard-v4-7/	4.7	16/04/2024
2.	VCS guidelines https://verra.org/wp-content/uploads/2023/08/VCS-Program-Guide-v4.4.pdf	4.4	29/08/2023
3.	VCS Project Webpage, VCS ID - 3298 (https://registry.verra.org/app/projectDetail/VCS/3298)	-	-
4.	Project Design Document Version 7	6.0	21/07/2023
5.	Applied CDM Methodology ACM0002 (https://cdm.unfccc.int/UserManagement/FileStorage/2P7FS6ZQAR84LG3NMKYUH50WI9ODBC20)	-	-
6.	VCS Monitoring Report for monitoring period i.e., 01-January-2023 to 31-December-2023	Ver.4.0	07-November-2024
7.	241011_elementsix_Togo_Monitoring Period 2_v3.0., 01-January-2023 to 31-December-2023	Ver.3.0	11-October-2024
8.	Onsite visit by Sustain Cert auditor – Photographic Evidence and videos (01 August 2024)	-	-
9.	VCS Methodology Requirements	4.4	29/08/2023
10.	DGR	-	January 2023 to December 2023

11.	School and clinic documents	-	
12.	Commissioning certificate of phase 2	-	17/02/2021
13.	Organization and Management Chart	-	-
14.	Double accounting and double claiming self-declaration (240910_AMEA Togo Solar Letter)	-	
15.	Environmental Impact study (ESIA)	-	-
16.	HS Audit Report	-	-
17.	Training Records	-	
18.	Meter's calibration certificate	-	08/05/2016
19.	Technical specifications of PV modules in Solar Power Plant.	-	-
20.	Purchase power agreement for the Solar Power Plant	-	18/10/2019
21.	Monthly Electricity Generation invoice for the entire duration of the monitoring period i.e., 01-January-2023—31-December-2023	-	January 2023 to December 2023
22.	Validation Report (FVR_VCS_Validation_Togo_v2.1_24.03.23 - clean)		12/04/2023
23.	Waste Management plan	-	24/06/2024
24.	Verification report (FVR_VCS 3298.pdf)		15/08/2023
25.	Carbon Rights Document (ERPA Grid Connected Solar PV - Blitta Togo_MASKED)		07/04/2022

APPENDIX 3: ABBREVIATIONS

AFOLU	Agriculture, Forestry and Other Land Use
CDM	Clean Development Mechanism
GHG	Green House Gases
GCC	Global Carbon Council
MR	Monitoring report
PDD	Project Design Document
PD	Project description
PP	Project Proponent
QA/QC	Quality assurance/quality control
SDG	Sustainable Development Goals
VCS	Verified Carbon Standard
VVB	Validation/Verification Bodies

APPENDIX 4: PROJECT FINDINGS

Rule	Assessment Question	Findings/Comments CAR#1	Developer Response
VCS Standard & VCS MR Template	Does a summary description of the implementation status of the project, including the following (no more than one page) in section 1.1 of MR: - A summary description of the implementation status of the technologies/measures (e.g., plant, equipment, process, or management or conservation measure) included in the project, including relevant implementation dates (e.g., dates of construction, commissioning, and continued operation periods). - The total GHG emission reductions and carbon dioxide removals	- MR section 1.1: As stated “commissioning date of Phase 2 with the expansion of 20 MW was in February 2024” in section 1.1. of the monitoring report PP shall update the commissioning status as on date and submit the supporting evidence accordingly. - MR section 1.1: As stated “Togo's clean energy strategy, aiming to achieve a 50% renewable electrification share by 2025 and full transition by 2030” PP shall update the source of the stated information for verification by VVB. - In section 1.1 of the MR PP has claimed that solar power plant produced an average of 6,481.26 MWh/month of electricity for the given monitoring period whereas in the ER Sheet PP has considered Net energy generation DGR (MWh) for calculation of emission	- The commissioning date for phase 2 is added and the supporting evidence is submitted. - The source is already provided as a footnote. - The values are rechecked to ensure consistency.

	generated in the monitoring period	reduction. PP shall consistently apply an average MWh value for the current monitoring period.	
	Rd 2	1. PP has submitted DECLARATION DE CONFORMITE_2eme Extension à 70 MW_Centrale BLITTA which is regarding declaration of the conformity of the second extension of 50 MW solar power plant to total indstalled capacity of 70MW this is signed on 05 Feb 2024 and is found in line with the update done by PP under section 1.1 of the MR. The evidence submitted by PP is found in line with section 3.8 of the VCS standard v 4.7 #CLOSED 2. PP has provided the relevant footnote 2 which direct to the UAE ministry of foreign affairs news which is reviewed by VVB and found in line with the statement submitted under section 1.1 of the MR. #CLOSED 3. In section 1.1 of the MR PP has claimed that solar power plant produced an average of 6,481.26 MWh/month of electricity for the given monitoring period which is in line with average of column c i.e. Net Energy Generation- DGR (MWh)	

		in the ER sheet tab of the ER spreadsheet. #CLOSED	
--	--	---	--

Rule	Assessment Question	Findings/Comments CAR#2	Developer Response
VCS Standard & VCS MR Template	Does section 1.8 indicate the project location and geographic boundaries (if applicable) including a set of geodetic coordinates	MR section 1.8 figure-1: PP may update the site google map location figure based on current operational status of the 70 MW project.	The Google Maps location provided shows the most recent image of the plant, and the section has been updated to reflect the proximity of both phases.
	Rd 2	PP has updated section 1.8 of the MR to provide details about the locations of both the phases in line with section 3.11.1 of the VCS standard v 4.7. Justification submitted by PP is reviewed by VVB and is found to be acceptable. #CLOSED	

Rule	Assessment Question	Findings/Comments CL#1	Developer Response
VCS Standard v 4.7. & VCS MR Template	The project description shall be accompanied by one or more of the following types of evidence establishing project ownership accorded to the project proponent(s), or program ownership accorded to the	1. MR section 1.10: PP shall provide evidence of project ownership in accordance with VCS standard 4.7 section 3.7.1. This would include a carbon transfer rights agreement with the end users, and land ownership evidence (if	1. Masked copy of the agreement between AMEA and ClimatePartner is submitted. The name of project proponent is updated. 2. The mentioned documents are resubmitted.

	jurisdictional proponent(s), as the case may be. Is the project receiving or seeking credit for reductions and removals from a project activity under another GHG program. Was the project registered or seeking registration under any other GHG programs?	applicable). Agreement between AMEA power LLC and Climate Partner GmbH as both are enlisted as project proponent under section 1.4 of the MR. In addition to this, VVB has sighted discrepancy with the name of project proponent in registered PDD and MR of the current monitoring period. PP shall ensure the name of project proponent is inline with the registered PDD. 2. PP shall also provide the following evidence: • Carbon ownership document • Certificate of Completion signed by the Togolese Republic • Power Purchase Agreement (PPA) signed by PP and the Togolese Republic • Declaration of Conformity signed by the Togolese Republic • Entry into Force of the Concession Agreement signed by PP and the Togolese Republic • Back Energization of the PV Plant Document signed by the Togolese	
--	--	---	--

		Republic, the Electricity Off-taker and PP	
	Rd 2	1. PP has submitted ERPA Grid Connected Solar PV - Blitta Togo_MASKED that clearly defines the positions of AMEA and climate Partner in the project activity in accordance with VCS standard 4.7 section 3.7.1. In addition to this PP has updated the project proponent in line with the registered PDD under section 1.4 of the MR. #CLOSED 2. All the above stated documents are submitted by PP which are reviewed by VVB and are found satisfactory . #CLOSED	

Rule	Assessment Question	Findings/Comments CL#2	Developer Response
------	---------------------	------------------------	--------------------

VCS Standard v 4.7. & VCS MR Template	To maintain environmental integrity, GHG emission reductions and carbon dioxide removals generated by a project must not be double counted or double sold. Double counting includes double issuance, double claiming, and double use. See VCS Program Definitions for the full definitions of these terms. This section	As per section 1.10 of the MR project is not involved in double counting or participation in other GHG programs. PP shall submit relevant evidence to support their claim in accordance with section 3.23 of VCS standard v 4.7.	A declaration from PP claiming that the project is not involved in double counting or participation in other GHG programs is submitted.
	Rd 2	PP has submitted a declaration that clearly mentions that the project activity is not involved in double counting or participation in other GHG programs in accordance with section 3.23 of VCS standard v 4.7. #CLOSED	

Rule	Assessment Question	Findings/Comments CL#3	Developer Response
VCS Standard v 4.7. & VCS MR Template	GHG emission reductions and removals issued as VCU's must not be double claimed (see VCS Program Definitions for the definition of double claiming). Where project activities are in a supply chain,	As per section 1.11 of the MR project is not involved in double claiming or scope 3 emissions. PP shall submit relevant evidence to support their claim in accordance with section 3.24 of VCS standard v 4.7. Also, PP shall clarify if the project technology is part of host country NDCs.	A declaration from PP claiming that the project is not involved in double claiming or scope 3 emissions and clarifying if the project technology is part of host country NDCs is submitted.

	steps must also be taken to avoid Scope 3 emissions double claiming.		
	Rd 2	PP has submitted the declaration that clearly mentions that the project activity is not involved double claiming or scope 3 emissions in accordance with section 3.24 of VCS standard v 4.7 In addition to this It is well established that the project technology is not the part of host country NDCs. #CLOSED	

Rule	Assessment Question	Findings/Comments CL#4	Developer Response
VCS Standard v4.7. & VCS MR Template	Evidence requirement for non-carbon SDGs	MR section 1.12: As stated “The evidence of the project’s SD contributions is provided in Appendix 2.” However, appendix-2 does not include the complete details of the SDG benefits information stated in section 1.12. Therefore, PP shall submit the supporting evidence w.r.t to information shared in this section.	All the supporting evidence for the mentioned SDGs is submitted.
	Rd 2	PP has submitted detailed recorded documentary evidence for each SDG mentioned	

		under section 1.12 of the MR. VVB has reviewed the same and is found appropriate. #CLOSED	
--	--	--	--

Rule	Assessment Question	Findings/Comments CL#5	Developer Response
VCS Standard v4.7. & VCS MR Template	The project proponent shall demonstrate how the project activities, or additional activities implemented by the project proponent, contribute to sustainable development, as defined by, and tracked against the SDGs. The project proponent shall demonstrate that a project contributes to at least three SDGs by the end of the first monitoring period, and in each subsequent monitoring period. Where possible, project proponents should demonstrate how the project activity(s) is consistent with the SDG objectives of the host country.	MR section 1.12, table-1 1. For SDG 7.b “The invoices for energy generation for the current monitoring period are attached to this report.” PP shall submit the evidence for the same. 2. PP shall provide documentary evidence to verify that clinics (SDG3) were constructed by PP and building 3 schools and renovation of 4 schools with necessary equipment and furniture in support of claims made under SDG3 and SDG4 respectively. 3. PP shall provide relevant employment records of personnel claimed under SDG 8. PP shall confirm if project activity employment is meeting with the minimum salary requirement of the host country during the current monitoring period.	1. The invoices are submitted to the VVB. 2. CSR evidence submitted to the VVB. 3. AMEA SOLAR TOGO SAU is committed to upholding the highest standards of labor practices, adhering strictly to the International Finance Corporation (IFC) and International Labour Organization (ILO) guidelines. In addition to meeting these international standards, AMEA SOLAR TOGO SAU ensures full compliance with all local labor laws in the regions where it operates, maintaining a strong commitment to ethical employment practices, workers' rights, and safe working conditions globally. 4. The unit is changed to maintain consistency.

		4. For SDG 13.1: As stated “The project is expected to prevent the release of 1,674 kilotonnes of carbon into the atmosphere”. PP shall use consistent units for SDG 13 under section 1.12 of MR.	
		1. PP has submitted an invoice as documentary evidence for SDG 7. VVB has reviewed the same and is found in line with the Tab “ER sheet” column D of the submitted ER spreadsheet. #CLOSED 2. PP has submitted photographs and documentary evidence that exhibit how AMEA facilitated renovation and constructions of the schools and clinic. VVB has reviewed the photographs, and the documentary evidence submitted and found it satisfactory with the claim made for SDG 3 and 4 under section 1.12 of MR. #CLOSED 3. PP has submitted the commitment to upholding the highest standards of labor practices in line with all the host country’s laws and benchmarks. PP has submitted O & M chart in line with SDG 8. #CLOSED	

		4. PP has updated section 1.12 of the MR to ensure consistency of the units throughout the document. #CLOSED	
--	--	---	--

Rule	Assessment Question	Findings/Comments CL#6	Developer Response
Monitoring report Template v4.4 requirement	Stakeholder engagement and consultation: Describe the process(es) used to identify stakeholders likely impacted by the project. List the stakeholders identified. The project proponent shall take due account of all input received during the stakeholder consultation and through ongoing communications.	- MR section 2.1.1: As per MR filling guideline PD shall include the list the stakeholders identified for the project and related details in table under section 2.1.1. PD shall also clarify if any new stakeholders were identified for phase-2 of the project which got constructed and commissioned during the current monitoring period and accordingly update the table under this section. - Appendix-3 of MR: The first and last date of stakeholder engagement log is 16 Jan and Oct-2023. PD shall clarify if any comments were log beyond these dates as the duration of MP is from 01 Jan to 31 Dec-2023. - Appendix-3 of MR: PP has included the stakeholder log details; however,	- The initial stakeholder consultation covered the entire 70 MW plant, so no new stakeholders were identified for the commissioning of phase 2. This is added to section 2.1.1. - It is clarified in Appendix 3 that no comments were added after 19-October-2023 as shown in the stakeholder engagement log. - The stakeholder engagement log in Appendix 3 is updated with any actions taken, along with the corresponding dates of those actions. - A summary of stakeholder engagement is added under section 2.1.

		• PP shall clarify if feedback given by stakeholders is resolved. PP shall provide a written response to these stakeholder feedback in a manner that is culturally appropriate. • PP shall clarify the date when the action taken on this stakeholder feedback log was/were resolved. 4. Reference of appendix-3 i.e., stakeholder feedback is missing in relevant section 2.1-2.4 of the MR of any feedback comment raised by stakeholder is related to these aspects or not.	
		1. PP has updated section 2.1.1 of the MR to clarify that as both the phases are located in the same area therefore there are no new stakeholders identified. VVB has found this clarification justified. #CLOSED 2. VVB has found the justification provided by PP satisfactory. PP has attached grievance record under appendix 3 of the MR. #CLOSED	

		3. PP has provided grievance records under appendix 3 for the current monitoring period with the date of resolution of the grievance. #CLOSED 4. PP has updated section 2.1-2.4 in the MR appropriately. #CLOSED	
--	--	--	--

Rule	Assessment Question	Findings/Comments CL#7	Developer Response
Monitoring report Template v4.4 requirement	Risks to Stakeholders and the Environment (VCS Standard 3.19.4-10) Demonstration of Management team expertise in implementing similar project activities and engaging communities.	MR section 2.2.1: This section of the monitoring report shall include the information w.r.t PP's expertise and experience for community engagement at the project scale and in the local context for management of risk to stakeholders and environment. As stated "All of the team members have passed internal monitoring training" PP shall submit the details to verify the information.	1. Information w.r.t PP's expertise and experience is added. 2. Training records are submitted to verify the information. 3. Health and Safety audit records are submitted. 4. A waste and wastewater management plan is submitted for detailed information. 5. The clarification is added to section 2.3.1. 6. Justifications are provided for sections marked n/a.

		MR section 2.2.2: As stated “The organization maintains a robust health and safety program, including regular audits” PD shall submit the sample copies of the audits and its results. MR section 2.2.2: PP shall clarify details w.r.t safe disposal of the pollutants or waste generation from the solar power plant’s operation and maintenance activities. MR section 2.3.1: PP shall clarify if the AMEA, Togo have any local Labor and work related compliances to be submitted to local authority at any defined frequency. MR section 2.3 and 2.4: PP shall provide justification in the column where “n/a” is marked for the sections.	
		PP has updated section 2.2.1 to provide details on the expertise and experience of PP for community engagement. Moreover, PP has provided training records for the current monitoring period. #CLOSED	

		PP has submitted the HSE audit report which consists of the audit checklist, the photographic evidence and the summary of level of risk indicator results. VVB has reviewed the document and found it appropriate. #CLOSED PP has submitted the waste and wastewater management plan that clearly defines roles and responsibilities, objectives, policies, practices, emergency procedures that are approved to be carried out onsite. This document is found to be appropriate. Furthermore, PP has updated section 2.2.2 of the MR to brief about the waste management practice. #CLOSED PP has appropriately updated section 2.3.1 of the MR to describe labor and work practices followed by PP in the project activity. #CLOSED PP has updated section 2.3 and 2.4 of MR appropriately. #CLOSED	
--	--	---	--

Rule	Assessment Question	Findings/Comments CL#8	Developer Response
VCS Standard v4.7. & VCS MR Template	Project activities must not negatively impact the natural environment or communities. Project proponents must identify and address any negative environmental and socio-economic impacts of project activities.	Section 2.2-2.4, MR: PD has claimed that there is no negative impact on the environmental and socio-economic impacts due to phase 1 and phase-2 of solar power project activity. PP shall provide relevant study/report conducted to support their claim made under section 2.2 to 2.4 of the MR.	ESIA report is submitted.
		PP has submitted ESIA report which is documentary evidence for claims made under section 2.2-2.4. VVB has reviewed the report and found it inline with the section 2.2-2.4 of the MR. #CLOSED	

Rule	Assessment Question	Findings/Comments CAR#3	Developer Response
VCS Standard v4.7. & VCS	Implementation Status of the Project Activity Whether data and parameters monitored and related QA/QC are	1. MR, section 3.1: Under technical details phase 1 table VVB is unable to sight clear segregation of PV modules under 390/395/400 Wp. PP shall clarify	1. The count of PV modules for each mentioned Wp is added and supporting evidence is provided.

MR Template	followed during the operation, implementation and maintenance of the project.	the count of PV modules for each mentioned Wp and also provide supporting evidence. 2. Section 4 of MR: PP shall provide tabulated summary details regarding the major breakdown maintenance (as given in DGR excel sheet) of solar power plant during the current monitoring period.	2. Section 4.2 includes details about the major breakdown and the management of electricity.
	Rd 2	1. PP has updated section 3.1 of the MR. Also, PP has provided line diagram and PV module table which is reviewed by VVB and found relevant. #CLOSED 2. PP has updated section 4.2 of MR to provide details of the major breakdown and electricity generation. The submitted justification is acceptable. #CLOSED	

Rule	Assessment Question	Findings/Comments CL#9	Developer Response
------	---------------------	------------------------	--------------------

VCS Standard v4.7. & VCS MR Template	The monitoring report shall specify the number of GHG emission reductions or carbon dioxide removals generated in each calendar year of the monitoring period.	1. Section 4.2, MR and ER excel sheet: PP shall submit evidence for the monthly generation values entered in the column “c” of ER sheet tab “ER Sheet”. PD shall clarify if these monthly generation values are certified by local grid authority. 2. Section 4.2, MR and ER excel sheet: PD shall explain any quality crosscheck measure in place to ensure the values are correctly reported with no material error. Moreover, PP shall elaborate as to why net energy generation value as per as reported in column “c” is different from Net energy generation- invoice report in column “D” of ER excel sheet.	1. The monthly generation values entered in column ‘c’ of the ER sheet are in accordance with the DGR reports. The monthly generation values are certified by the local grid authority as shown in the invoices. 2. These are clarified under section 4.2 and 4.3 of the MR.
	Rd 2	1. PP has submitted DGR sheet which is reviewed by VVB and found appropriate. #CLOSED	

		2. Net energy generation DGR is sourced from DGR report submitted by PP to VVB. Since the invoice value is more hence the conservative value has been taken. Therefore, the justification provided by PP for the difference of values between column c and d of the ER sheet tab in the ER spreadsheet under section 4.2 appropriate. #CLOSED	
--	--	--	--

Rule	Assessment Question	Findings/Comments CL#10	Developer Response
VCS Standard 4.7. & VCS MR Template	Check the quantification of GHG emission reductions (reductions) for the monitoring period undergoing verification. Check the quality assurance and quality control (QA/QC) procedures to be applied, including the calibration procedures where applicable.	1. PP shall ensure that the calculation considering for the period when the calibration was delayed is accurate and conservative. While doing so PD shall use a conservative approach followed for calculation of maximum observed error as per 'CDM validation and verification standard for project activities', 366(a) and 366(b).	1. The calculation sheet is updated by applying the maximum observed error to both import and export energy values. 2. The required details are added under Appendix 5. Section 4.2 and Appendix 5 are kept separate to ensure clarity and prevent the section from becoming overly dense or confusing. References to the appendix are included within the section to provide additional context.

		2. Appendix-5, MR: PP shall include the location details of energy meters, next due date of calibration in column next to “calibration results” and results of calibration to ensure that calibration was OK/Not OK. PP may combine the calibration details from section 4.2 at one place for more clarity to any third reader. 3. As stated in ER excel sheet and appenedix-6 i.e., “As the calibration of the meters took place on 25-October-2022 and the next one on 26-November-2023”. PD shall submit the calibration record of energy meters dated 25-Oct-2022 for verification.	3. The calibration reports are submitted.
		1. PP has submitted calculation on corrected values where calculation of corrected import values is in line with the 'CDM validation and verification standard for project activities', 366(a) and 366(b). #CLOSED	

		2. PP has updated appendix 5 to mention the due date of calibration and location of the meters. PP added calibration results in the tabular form for every calibration performed appropriately. #CLOSED 3. PP has submitted calibration record of energy meters dated 25-Oct-2022 and is found appropriate and inline with the requirements of calibration stated in the registered PDD. #CLOSED	
--	--	--	--

Rule	Assessment Question	Findings/Comments CAR#4	Developer Response
VCS Standard v4.7. & VCS MR Template	Quality management procedures to manage data and information shall be applied and established. Where applicable, procedures to account for uncertainty in data and parameters shall be applied in accordance with the requirements set out in the methodology	MR section 4.3: PP has included the monitoring plan and quality management system along with the diagram under section 4.3 of the document. However, PP shall provide brief details of the roles and responsibility (as reflected in O&M Organization chart) defined for each level of project management in this section. PP shall provide evidence for internal or external audits if any conducted for the solar power plant facility.	Brief details of the roles and responsibility (as reflected in the O&M Organization chart) are provided in section 4.3. The O&M chart along with detailed responsibilities is also submitted.

		PP has updated section 4.3 to briefly describe the roles and responsibilities of the personnel in the project activity. PP has submitted documentary evidence of internal audits. In addition to this PP has submitted a detailed document on roles and responsibilities along with the organization chart which is reviewed by VVB and found appropriate. #CLOSED	
--	--	---	--

Rule	Assessment Question	Findings/Comments CL#11	Developer Response
VCS Standard 4.7. & VCS MR Template	Check the quantification of GHG emission reductions (reductions) for the monitoring period is clearly and accurately presented in emission reduction excel sheet and associated linked raw data.	MR section 5 and Emission reduction excel sheet: VVB has sighted constant operating hours considered for Solar power plant irrespective of length of the day and accounting rainy season. Also reading of final value of previous day is same as initial value of next day. PP shall clarify the rationale behind consideration of 11.5 hours only per day and managing same values for final reading pervious day and initial reading next day in DGR Sheet_TOGO_2023.xls DGR Tab.	This was an editorial error that has been updated from FY 2024 in accordance with the generation start and stop times. There is no impact on electricity generation.

	Rd 2	The justification submitted by PP is acceptable as the recording hours doesn't not affect the electricity generation. #CLOSED	
--	------	---	--

Rule	Assessment Question	Findings/Comments CAR#5	Developer Response
VCS Standard v4.7. & VCS MR Template	The project boundary shall be described (using diagrams, as required) and GHG sources, sinks, and reservoirs shall be identified and assessed in accordance with the methodology applied to the project. The project shall justify not selecting any relevant GHG source, sink, and reservoir.	MR, Appendix-4: Single line diagram has been provided in appendix-4 of the MR. However, PP shall elaborate on the energy meter locations (as detailed in appendix-4) in diagram under appendix 4 of the document for more clarity.	Detailed Single line diagram is submitted.
		VVB has reviewed detailed line diagram submitted by PP and is found appropriate. #CLOSED	

Rule	Assessment Question	Findings/Comments CAR#6	Developer Response
VCS Standard v4.7. & VCS	Check whether specific instructions for completing each section of the	Inline, with template guidelines, complete all sections using size 10.5, black, regular (non-italic) Arial or	All sections are rechecked to make sure it adheres to the template guidelines.

MR Template	monitoring report are followed as per VCS Monitoring Report template.	Franklin Gothic Book font, PP shall make sure that font guidelines are maintained through the report.	
		PP has updated MR document to ensure font consistency as per MR template guidelines. #CLOSED	

APPENDIX 5: COMPETENCE OF TEAM MEMBERS AND TECHNICAL REVIEWERS

Verification Team members

Competency Statement	
Name	Manika Mongia
Years of Experience	3+
Qualifying Roles	
Team Leader	No
Auditor	Yes
Country Expert	Yes, CE Region 1 (English) / CE Region 6 (Hindi)
Technical Expert	Yes (1.1)

Financial Expert	No
Independent Reviewer	No
Approval	
Approved by	Head of Quality and Compliance, SustainCERT
Date	23/02/2024

Competency Statement		
	Name	Durando NDONGSOK
	Years of Experience	1+
	Qualifying Roles	
	Team Leader	No
	Auditor	No
	Country Expert	Yes, CE Region 1 (English) CE Region 3, (French)
	Technical Expert	Yes (1.2)
	Financial Expert	No
	Independent Reviewer	No
	Approval	

	Approved by	Head of Quality and Compliance, SustainCERT
	Date	05/07/2024

Competency Statement	
Name	Indrapal Parmar
Years of Experience	15+
Qualifying Roles	
Team Leader	Yes
Auditor	Yes
Country Expert	Yes, CE Region 1 (English) / CE Region 6 (Hindi)
Technical Expert	Yes (1.1, 1.2, 1.6)
Financial Expert	Yes
Independent Reviewer	Yes
Approval	
Approved by	Head of Quality and Compliance, SustainCERT
Date	15/07/2022

Competency Statement	
Name	Muskan Chawla
Years of Experience	2+
Qualifying Roles	
Team Leader	Yes
Auditor	Yes
Country Expert	Yes, CE Region 1 (English) / CE Region 6 (Hindi)
Technical Expert	Yes (1.1, 1.2)
Financial Expert	No
Independent Reviewer	Yes
Approval	
Approved by	Head of Quality and Compliance, SustainCERT
Date	5/9/2023

APPENDIX 6: ONSITE VISIT EVIDENCES

