



**Verified Carbon
Standard**

UZUNDERE I 63.0 MW HYDROELECTRIC POWER PLANT PROJECT, TURKEY 2ND VERIFICATION REPORT



Report Prepared By: Re Carbon Gözetim Denetim ve Belgelendirme Ltd. Şti.

Project Title	Uzundere I 63.0 MW Hydroelectric Power Plant Project, Turkey
Version	01.3
Report ID	626

Report Title	Uzundere I 63.0 MW Hydroelectric Power Plant Project, Turkey 2 nd Verification Report
Client	Karadeniz HES Elektrik A.Ş.
Pages	68
Date of Issue	12-02-2022
Prepared By	Re Carbon Gözetim Denetim ve Belgelendirme Ltd. Şti.
Contact	Address: Prof. Dr. Aziz Sancar Cad. No: 27/6 06690 Çankaya/Ankara/TURKEY Tel.: 0090-312-287 51 22 Fax: 0090-312-287 33 73

	email: info@re-carbon.net Website: www.re-carbon.net	
Approved By	Mr. Sandeep KANDA Technical Reviewer	Mr. Esin TUNALI Certification Manager
		
Work Carried Out By	Verification Team Leader	Verification Team Members
	Mr. Anıl SÖYLER	N/A

Summary:

The project includes the installation of a runoff river hydroelectric power plant (HEPP) with an installed capacity of 63.068 MWm / 62.152 MWe on Uzundere River in Rize city of Turkey. The purpose of the project activity is to generate electricity and supply it into the public grid. The project activity reduces greenhouse gas (GHG) emissions that would have otherwise occurred in the absence of the project activity by avoiding electricity generation from fossil fuel sources and it includes the installation of vertical axis two Pelton turbines with the installed capacity of 31.076 MWe each.

The scope of the verification is the independent and objective review of the monitored GHG reductions. The verification activity is based on the validated and registered PD version 04 and dated 22/11/2010.

The project activity and the monitoring report are assessed against the requirements of the approved consolidated baseline and monitoring Methodology "ACM0002: "Grid-connected Electricity Generation from Renewable Sources" version 11.0 and other related rules according to the guidance given in VCS version 4.1.

The only purpose of the verification and certification is its usage during the issuance process as part of the VCS project cycle.

During this verification 25 Corrective Action Requests (CARs) and 03 Clarification Requests (CLs) were raised all of which were resolved by either revising the Monitoring Report or by sending objective evidence to the verification team.

Re Carbon Ltd. hereby confirms that the level of assurance of this verification report is reasonable, with respect to material errors, omissions and misrepresentations. To guarantee this level of assurance all data that is used in the GHG emission reduction calculations have been reviewed without any sampling.

Re Carbon Ltd. also confirms the following based on the results of document review for the period between 02 December 2011 and 30 November 2017:

Year	Baseline emissions or removals (tCO ₂ e)	Project emissions or removals (tCO ₂ e)	Leakage emissions (tCO ₂ e)	Net GHG emission reductions or removals (tCO ₂ e)
------	---	--	--	--

2011	2,473	0	0	2,473
2012	65,959	0	0	65,959
2013	66,784	0	0	66,784
2014	75,036	0	0	75,036
2015	71,657	0	0	71,657
2016	97,304	0	0	97,304
2017	74,669	0	0	74,669
Total	453,882	0	0	453,882

CONTENTS

1	Introduction	5
1.1	Objective	5
1.2	Scope and Criteria.....	5
1.3	Level of Assurance	5
1.4	Summary Description of the Project	5
2	Verification Process	6
2.1	Method and Criteria	7
2.2	Document Review.....	7
2.3	Interviews.....	10
2.4	Site Inspections	11
2.5	Resolution of Findings.....	12
2.5.1	Forward Action Requests.....	15
2.6	Eligibility for Validation Activities	16
3	Validation Findings.....	17
3.1	Participation under Other GHG Programs	17
3.2	Methodology Deviations	17

3.3	Project Description Deviations	17
3.4	Grouped Project	17
4	Verification Findings.....	18
4.1	Project Implementation Status	18
4.2	Safeguards	20
4.2.1	No Net Harm.....	20
4.2.2	Local Stakeholder Consultation	21
4.3	AFOLU-Specific Safeguards	21
4.4	Accuracy of GHG Emission Reduction or Removal Calculations.....	21
4.5	Quality of Evidence to Determine GHG Emission Reductions or Removals	24
4.6	Non-Permanence Risk Analysis.....	25
5	Verification Conclusion	26
	Annex 1: Verification Protocol	28
	Annex 2: Verification Team And ITR Competence	66
	Annex 2-1: Appointment Certificates	67

1 INTRODUCTION

1.1 Objective

Re Carbon Ltd. has been appointed by “Karadeniz HES Elektrik A.Ş.” to perform the second verification of the “Uzundere I 63.0 MW Hydroelectric Power Plant Project, Turkey” with the service agreement dated 18/08/2020. The objective of this verification activity is to assess, with objective evidence:

- if the monitoring report version 07 dated 11/02/2022 conforms with the requirements of the monitoring plan of the registered Project Description (PD) and the approved methodology
- if the project activity conforms with the monitoring report and the registered PD, and
- if the data reported in the monitoring report are complete and transparent.

1.2 Scope and Criteria

The scope of the verification is the independent and objective review of the monitored GHG reductions. The verification activity is based on the validated and registered PD version 04 and dated 22/11/2010.

The project activity and the monitoring report are assessed against the requirements of the ACM0002: “Grid-connected Electricity Generation from Renewable Sources” version 11.0, according to the guidance given in the according to the guidance given in the VCS version 4.1.

The only purpose of the verification and certification is its usage during the issuance process as part of the VCS project cycle. Therefore, Re Carbon Ltd. can't be held liable by any party for decisions made or not made based on the verification and certification opinion, which will go beyond that purpose.

1.3 Level of Assurance

Re Carbon Ltd. hereby confirms that the level of assurance of this verification report is reasonable, with respect to material errors, omissions and misrepresentations. To guarantee this level of assurance all data that is used in the GHG emission reduction calculations have been reviewed without any sampling.

1.4 Summary Description of the Project

Uzundere I 63.0 MW Hydroelectric Power Plant Project, Turkey has been located on Uzundere River in Rize city of Turkey and developed by Karadeniz HES Elektrik A.Ş¹. The project has vertical axis two Pelton turbines with the installed capacity of 31.076 MWe each turbine, so it

¹ The project was transferred to Karadeniz HES Elektrik A.Ş. by Karadeniz Elektrik Üretim San. A.Ş. as confirmed through the relevant legal authority (Energy Market Regulatory Authority, EMRA) official web page (<https://www.epdk.gov.tr/Detay/Icerik/3-0-86/elektriklisans-islemleri#>) and <http://lisans.epdk.gov.tr/epvys-web/faces/pages/lisans/elektrikUretim/elektrikUretimOzetSorgula.xhtml>) and PP is Karadeniz HES Elektrik A.Ş. at the time of this verification process.

has a total capacity of 63.068 MWm / 62.152 MWe in line with the electricity generation licence and provisional acceptance protocols and the project also supports the sustainable economic development in the region.

The key parameters about the technical design of the project are listed below in Table-1:

Table 1: Technical specifications of the project

Component	Property
Turbine type	Pelton
Turbine firm	Alstom
Rotation	750 r / min
Production year	2008
Average flow rate	4.75 m ³ / s
Number of turbines	2
Serial numbers of the turbines	2073 & 2074
Installed capacity of each turbine	31.534 MWm / 31.076 MWe
Generator type	SAV 217/120/8
Generator firm	Alstom
Frequency	50 Hz
Rating	34,500 kVA
Number of generators	2
Serial numbers of the generators	G0N122 & G0N123

The start date of the project activity is 27/05/2010 which is the date when the project is commissioned and the electricity was first supplied to the grid as verified through the provisional acceptance protocols and the first crediting period is from 27th May 2010 until 26th of May 2020 with two times renewable crediting period of 10 years.

2 VERIFICATION PROCESS

The relevant details with regards to the verification process are available in the following sub sections.

2.1 Method and Criteria

Re Carbon Ltd. has been appointed by “Karadeniz HES Elektrik A.Ş. ” to perform the second verification of the “Uzundere I 63.0 MW Hydroelectric Power Plant Project, Turkey” with the service agreement dated 18/08/2020. The objective of this verification activity is to assess, with objective evidence:

- if the monitoring report version 07 dated 11/02/2022 conforms with the requirements of the monitoring plan of the registered PD and the approved methodology
- if the project activity conforms with the monitoring report and the registered PD, and
- if the data reported in the monitoring report are complete and transparent.

The scope of the verification is the independent and objective review of the monitored GHG reductions. The verification activity is based on the validated and registered PD version 04 and dated 22/11/2010.

The project activity and the monitoring report are assessed against the requirements of the ACM0002: “Grid-connected Electricity Generation from Renewable Sources” version 11.0, according to the guidance given in VCS version 4.1.

There hasn't been any sampling approach applied during the verification and all monitored data/parameters have been checked by the verification team.

The only purpose of the verification and certification is its usage during the issuance process as part of the VCS project cycle. Therefore, Re Carbon Ltd. can't be held liable by any party for decisions made or not made based on the verification and certification opinion, which will go beyond that purpose.

2.2 Document Review

The basis for the verification activity is the monitoring report version 01 dated 29/09/2020 which was submitted to the verification team on the same date. This monitoring report was revised due to the issued CARs and CLs, version 07 dated 11/02/2022 being the final version. The monitoring report and the monitoring activities were assessed against the registered PD version 04 and dated 22/11/2010, ACM0002: “Grid-connected Electricity Generation from Renewable Sources” version 11.0, the relevant VCS rules and regulations including VCS version 4.1, the final validation report version 02 dated 17/03/2011 and the final initial verification report version 02 dated 20/11/2012.

The following actions were involved in the desk review:

- A review of the data and information presented to verify their completeness
- A review of the monitoring plan and monitoring methodology, paying particular attention to the frequency of measurements, the quality of metering equipment including calibration requirements, and the quality assurance and quality control procedures
- An evaluation of data management and the quality assurance and quality control system in the context of their influence on the generation and reporting of emission reductions

The list of the documents which were reviewed during the validation period is given in the Table 2-1 below:

Table 2-1: List of documents reviewed

Document Number	Document Name	Version	Date (dd/mm/yyyy)
D01	Registered PD	07	14/03/2011
D02	Final Validation Report	02	17/03/2011
D03	Initial Verification Report	02	20/11/2012
D04	ACM0002: Grid-connected Electricity Generation from Renewable Sources	11.0	-
D05	Verification Service Agreement	-	18/08/2020
D06	Monitoring Report	01	29/09/2020
D07	Monitoring Report	02	28/06/2021
D08	Monitoring Report	03	31/08/2021
D09	Monitoring Report	04	15/11/2021
D10	ER Calculation Excel Sheet	01	29/09/2020
D11	ER Calculation Excel Sheet	02	28/06/2021
D12	ER Calculation Excel Sheet	03	31/08/2021
D13	ER Calculation Excel Sheet	04	15/11/2021
D14	VCS Standard	4.1	22/04/2021
D15	VCS Program Guide	4.0	19/09/2019
D16	EIA Not Necessary Decision	-	01/04/2010
D17	Construction Agreement	-	01/04/2010
D18	Electricity Generation Licence (Last Amendment)	-	28/01/2010
D19	TEIAS Monthly Reading Protocols	-	12/2011-11/2017
D20	EPIAS Screenshoots		12/2011-11/2017
D21	Meters Test Reports	-	08/02/2010 09/09/2013 30/09/2014 19/09/2015 26/09/2016

Document Number	Document Name	Version	Date (dd/mm/yyyy)
			20/11/2017 06/11/2018 15/10/2020
D22	Electricity Meters Photos	-	-
D23	Power Plant Coordinates	-	-
D24	Waste Water Storage Tank Photos	-	-
D25	Hazardous Waste Storage Area Photos	-	-
D26	Hazardous Waste Declaration Forms to Ministry of Environment and Urbanization	-	2011 2012 2013 2014 2015 2016 2017
D27	Waste Water Transfer and Disposal Agreement with Madenli Municipality	-	01/01/2016 01/01/2017
D28	Domestic Waste Container Photographic Evidences	-	-
D29	Fish Passage Photos	-	-
D30	Turbine Brochure and Nameplates	-	-
D31	Signed Letter by the Çataldere and Incesu Villages' Heads (Mukhtars) (About the Contact Details of PP Relevant Staff In case of Any Complaint)	-	26/02/2021
D32	Letter by the PP (About Double Counting and Renewable Energy Certification (REC))	-	26/02/2021
D33	Provisional Acceptance Protocols	-	27/05/2010 07/11/2010
D34	Life Line Water Records (Signed by State Hydraulic Works)	-	06/02/2015 10/07/2015 10/02/2017 12/02/2018 28/01/2019 12/02/2020 27/01/2021

Document Number	Document Name	Version	Date (dd/mm/yyyy)
D35	Reservoir Area Layout	-	-
D36	Social Security Rords for PP Site Employees	-	-
D37	Training Records	-	13/12/2013 09-10/05/2016 25/10/2019 08/02/2021
D38	Meteorological Records Published by the General Directorate of Meteorology in Turkey (About Annual Areal Precipitation) https://mgm.gov.tr/veridegerlendirme/yillik-toplam-yagis-verileri.aspx	-	-
D39	Site Photos	-	02/10/2020
D40	Monitoring Report	05	02/12/2021
D41	ER Calculation Excel Sheet	05	02/12/2021
D42	Monitoring Report	06	28/01/2022
D43	Monitoring Report	07	11/02/2022

2.3 Interviews

During the verification period follow-up interviews were realized by the verification team to further analyze the correctness and accurateness of the information provided.

The list of people who were interviewed during the online (remote) verification site visit handled on 02/10/2020 and through Zoom program is given in the Table 2-2 below:

Table 2-2: List of persons interviewed

Reference Number	Means of Interview ²	Full Name	Title	Organization
I01	SV	Osman Köse	Plant Manager	Karadeniz HES Elektrik A.Ş.
I02	SV	Orçun Altınbaş	Engineer	Karadeniz HES Elektrik A.Ş.
I03	SV	Sıla Duran	Consultant	Sekans Danışmanlık

² SV: Online site visit; T: Telephone; E: E-mail

Reference Number	Means of Interview ²	Full Name	Title	Organization
I04	SV	Yusuf Sukaş	Village Head (Mukhtar)	Incesu Village
I05	SV	Celal Kork	Villager	Incesu Village
I06	SV	Zeynep Kork	Villager	Incesu Village

2.4 Site Inspections

As a part of the verification activities, online (remote) site visit was performed to the project activity site on 02/10/2020 and through Zoom program, details of which can be seen in the Table 2-3 below:

Table 2-3: Online (remote) site visit details

Points Verified	Source of Information
Implementation and operation of the proposed VCS project activity as per the registered PD	Document review, online site visit and interviews with the PP representatives and local stakeholders from Incesu Village
Review of information flows for generating, aggregating and reporting the monitoring parameters	Document review, online site visit and interviews with the PP representatives and local stakeholders from Incesu Village
Interviews with relevant personnel to confirm that the operational and data collection procedures are implemented in accordance with the monitoring plan in the PD	Interviews with the PP representatives
Cross-check between information provided in the monitoring report and data from other sources such as plant log books, inventories, purchase records or similar data sources	Document review and site visit
Check of the monitoring equipment including calibration performance and observations of monitoring practices against the requirements of the PD and the selected methodology	Document review, online site visit and interviews with the PP representatives and local stakeholders from Incesu Village
Review of calculations and assumptions made in determining the GHG data and emission reductions	Document review
Identification of quality control and quality assurance procedures in place to prevent or identify and correct any errors or omissions in the reported monitoring parameters	Document review and interviews with the PP representatives and local stakeholders from Incesu Village

The project owner representatives and local stakeholders had been interviewed as in above during the online (remote) site visit using Zoom program and some photographic evidences like electricity meters, waste storage areas etc. have been taken along with the document

review process to achieve the reasonable level of assurance during the verification as detailed in other sections of the report.

2.5 Resolution of Findings

The verification of this VCS project activity includes the following steps:

- Assessment of the conformity of the actual project activity and its operation with the registered PD version 04 and dated 22/11/2010
- Assessment of the compliance of the monitoring plan with the relevant methodology ACM0002: “Grid-connected Electricity Generation from Renewable Sources” version 11.0
- Assessment of the compliance of monitoring with the monitoring plan
- Assessment of data and calculation of greenhouse gas emission reduction
- Issuance of the verification report
- Independent technical review
- Approval of the verification report and request of issuance

The Verification Protocol is used for the assessment of each requirement during the execution of verification activities and is given in Annex-1 of this verification report.

The Verification Protocol consists of two tables:

- Table 1 (Monitoring Report and VCS verification requirements) and
- Table 2 (Resolution of Corrective Action, Forward Action and Clarification Requests)

The usage description of Table-1 in Verification Protocol is explained in Table 2-4 below:

Table 2-4: Explanation about Table-1 in Verification Protocol

Question	Reference	MoV*	Findings, comments, references and document sources	Draft & Final Conclusion
The requirements related with the monitoring report and verification	Gives reference to the legislation or documents where the relevant requirement is found	Explains how conformance with question is investigated. Examples of means of verification are Document Review (DR), Interview (I) and Not Applicable (NA)	Is used to elaborate and discuss the question and/or conformance to the question by giving related references and document sources based on which the finding is issued or evidence is checked	Either acceptable based on the evidence provided (OK), non-compliance with the requirement (CAR), further clarification (CL) due to insufficient, unclear or not transparent information, forward action request (FAR) that needs to be solved during the next periodic verification

The usage description of Table-2 in Verification Protocol is explained in Table 2-5 below:

Table 2-5: Explanation about Table-2 in Verification Protocol

Draft Report Clarifications, Forward Action and Corrective Action Requests by Verification Team	Ref. to Questions in Table-1	Summary of Project Participants' Response	Verification Team Conclusion
The all CL, FAR and CARs determined during the draft verification report should be listed here	Gives reference to the checklist questions in Table-1 of Verification Protocol	Is used to summarize the responses by project participants regarding the non-conformities	Is used to summarize the responses by verification and their conclusions

The Verification Protocol is fulfilled by the verification team in line with the descriptions above and all the CARs, CLs and FARs are listed in a transparent and clear manner.

During the verification period, a Verification Protocol which is attached in Annex 1 to this verification report was used to submit the findings to the project participants.

In line with Re Carbon Ltd. internal terminology and VCS version 4.1, the team reports the non-conformities in the forms of Corrective Action Requests (CARs), Clarification Requests (CLs) and Forward Action Requests (FARs). When and for which type of non-conformities CARs, CLs and FARs are issued are explained below:

- The verification team raises a CAR if one of the following occurs:
 - Non-conformities with the monitoring plan or methodology are found in the monitoring and reporting, or if the evidence provided to prove conformity is insufficient;
 - Mistakes have been made in applying assumptions, data or calculations of emission reductions that will impair the estimate of emission reductions;
 - Issues identified in a FAR during validation to be verified during verification have not been resolved by the project participants.
- The verification team raises a CL if information is insufficient or not transparent not clear enough to determine whether the applicable VCS requirements have been met.
- The verification team raises a FAR during verification for actions if the monitoring and reporting require attention and/or adjustment for the next verification period.

According to these principles total of 25 CARs and 03 CLs were issued all of which are listed in the Verification Protocol. There hasn't been any FARs issued during the verification.

The appointment process of the verification team takes into account the technical area(s), sectoral scope(s), and relevant host country experience required amongst team members for the verification of the emission reductions achieved by the project activity in the relevant monitoring period for this verification. The relevant VCS verification and previous ITR experiences are also assessed during the selection of the team members and Independent Technical Reviewer (ITR), respectively. The verification team and ITR are assigned to this verification activity on 12/06/2020 taking all the above factors into consideration and as a result of the contract review process.

The verification team and ITR details are given in Table 2-6 below:

Table 2-6: Verification team and ITR details

Name	Role	Host Country Experience	Scope Coverage	Technical Expertise	Involvement*
Anıl Söyler	Team Leader	☒	☒	☒	A, DR, SV, R
Sandeep Kanda	ITR	☒	☒	☒	ITR

* Explanations for the abbreviations used for involvement types are as follows:

A : Administrative

DR : Desk Review

SV : Online Site Visit

R : Reporting

ITR : Independent Technical Review

As a final step of verification, the final documentation including the verification report and its annexes have to undergo an internal quality control by Re Carbon Ltd. This quality control is also referred to as Independent Technical Review process.

The Independent Technical Review is performed by another Team Leader who hasn't involved in the verification activities of this project activity. When the Team Leader finalizes the Verification Report, the report is sent to Independent Technical Reviewer, at this stage not only the report but all the supporting documents like emission factor calculations and relevant excel sheets etc. are reviewed.

Further CLs and CARs can be issued by the Independent Technical Reviewer during this review, to cover all the points that may need further clarification.

After all the CLs and CARs are closed, the verification report is reviewed and approved by the Team Leader, ITR and the Certification Manager/General Manager, and the request of issuance is submitted to the VCS Organization in line with the positive verification opinion and along with the all relevant documents.

2.5.1 Forward Action Requests

The verification team raises a FAR during verification for actions if the monitoring and reporting require attention and/or adjustment for the next verification period as explained in Section 2.5.

According to these principles, no FARs was issued during the verification.

2.6 Eligibility for Validation Activities

Re Carbon Ltd. holds accreditation for the validation and verification activities in scope 1: “Energy Industry – Renewable/Non-renewable Sources” in which the project activity falls into.

3 VALIDATION FINDINGS

3.1 Participation under Other GHG Programs

The project does not participate under any emission trading program and other GHG Programs including renewable energy certificates (RECs) and this is also confirmed by the PP through the signed and sealed letters by PP dated as 26/02/2021.

3.2 Methodology Deviations

N/A (There haven't been any methodology deviations applied).

3.3 Project Description Deviations

There haven't been any change on project's design and characteristics comparing with the registered project activity. However, the project was transferred to Karadeniz HES Elektrik A.Ş. by Karadeniz Elektrik Üretim San. A.Ş. as confirmed through the relevant legal authority (Energy Market Regulatory Authority, EMRA) official web page (<https://www.epdk.gov.tr/Detay/Icerik/3-0-86/elektriklisans-islemleri#http://lisans.epdk.gov.tr/epvys-web/faces/pages/lisans/elektrikUretim/elektrikUretimOzetSorgula.xhtml>) and PP is Karadeniz HES Elektrik A.Ş. at the time of this verification process.

Besides that, the other entity involved in the project as carbon consultant was Gaia Finansal Danışmanlık Ltd. Şti. in the project description. However, it's been changed as Sekans Danışmanlık Ltd. at the time of this verification process as indicated in the monitoring report.

There hasn't been any other change or event that may impact the GHG emission reductions or removals and monitoring during this monitoring period.

Re Carbon Ltd. hereby confirms that the changes in the PP and other entity involved in the project as carbon consultant have no impact on the project to be in compliance with the VCS rules and requirements and have no impact on the applicability of the methodology, additionality and the appropriateness of the baseline scenario.

3.4 Grouped Project

The project is not a grouped project.

4 VERIFICATION FINDINGS

The verification findings have been detailed as in below.

4.1 Project Implementation Status

Compliance of the Project Implementation with the Registered PD:

As a result of the reviewed documents, Re Carbon Ltd. hereby confirms that the project is fully implemented according to the description given in the registered PD.

It can also be confirmed through the reviewed documents that all physical features of the project activity including data collecting systems and storage have been implemented in accordance with the registered PD. The project activity is completely operational and the same has been confirmed through the provided evidences including EPIAS records, TEIAS meter reading protocols, electricity meter test protocols and the photos of electricity meters.

According to the registered PD, the estimated annual emission reduction is 87,318 tCO₂e and corresponding total estimated amount for the monitoring period is 523,669 tCO₂e. The actual values achieved for the current monitoring period is 453,882 tCO₂e. The actual amount of emission reduction for the current monitoring period is about 13.3% less than the estimated emission reduction amount. However, the difference is due to the annual changes and deviations in the precipitation regime and so as in the water flow. Besides that, the difference in the values does not lead to a substantial increment of the ER in this period in relation to the estimates in the registered PD.

According to the official records published by the General Directorate of Meteorology in Turkey, annual areal precipitation in the Black Sea Region, where the project is located, is significantly higher in 2016.³ (Please see the figure with the name “Karadeniz Bölgesi Yıllık Alansal Yağışlar” in the provided web link).. Therefore, there could be decrease and increase in emission reduction amount throughout the long lifetime of the project activity considering the deviations in annual precipitation amount and it could be concluded that the increase in 2016 does not impact the materiality of the project.

The project also contributes to SDG 7 (Affordable and Clean Energy with 811,962.21 MWh net electricity generation), SDG 8 (Decent Work and Economic Growth with 16 employed staff during the recent year of operation period) and SDG-13 (Climate Action with achieved emission reduction of 453,882 tCO₂e) during the monitoring period.

The project was commissioned on 27/05/2010 which was verified by the provisional acceptance protocol. The project activity does not consist of more than one site and does not have any phased implementation.

³ <https://mgm.gov.tr/veridegerlendirme/yillik-toplam-yagis-verileri.aspx>

The GHG emission reductions generated by the project are not included in an emission trading program or any other mechanism that includes GHG allowance trading, because of the position of the host country.

The project activity has not received any other form of environmental credits, as there are no such crediting schemes in the host country as declared by the PP.

The only other eligible GHG program in the host country is Gold Standard and the certification program is Renewable Energy Certification (REC), and the project hasn't been listed in any of them, hence Re Carbon Ltd. confirms that the project has not participated or been rejected under any other GHG programs since the validation.

Remaining Issues from Validation or Previous Verifications

There hasn't been any issued Forward Action Requests (FARs) from the initial verification stage in line with the provided initial verification report version 02 dated 20/11/2012.

Compliance of the Monitoring Plan with the Monitoring Methodology

The monitoring plan is in accordance with the approved methodology, ACM0002 version 11.0, applied by the project activity.

In line with the methodology and the registered PD, the monitored parameters are quantity of net electricity generation supplied by the project plant to the grid ($E_{g, \text{facility}, y}$), installed capacity of the hydro power plant after the implementation of the project activity (CAP_{PJ}) and area of the reservoir (AP_J) as in below:

- $E_{g, \text{facility}, y}$: The quantity of net electricity delivered to the grid has been calculated with the EPIAS (the financial settlement centre of TEIAS) records provided to the PP by TEIAS. The net electricity is measured continuously by two main electricity meters at the grid interface and recorded monthly. There are also two back up electricity meters. That means, the electricity generation and consumption values have been determined through the summation of the measured values of two main meters and checked through two back up meters. All readings and billings are done via EPIAS system which is the legal database of the Ministry of Energy and Natural Resources in Turkey. During this verification, all EPIAS and TEIAS meter reading records have been reviewed by the verification team. The project mainly uses its own electricity however during the times when there is no generation, the project imports electricity from the grid. There are also internal reviews of the metered data which is checked by different parties. SCADA system is also available from which daily reports are taken and the data collected daily is saved in plant manager computer and backed up.
- CAP_{PJ} : According to the monitoring plan in the registered PD, the installed capacity of the power plant is monitored supplier information on the equipment and the number of turbines. The project has two vertical axis Pelton turbines with the installed capacity of 31.076 MWe each, so it has total capacity of 62.152 MWe in line with the electricity generation licence and provisional acceptance protocols. Re Carbon Ltd. hereby confirms that there hasn't been any change regarding the total installed capacity of the project.
- AP_J : According to the monitoring plan in the registered PD, the area of the reservoir is monitored via topographical surveys, maps and satellite pictures. The reservoir area has been checked through the reservoir layout drawing of the project considering

maximum possible water level as in the registered PD and initial verification process. Area of the reservoir measured in the surface of the water, after the implementation of the project activity, when the reservoir is full has been determined through the topographical drawings and 3D models, assuming a water height equivalent to the theoretical design maximum of the weir i.e. 1638 m elevation. Actual water level was lower than this maximum value and the associated value is fairly conservative. Based on that, the reservoir area is taken as 7,275.54 m² accordingly.

All data collected as part of monitoring will be archived electronically by the project owner and be kept at least for 2 years after the end of the last crediting period.

CAR-18, CAR-19 and CAR-20 were issued regarding the monitoring and they had been closed out as detailed in Annex-1.

Compliance with the Calibration Frequency Requirements for Measuring Instruments:

The net electricity is measured continuously by one main electricity meter at the grid interface and recorded monthly. There is also one back up electricity meter.

The calibrated electricity meters were installed as per the regulations. Although, re-calibration is required after ten years, nevertheless, in case of irregular difference between main and cross-check spare meters, TEIAS (grid company) responsible are informed for the intervention. That means, TEIAS is responsible for the calibration and maintenance of the meters. Although the calibration of the meters is valid for 10 years in line with the relevant legal regulation, the tests for the meters were performed on 08/02/2010 (initial meter test), 09/09/2013, 30/09/2014, 19/09/2015, 26/09/2016, 20/11/2017, 06/11/2018, 10/10/2018 and 15/10/2020, respectively and those test reports were provided to VVB.

The serial number of the currently available main meter (EMH model and accuracy class is C-1s) is 9674605 and that of back up meter (EMH model and accuracy class is C-1s) is 9674606, respectively and these have been verified through the electricity meter photos and meter test protocols. The serial numbers of dismantled main meter is 53064430 and that of back up meter is 53064429, respectively in line with the meter change protocol dated as 15/10/2020 (the meters were replaced due to the end of 10 year usage period of them in line with the relevant legal regulation) and these meters were available until 15/10/2020 during the monitoring period in line with the meter test protocols. All these meters are bi-directional (meter the energy in two directions – generation and consumption).

CAR-18 was issued regarding the calibration and meter testing and this CAR had been closed as detailed in Annex-1.

4.2 Safeguards

4.2.1 No Net Harm

There hadn't been any observed significant environmental impact of the project activity as indicated in the registered PD and this was also confirmed through the reviewed documents. The EIA Not Necessary Decision dated as 01/04/2010 by the Provincial Directorate of Environment and Urbanization was also provided by the PP.

Besides that, the photos of waste storage areas and the hazardous waste declaration forms to Ministry of Environment and Urbanization for 2018, 2019 and 2020 and waste water transfer and disposal agreements with Madenli Municipality dated as 01/01/2016 and 01/01/2017 have been provided by the PP. The photographic evidences of fish passage and official signed lifeline water records have also been provided.

4.2.2 Local Stakeholder Consultation

There hadn't been any complaint raised by the interviewed local stakeholders during the verification site visit as detailed in Section 2.3.

The local stakeholders as stated in the Table 2-2 above were interviewed about the following issues and there hadn't been any complaint by the interviewed local stakeholders during the online site visit:

- Noise due to the project activity
- Impact on the aquatic life where the project had been constructed
- Sufficiency of local employment (The interviewed local stakeholders were pleased about the provided local employment opportunities by the PP)
- Waste management practices implemented by PP

It was also concluded that the grievance mechanism is in place and this was also confirmed by the interviewed local stakeholders during the online (remote) site visit. The documents showing the contact details of the relevant person within PP with the signatures of Çataldere and Incesu Villages Mukhtars (Village Heads) and dated as 26/02/2021 were also provided to VVB.

Therefore, it could also be concluded that there hasn't been any complaint during the monitoring period in line with the provided records, information by PP and interviews with some local stakeholders.

4.3 AFOLU-Specific Safeguards

N/A (The project is not an AFOLU project).

4.4 Accuracy of GHG Emission Reduction or Removal Calculations

EPIAŞ records are presented for all months of the monitoring period. All data in emission reductions table are checked with EPIAŞ records as the main source and crosschecked with TEAIS meter reading protocol records. The net electricity generated during the current monitoring period was as follows in Table 4-1 below:

Table 4-1: Net electricity generation

Period	Amount	Compliance Check
02/12/2011-31/12/2011	Export to Grid: 4,466.60 MWh Import from Grid: 41.87 MWh Net electricity supplied to grid: 4,424.73 MWh	Monthly EPIAS records

Period	Amount	Compliance Check
01/01/2012-31/12/2012	Export to Grid: 118,357.09 MWh Import from Grid: 360.84 MWh Net electricity supplied to grid: 117,996.25 MWh	Monthly records EPIAS
01/01/2013-31/12/2013	Export to Grid: 119,792.47 MWh Import from Grid: 321.35 MWh Net electricity supplied to grid: 119,471.12 MWh	Monthly records EPIAS
01/01/2014-31/12/2014	Export to Grid: 134,538.26 MWh Import from Grid: 304.35 MWh Net electricity supplied to grid: 134,233.91 MWh	Monthly records EPIAS
01/01/2015-31/12/2015	Export to Grid: 128,444.16 MWh Import from Grid: 254.89 MWh Net electricity supplied to grid: 128,189.27 MWh	Monthly records EPIAS
01/01/2016-31/12/2016	Export to Grid: 174,294.46 MWh Import from Grid: 225.14 MWh Net electricity supplied to grid: 174,069.32 MWh	Monthly records EPIAS
01/01/2017-30/11/2017	Export to Grid: 133,805.45 MWh Import from Grid: 227.84 MWh Net electricity supplied to grid: 133,577.61 MWh	Monthly records EPIAS
Total	Export to Grid: 813,698.49 MWh Import from Grid: 1,736.28 MWh Net electricity supplied to grid: 811,962.21 MWh	Monthly records EPIAS

Emission factor and data and parameters available before validation are also applied in line with the registered PD and baseline excel sheet for validation.

According to the applied methodology ACM0002 version 11.0 and the registered PD, the GHG emission reductions are calculated as follows:

$$ER_y = BE_y - PE_y$$

Where:

ER_y = Emission reductions in year y (tCO₂e/yr)

BE_y = Baseline emissions in year y (tCO₂e/yr)

PE_y = Project emissions in year y (tCO₂e/yr)

According to the applied methodology, for hydropower plants if the power density of the reservoir is higher than 10 W/m², then $PE_y = 0$. The power density of the project is calculated as follows:

$$PD = \frac{Cap_{PJ} - Cap_{BL}}{A_{PJ} - A_{BL}}$$

Where;

PD = Power density of the project activity (W/m²)

Cap_{PJ} = Installed capacity of the hydro power plant after the implementation of the project activity (W)

Cap_{BL} = Installed capacity of the hydro power plant before the implementation of the project activity (W). For new hydro power plants, this value is zero

A_{PJ} = Area of the single or multiple reservoirs measured in the surface of the water, after the implementation of the project activity, when the reservoir is full (m²)

A_{BL} = Area of the single or multiple reservoirs measured in the surface of the water, before the implementation of the project activity, when the reservoir is full (m²). For new reservoirs, this value is zero

The project activity is a green field run-of-river hydropower project, so Cap_{BL} and A_{BL} are equal to zero.

A_{PJ} = 7,275.54 m² (according to the provided PD of the project and the initial verification process)

Cap_{PJ} = 62,152,000 W

The power density is calculated as follows:

$$PD = 62,152,000 / 7,275.54 = 8542.6 \text{ W/m}^2$$

As the power density is higher than 10W/m², the project emissions of the project are equal to zero. Therefore, the emission reductions generated during the monitoring period are equal to baseline emissions.

The baseline emissions in the monitoring period are calculated using the following formula:

$$BE_y = EG_{PJ,y} * EF_{grid,CM,y}$$

Where;

BE_y= Baseline emissions in year y (t CO₂/y)

EG_{PJ,y}= Quantity of net electricity generation that is produced and fed into the grid as a result of the implementation of the project activity in year y (MWh/y)

EF_{grid,CM,y}= Combined margin CO₂ emission factor for grid connected power generation in year y calculated using the latest version of the "Tool to calculate the emission factor for an electricity system" (tCO₂ / MWh)

Since the project is a greenfield renewable power plant:

EG_{PJ,y} = EG_{facility,y}=The amount of net electricity produced and fed into the grid by the project in year y.

Combined margin CO₂ emission factor ($EF_{grid,CM,y}$) is calculated once during the validation of the project activity and is valid throughout the first crediting period of 10 years.

It has been confirmed that the data used for emission reductions are correct. The grid emission factor taken is 0.559 tCO₂ / MWh and the value is same as fixed ex-ante in the registered PD. It is also confirmed that the methods and formulae used for calculating baseline emissions are in line with the relevant methodology and the registered PD. The net electricity generation is multiplied with the grid emission factor to arrive at the emission reductions value.

According to the registered PD, the estimated emission reduction for this monitoring period would be 523,669 tCO₂e corresponding to the monitoring period. However, the project in operation totally reached 453,882 tCO₂e in this period.

The vintage break-up of the emission reductions during the current monitoring period was as follows in Table 4-2 below:

Table 4-2: Emission reductions

Period	Emission reductions (tCO ₂ e)
02/12/2011 – 31/12/2011	2,473
01/01/2012 – 31/12/2012	65,959
01/01/2013 – 31/12/2013	66,784
01/01/2014 – 31/12/2014	75,036
01/01/2015 – 31/12/2015	71,657
01/01/2016 – 31/12/2016	97,304
01/01/2017 – 30/11/2017	74,669

Calculations have been reproduced by DOE and the source data (EPIAS records) are presented by PP as explained above.

CAR-23 was issued regarding the emission reduction calculations and the data used for these calculations and it had been closed as detailed in Annex-1. Therefore, Re Carbon Ltd. hereby confirms that the above mentioned electricity generation figures and GHG emission reduction calculations are presented and quantified correctly and are in accordance with the monitoring methodology ACM0002 version 11.0 and the monitoring plan given in the registered PD.

4.5 Quality of Evidence to Determine GHG Emission Reductions or Removals

The GHG emission reductions are a function of the net electricity generated and fed into the grid by the project activity and the combined margin emission factor which is determined during validation for the whole crediting period. According to the validation report version 02 dated 17/03/2011, the combined margin emission factor had been validated and will remain the same for the first crediting period of 10 years as 0.559 tCO₂/MWh.

The only parameter that needs to be closely verified is the net electricity generation and this value is taken from the EPIAS records. EPIAS records are the basis for billing and these records for each month has been submitted to and reviewed. They are recorded and saved

automatically by the relevant government authority and there is no base for any option of material information.

Level of materiality is ensured by application of “Guideline on the Application of Materiality in Verifications” version 02. To guarantee this level of assurance, all data that is used in the GHG emission reduction calculations have been reviewed without any sampling.

As a cross check means, TEIAS meter reading protocol records which include the monthly generation and consumption figures of the plant for every month have been reviewed by the verification team.

Therefore, Re Carbon Ltd. hereby confirms that the evidence used to determine the GHG emission reductions are sufficient in quantity and appropriate in quality.

4.6 Non-Permanence Risk Analysis

N/A. (The project isn't an AFOLU project).

5 VERIFICATION CONCLUSION

Re Carbon Ltd. has performed the second verification of “Uzundere I 63.0 MW Hydroelectric Power Plant Project, Turkey” which is a project with the VCS registry reference number “964” for the period between 02 December 2011 and 30 November 2017. The scope of the activities cover the verification and certification of GHG emissions reductions reported in monitoring report version 07 dated 11/02/2022.

Sekans Danışmanlık Ltd. is responsible for the preparation of the GHG emissions data and the reported GHG emissions reductions of the project on the basis set out within the project monitoring plan indicated in the registered PD. The development and maintenance of the records and reporting procedures in accordance with that plan, including the calculation and determination of GHG emission reductions from the project, is the responsibility of both Sekans Danışmanlık Ltd. and the management of the project. The development and maintenance of the records and the related monitoring procedures are in accordance with the monitoring report version 07.

The verification has been performed by a verification team consisting of “Anıl Söyler as team leader and Sandeep Kanda as an ITR” and the project activity was checked against the applicable rules and regulations and the relevant guidance in VCS version 4.1.


Re Carbon Ltd. hereby confirms that the project activity “Uzundere I 63.0 MW Hydroelectric Power Plant Project, Turkey” in Turkey is implemented in accordance with the validated and registered PD version 04 and dated 22/11/2010. The monitoring system is in place and the emission reductions are calculated without material misstatements as per the applied approved methodology, which is ACM0002 version 11.0. It is also confirmed that the level of assurance of this verification report is reasonable.

Re Carbon Ltd. confirms the following based on the results of document review for the period between 02 December 2011 and 30 November 2017:

Year	Baseline emissions or removals (tCO ₂ e)	Project emissions or removals (tCO ₂ e)	Leakage emissions (tCO ₂ e)	Net GHG emission reductions or removals (tCO ₂ e)
2011	2,473	0	0	2,473
2012	65,959	0	0	65,959
2013	66,784	0	0	66,784
2014	75,036	0	0	75,036
2015	71,657	0	0	71,657
2016	97,304	0	0	97,304
2017	74,669	0	0	74,669
Total	453,882	0	0	453,882



Anıl SÖYLER
Team Leader
12/02/2022



Sandeep KANDA
ITR
12/02/2022



Esin TUNALI
Certification Manager
12/02/2022

ANNEX 1: VERIFICATION PROTOCOL

Table 1 – VCS Monitoring Report (MR) Form Requirements

Question	Reference	Means of verification *	Findings, comments, references and document sources	Draft opinion	Final opinion
Cover Page and General Requirements					
1. Are all items in the box at the bottom of the cover page completed using Arial 10.5 pt, black, regular (non-italic) font?	VCS Std. Version 4.1	DR	Please clarify whether all items in the box at the bottom of the cover page and all Sections text part using Arial 10.5 pt, black, regular (non-italic) font since the provided MR is pdf document.	CAR-1	OK
2. Are the followings provided at the cover page in a tabular format?	VCS Std. Version 4.1	DR	Please see in below.	OK	OK
2.1. Name of the project?	VCS Std. Version 4.1	DR	Please check and correct the project name in line with the VCS registry, registered PDD and validation report.	CAR-2	OK
2.2. Version number of the VCS MR?	VCS Std. Version 4.1	DR	This is available as version 01.	OK	OK
2.3. Report ID of the document	VCS Std. Version 4.1	DR	This is available as UZNMONTORING2.	OK	OK
2.4. The issuance date of the document in DD-Month-YYYY format?	VCS Std. Version 4.1	DR	This is available as 29/09/2020.	OK	OK
2.5. VCS project database ID, if registered	VCS Std. Version 4.1	DR	This is available as 964.	OK	OK
2.6. Monitoring period in DD-Month-YYYY to DD-Month-YYYY format	VCS Std. Version 4.1	DR	Please correct the monitoring start and end dates considering the end of previous monitoring period.	CAR-3	OK
2.7. Individual or entity that prepared the document?	VCS Std. Version 4.1	DR	This is available as Sekans Danışmanlık.	OK	OK
2.8. Physical address, telephone, email, website?	VCS Std. Version 4.1	DR	These details are available.	OK	OK
3. Is this box available on the title page of the final document?	VCS Std. Version 4.1	DR	This is available in the version 01 of the MR.	OK	OK
4. Is there "Table of Contents" in the VCS MR?	VCS Std. Version 4.1	DR	This is available.	OK	OK
5. Is the VCS MR used as a basis for verification prepared in accordance with the latest template and guidance from the VCS?	VCS Std. Version 4.1	DR	Please see CAR-1.	CAR-1	OK
6. Are the VCS MR and other documents required under the VCS Program in English?	VCS Std. Version 4.1	DR	MR and all other required documents are in English except for some legal permit documents since they are in Turkish.	OK	OK

*DR= Document Review, I= Interview, SV=Site Visit

Question	Reference	Means of verification *	Findings, comments, references and document sources	Draft opinion	Final opinion
1. PROJECT DETAILS					
1.1. Summary Description of the Implementation Status of Project					
1.1.1. Has a brief summary of the project description provided under Section 1.1 of the MR?	VCS Std. Version 4.1	DR	The brief summary is available but please see in below: a) Please correct the commissioning date of first turbine under Section 1.1 of the MR. b) Please correct the initial and second monitoring period details under Section 1.1 of the MR. c) Please provide the relevant evidence documents for the turbine properties.	CAR-4	OK
1.1.2. Has the purpose of the project activity and the measures taken to reduce greenhouse gas emissions been provided under section 1.1 of the MR?	VCS Std. Version 4.1	DR	Please provide the purpose of the project activity in the Section 1.1 of the MR.	CAR-5	OK
1.1.3. Has a brief description of the installed technology and equipment been provided under Section 1.1 of the MR?	VCS Std. Version 4.1	DR	Please include the brief description of the installed technology and equipment including turbine types, brand and relevant reference documents in the Section 1.1 of the MR.	CAR-6	OK
1.1.4. Has the relevant dates for the project activity (e.g. construction, commissioning, continued operation periods, etc.) been provided under Section 1.1 of the MR?	VCS Std. Version 4.1	DR	Please provide the construction date of the project activity in the Section 1.1 of the MR.	CAR-7	OK
1.1.5. Has the total emissions reductions achieved in this monitoring period been provided under Section 1.1 of the MR?	VCS Std. Version 4.1	DR	The total emissions reductions achieved in this monitoring period has been provided under Section 1.1 of the MR but please see CAR-3.	CAR-3	OK
1.2. Sectoral Scope and Project Type					
1.2.1. Is it indicated whether this a grouped project under Section 1.2 of the MR?	VCS Std. Version 4.1	DR	This has been indicated and the project is not a grouped project.	OK	OK
1.2.2. Is the sectoral scope(s) applicable to the project indicated?	VCS Std. Version 4.1	DR	The sectoral scope of the project has been indicated in the Section 1.2 of the MR.	OK	OK

*DR= Document Review, I= Interview, SV=Site Visit

Question	Reference	Means of verification *	Findings, comments, references and document sources	Draft opinion	Final opinion
1.2.3. Is the category of the project activity specified?	VCS Std. Version 4.1	DR	N/A (Since this isn't an AFOLU project, the category is not applicable).	OK	OK
1.3. Project Proponent					
1.3.1. Are the contact information for the project proponent(s) provided in the tabular format?	VCS Std. Version 4.1	DR	This is available in the Section 1.3 of the MR but please check and clarify if the relevant person and contact details are up to date in the Section 1.3 of the MR.	CL-1	OK
1.4. Other Entities Involved in the Project					
1.4.1. Are the contact information and roles/responsibilities for any other entities involved in the development of the project provided?	VCS Std. Version 4.1	DR	This is available in the Section 1.4 of the MR.	OK	OK
1.5. Project Start Date					
1.5.1. Is the project start date (the date on which the project began reducing or removing GHG emissions) indicated in day, month and year format?	VCS Std. Version 4.1	DR	This is available as 27/05/2010.	OK	OK
1.6. Project Crediting Period					
1.6.1. Is the total crediting period including the day, month and year for the start and end dates and the total number of years indicated?	VCS Std. Version 4.1	DR	Please correct the end date of crediting period in the Section 1.6 of the MR.	CAR-8	OK
1.7. Project Location					

*DR= Document Review, I= Interview, SV=Site Visit

Question	Reference	Means of verification *	Findings, comments, references and document sources	Draft opinion	Final opinion
1.7.1. Has complete information on the location of the project activity, including town, city, country and GPS coordinates been provided under Section 1.7 of the MR?	VCS Std. Version 4.1	DR	Please include the reference document information for all provided coordinates in Section 1.7 of the MR.	CAR-9	OK
1.8. Title and Reference of Methodology					
1.8.1. Is the following information provided regarding the methodology(s) applied to the project?	VCS Std. Version 4.1	DR	Please see in below.	OK	OK
1.8.1.1. The title of the methodology(ies)	VCS Std. Version 4.1	DR	Please correct the version number of the methodology in the Section 1.8 of the MR.	CAR-10	OK
1.8.1.2. The reference of the methodology(ies)	VCS Std. Version 4.1	DR	Please see CAR-10.	CAR-10	OK
1.8.1.3. The version number of the methodology(ies)	VCS Std. Version 4.1	DR	Please see CAR-10.	CAR-10	OK
1.8.2. Is the following information provided regarding the tool(s) applied to the project?	VCS Std. Version 4.1	DR	Please correct the version number of the referred tools in the Section 1.8 of the MR.	CAR-11	OK
1.8.2.1. The title of the tool(s)	VCS Std. Version 4.1	DR	Please see CAR-11.	CAR-11	OK
1.8.2.2. The version number of the tool(s)	VCS Std. Version 4.1	DR	Please see CAR-11.	CAR-11	OK
1.9. Participation under Other Programs					
1.9.1. Has it been indicated whether the project has been registered or seeking registration under any other GHG programs?	VCS Std. Version 4.1	DR	It has been stated that the project hasn't been registered or seeking registration under other GHG programs but please provide a signed and sealed letter on company letterhead that the project hasn't been registered, or hasn't been seeking registration under any other GHG programs.	CAR-12	OK
1.9.2. If the project has been registered under any other GHG programs, have the PPs provided the registration number and details?	VCS Std. Version 4.1	DR	N/A (It has been stated that the project hasn't been registered or seeking registration under other GHG programs).	OK	OK

*DR= Document Review, I= Interview, SV=Site Visit

Question	Reference	Means of verification *	Findings, comments, references and document sources	Draft opinion	Final opinion
1.9.3. If the project has been registered under any other GHG programs, have the details of any GHG credits claimed under such programs been provided in the Section 1.9 of the MR?	VCS Std. Version 4.1	DR	N/A (It has been stated that the project hasn't been registered or seeking registration under other GHG programs).	OK	OK
1.10. Other Forms of Credit					
1.10.1. Does the project reduce GHG emissions from activities that are included in an emissions trading program; or any other mechanism that includes GHG allowance trading?	VCS Std. Version 4.1	DR	Please provide a signed and sealed letter on company letterhead that project hasn't been created other forms of credit (e.g. renewable energy certificates).	CAR-13	OK
1.10.2. If the project reduces GHG emissions from activities that are included in an emissions trading program; or any other mechanism that includes GHG allowance trading, have the PPs provided evidence on the following?	VCS Std. Version 4.1	DR	Please see CAR-13.	CAR-13	OK
1.10.2.1. the reductions or removals generated by the project have or will not be used for compliance under such program(s) or mechanism(s)	VCS Std. Version 4.1	DR	Please see CAR-13.	CAR-13	OK
1.10.3. Have the project(s) created other forms of environmental credit (for example renewable energy certificates)?	VCS Std. Version 4.1	DR	Please see CAR-13.	CAR-13	OK
1.10.4. If the project(s) created other forms of environmental credit (for example renewable energy certificates), has the PPs provided all relevant information about the GHG-related environmental credits and the related program?	VCS Std. Version 4.1	DR	Please see CAR-13.	CAR-13	OK

*DR= Document Review, I= Interview, SV=Site Visit

Question	Reference	Means of verification *	Findings, comments, references and document sources	Draft opinion	Final opinion
1.10.5. Have all other programs under which the project is eligible to participate (to create another form of GHG-related environmental credit) been listed?	VCS Std. Version 4.1	DR	Please see CAR-13.	CAR-13	OK
1.11. Sustainable Development					
1.11.1. Has it been described how the project contributes to achieving any nationally stated sustainable development priorities, including any provisions for monitoring and reporting same?	VCS Std. Version 4.1	DR	These have been explained in the Section 1.11 of the MR.	OK	OK
2. SAFEGUARDS					
2.1. No Net Harm					
2.1.1. Has it been summarized by PPs any potential negative environmental and socio-economic impacts of the project activity and the steps taken to mitigate them?	VCS Std. Version 4.1	DR	Please provide the following records: - The noise assessment report, if any, - The photographic evidences of hazardous waste and waste water storage areas - The hazardous waste transfer and disposal records - The waste water transfer and disposal records - Training records for PP site employees - The social security records of PP site employees	CL-2	OK
2.2. Local Stakeholder Consultation					
2.2.1. Has the process regarding the local stakeholder consultation been described by PPs including the following?	VCS Std. Version 4.1	DR	Please see in below.	OK	OK
2.2.1.1. The procedures or methods used for engaging local stakeholders (e.g. dates of announcements or meetings, periods during which input was sought)	VCS Std. Version 4.1	DR	a) Please correct the future tense sentences in the Section 2.2 of the MR since the project is already operational. b) Please provide the current status details of the project in the Section 2.2 of the MR.	CAR-14	OK

*DR= Document Review, I= Interview, SV=Site Visit

Question	Reference	Means of verification *	Findings, comments, references and document sources	Draft opinion	Final opinion
2.2.1.2. The procedures or methods used for documenting the outcomes of the local stakeholder communication	VCS Std. Version 4.1		Please see CAR-14.	CAR-14	OK
2.2.1.3. The mechanism for on-going communication with local stakeholders conducted prior to verification	VCS Std. Version 4.1		a) Please provide the signed document about the contact details of the PP relevant staff in case of any complaint by Incesu and Çataldere villages and whether there is any complaint received by the Muhktars from the local stakeholders. b) Please provide the evidence of the communication methods (announcements and meetings) with the local stakeholders during the monitoring period.	CAR-15	OK
2.2.1.4. How due account of all and any input received during ongoing communication has been taken	VCS Std. Version 4.1		It has been clarified in the Section 2.2 of the MR that there hasn't been any complaint by the local stakeholders during the monitoring period	OK	OK
2.2.1.5. The details on any updates to the project design or justifying why updates are not appropriate.	VCS Std. Version 4.1		This has been identified in the Section 2.2 of the MR.	OK	OK
3. IMPLEMENTATION STATUS					
3.1. Implementation Status of The Project Activity					
3.1.1. Has a description of the implementation and operational status of the project as of this monitoring period been provided under section 3.1 of the MR?	VCS Std. Version 4.1	DR	These are available in the Section 1.1 of the MR.	OK	OK
3.1.2. Has the installed technology(ies), technical process and equipment, including the diagrams, where appropriate, been included in section 3.1 of the MR?	VCS Std. Version 4.1	DR	This has been provided in the Section 1.1 of the MR but please see CAR-4 and CAR-6.	OK	OK
3.1.3. Has the starting date of operation of the project activity been provided under Section 3.1 of the MR?	EB 111 Report Annex 1 §256b	DR	The starting date of operation of the project activity has been provided in the Section 1.1 of the MR but please see CAR-4.	CAR-4	OK

*DR= Document Review, I= Interview, SV=Site Visit

Question	Reference	Means of verification *	Findings, comments, references and document sources	Draft opinion	Final opinion
3.1.4. If the project activity consists of more than one site, has the status of implementation and starting date of operation for each site been clearly described under Section 3.1 of the MR?	EB 111 Report Annex 1 §256b	DR	N/A	OK	OK
3.1.5. If the implementation of the project activity planned to be realized in different phases, has the progress of the proposed VCS project activity achieved in each phase been indicated under Section 3.1 of the MR?	EB 111 Report Annex 1 §256b	DR	N/A	OK	OK
3.1.6. Do the actual project activity and its operation comply with the registered PD and/or an approved revised PD??	EB 111 Report Annex 2 §354a	DR	The actual project activity and its operation complies with the registered PD.	OK	OK
3.1.7. Have the PPs implemented and operated the VCS project activity as per the descriptions contained in the registered PD?	EB 111 Report Annex 2 §354b	DR	The actual project activity and its operation complies with the registered PD.	OK	OK
3.1.8. Has the installed technology(ies), technical process and equipment, including the diagrams, where appropriate, been included in Section 3.1 of the MR?	VCS Std. Version 4.1	DR	This has been provided in the Section 1.1 of the MR.	OK	OK
3.1.9. Are there any other changes (e.g. to project proponent or other entities) with respect to the registered project?	VCS Std. Version 4.1	DR	a) Please clarify the PP of the project activity whether it is Karadeniz Elektrik Uretim San. A.S. or Karadeniz HES Elektrik A.Ş. along with the relevant evidence. b) Please clarify in the Section 3.1 of the MR if there are any other entities involved in the project defined in the registered PD.	CL-3	OK
3.2. Deviations					
3.2.1. Methodology Deviations					
3.2.1.1. Are there any deviations from the methodology?	VCS Std. Version 4.1	DR	N/A (There haven't been any deviations from the methodology).	OK	OK
3.2.1.2. If there are any deviations from the methodology, are these deviations described properly?	VCS Std. Version 4.1	DR	N/A (There haven't been any deviations from the methodology).	OK	OK

*DR= Document Review, I= Interview, SV=Site Visit

Question	Reference	Means of verification *	Findings, comments, references and document sources	Draft opinion	Final opinion
3.2.1.3. If there are any deviations from the methodology, are these deviations justified properly and clearly?	VCS Std. Version 4.1	DR	N/A (There haven't been any deviations from the methodology).	OK	OK
3.2.2. Project Description Deviations					
3.2.2.1. Are there any deviations from the registered project description?	VCS Std. Version 4.1	DR	N/A (There haven't been any deviations from the project description).	OK	OK
3.2.2.2. If there are any deviations from the project description, are these deviations described properly?	VCS Std. Version 4.1	DR	N/A (There haven't been any deviations from the project description).	OK	OK
3.2.2.3. If there are any deviations from the project description, are these deviations justified properly and clearly?	VCS Std. Version 4.1	DR	N/A (There haven't been any deviations from the project description).	OK	OK
3.2.2.4. Is the outcome of the deviation from the project description provided?	VCS Std. Version 4.1	DR	N/A (There haven't been any deviations from the project description).	OK	OK
3.3. Grouped Projects					
3.3.1. Is this a grouped project?	VCS Std. Version 4.1	DR	N/A (The project isn't a grouped project).	OK	OK
3.3.2. If it is a grouped project, is the relevant information about new instances of the project activity(ies) provided?	VCS Std. Version 4.1	DR	N/A (The project isn't a grouped project).	OK	OK
3.3.3. If it is a grouped project, is it demonstrated clearly and transparently that each new instance of the project activity(s) meets the eligibility criteria set out in the project description?	VCS Std. Version 4.1	DR	N/A (The project isn't a grouped project).	OK	OK
4. DATA AND PARAMETERS					

*DR= Document Review, I= Interview, SV=Site Visit

Question	Reference	Means of verification *	Findings, comments, references and document sources	Draft opinion	Final opinion
4.1. Data and Parameters Available at Validation					
4.1.1. Has all the data that is determined only once for the crediting period but are used after registration of the project, been listed under Section 4.1 using the tabular format?	VCS Std. Version 4.1	DR	All data that is determined only once for the crediting period but are used after registration of the project, has been listed under Section 4.1 of the MR but please include the values applied of FCi,y and NCVi,y parameters.	CAR-16	OK
4.1.2. If all the data that is determined only once for the crediting period but are used after registration of the project, does the listed data include all the parameters used to calculate baseline, project and leakage emissions as well as other relevant parameters required by the approved methodology and the monitoring plan?	VCS Std. Version 4.1	DR	Please see CAR-16.	CAR-16	OK
4.1.3. In the data/parameter tables provided under Section 4.1 of the MR, for each data has the name of the data/parameters given in accordance with the registered VCS PD and the applied approved methodology?	VCS Std. Version 4.1	DR	All data that is determined only once for the crediting period but are used after registration of the project are in line with the registered PD.	OK	OK
4.1.4. In the data/parameter tables provided under Section 4.1 of the MR, for each data has the unit of the data/parameters given in accordance with the registered VCS PD and the applied approved methodology?	VCS Std. Version 4.1	DR	All data that is determined only once for the crediting period but are used after registration of the project are in line with the registered PD.	OK	OK
4.1.5. In the data/parameter tables provided under Section 4.1 of the MR, for each data has the description of the data/parameters given in accordance with the registered VCS PD and the applied approved methodology?	VCS Std. Version 4.1	DR	This is in line with the registered PD.	OK	OK
4.1.6. In the data/parameter tables provided under Section 4.1 of the MR, for each data has the source of the data/parameters given in accordance with the registered VCS PD and the applied approved methodology?	VCS Std. Version 4.1	DR	This is in line with the registered PD.	OK	OK

*DR= Document Review, I= Interview, SV=Site Visit

Question	Reference	Means of verification *	Findings, comments, references and document sources	Draft opinion	Final opinion
4.1.7. In the data/parameter tables provided under Section 4.1 of the MR, for each data has the values applied of the data/parameters given in accordance with the registered VCS PD and the applied approved methodology?	VCS Std. Version 4.1	DR	This is in line with the registered PD.	OK	OK
4.1.8. In the data/parameter tables provided under Section 4.1 of the MR, for each data has the justification of choice of data or description of measurement methods and procedures applied been provided?	VCS Std. Version 4.1	DR	This is in line with the registered PD.	OK	OK
4.1.9. In the data/parameter tables provided under Section 4.1 of the MR, for each data has it been indicated what the data/parameters are used for (baseline/project /leakage emission calculations)?	VCS Std. Version 4.1	DR	Please indicate for each data/parameter provided under Section 4.1 of the MR what the data/parameters are used for (baseline/project /leakage emission calculations).	CAR-17	OK

*DR= Document Review, I= Interview, SV=Site Visit

Question	Reference	Means of verification *	Findings, comments, references and document sources	Draft opinion	Final opinion
4.2. Data and Parameters Monitored					
4.2.1. Has all the data that are monitored been listed under Section 4.2 using the tabular format?	VCS Std. Version 4.1	DR	EGfacility,y, CAPpj and Apj are the monitored parameters in line with the registered PD.	OK	OK
4.2.2. In the data/parameter tables provided under section 4.2 of the MR, for each data has the name of the data/parameters given in accordance with the registered VCS PD and the applied approved methodology?	VCS Std. Version 4.1	DR	EGfacility,y, CAPpj and Apj are the monitored parameters in line with the registered PD.	OK	OK
4.2.3. In the data/parameter tables provided under section 4.2 of the MR, for each data has the unit of the data/parameters given in accordance with the registered VCS PD and the applied approved methodology?	VCS Std. Version 4.1	DR	The units are in line with the registered PD.	OK	OK
4.2.4. In the data/parameter tables provided under section 4.2 of the MR, for each data has it been described how the data is monitored?	VCS Version 4.1	DR	This is stated in the Section 4.2 of the MR.	OK	OK
4.2.5. In the data/parameter tables provided under section 4.2 of the MR, for each data has the source of data been indicated (like logbooks, daily records, surveys, etc.)?	VCS Std. Version 4.1	DR	This is in line with the registered PD.	OK	OK
4.2.6. In the data/parameter tables provided under section 4.2 of the MR, for each data has the estimated values of the monitoring parameter been indicated?	VCS Std. Version 4.1	DR	This has been provided.	OK	OK

*DR= Document Review, I= Interview, SV=Site Visit

Question	Reference	Means of verification *	Findings, comments, references and document sources	Draft opinion	Final opinion
4.2.7. In the data/parameter tables provided under section 4.2 of the MR, for each data has the QA/QC procedures being applied been given?	VCS Std. Version 4.1	DR	a) Please include the meter test and calibration dates of the electricity meters. b) Please provide the electricity meter test protocols covering the monitoring period. c) Please provide the photographic evidences of electricity meters. d) Please provide the photographic evidences of turbine name plates and turbine documents. e) Please provide the reservoir area evidence documents. f) Please provide the project capacity evidence documents. g) Please correct the future tense sentence for QA/QC procedures of CAPpj parameter since the project is operational.	CAR-18	OK
4.2.8. In the data/parameter tables provided under section 4.2 of the MR, for each data has the purpose of data been given?	VCS Std. Version 4.1	DR	Please provide the purpose for each data/parameter provided in the Section 4.2 of the MR.	CAR-19	OK
4.2.9. If applicable, has the calculation method, including any equations, used to establish the data/parameter been given?	VCS Std. Version 4.1	DR	This is available in the Excel spreadsheet.	OK	OK
4.2.10. In the data/parameter tables provided under section 4.2 of the MR, for each data has it been indicated what types of equipment are used to monitor each parameter, including following, if applicable as per the monitoring plan?	VCS Std. Version 4.1	DR	Please see in below.	OK	OK
4.2.10.1. Details on accuracy class	VCS Std. Version 4.1	DR, SV	The accuracy class information of the electricity meters have been provided in the Section 4.2 of the MR.	OK	OK
4.2.10.2. The person/entity responsible for the measurement	VCS Std. Version 4.1	DR	This is available and in line with the registered PD.	OK	OK
4.2.10.3. Any standards or protocols to be followed	VCS Std. Version 4.1	DR	This is available in the Section 4.2 of the MR.	OK	OK
4.2.10.4. Calibration frequency	VCS Std. Version 4.1	DR	This is available as ten years.	OK	OK
4.2.10.5. Serial number	VCS Std. Version 4.1	DR, SV	Please see CAR-18.	CAR-18	OK

*DR= Document Review, I= Interview, SV=Site Visit

Question	Reference	Means of verification *	Findings, comments, references and document sources	Draft opinion	Final opinion
4.2.10.6. Calibration date	VCS Std. Version 4.1	DR	Please see CAR-18.	CAR-18	OK
4.2.10.7. Validity of the calibration	VCS Std. Version 4.1	DR	This is available as ten years.	OK	OK
4.2.11. In the data/parameter tables provided under section 4.2 of the MR, for each data has the measurement and recording frequency been indicated?	VCS Std. Version 4.1	DR	Please correct the monitoring frequency of EGfacility,y parameter.	CAR-20	OK
4.2.12. Is the calibration frequency for measuring equipment specified in the monitoring methodology, in the applied standardized baselines or in the monitoring plan??	EB 111 Report Annex 2 §370 VCS Std. Version 4.1	DR	This is in line with the registered PD and relevant legal regulation.	OK	OK
4.2.13. If the calibration frequency for measuring equipment isn't specified in the monitoring methodology, guidance provided by the Board or the monitoring plan, are the equipment calibrated either in accordance with the specifications of the local/national standards, or as per the manufacturer's specification?	EB 111 Report Annex 2 §370 VCS Std. Version 4.1	DR	This is in line with the registered PD and relevant legal regulation.	OK	OK
4.2.14. If neither local/national standards nor the manufacturer's specification are available, have the international standards been used?	EB 111 Report Annex 2 §370 VCS Std. Version 4.1	DR	This is in line with the registered PD and relevant legal regulation.	OK	OK
4.2.15. Is the calibration of the measuring equipment that have an impact on the claimed emission reductions conducted by the PPs at a frequency specified in the applied monitoring methodology and/or the monitoring plan?	EB 111 Report Annex 2 §370 VCS Std. Version 4.1	DR	This is in line with the registered PD and relevant legal regulation.	OK	OK

*DR= Document Review, I= Interview, SV=Site Visit

Question	Reference	Means of verification *	Findings, comments, references and document sources	Draft opinion	Final opinion
4.2.16. Has the calibration been delayed and has the calibration been implemented after the monitoring period in consideration (i.e. the results of delayed calibration are available) for the certain monitoring period?	EB 111 Report Annex 2 §366 VCS Std. Version 4.1	DR	This is in line with the registered PD and relevant legal regulation.	OK	OK
4.2.17. If the calibration is delayed and if the calibration is implemented after the monitoring period in consideration (i.e. the results of delayed calibration are available) for the certain monitoring period, are one of the following approaches adopted by the PPs for the calculation of emission reductions?	EB 111 Report Annex 2 §366 VCS Std. Version 4.1	DR	N/A (The calibration of the meters is valid ten years).	OK	OK
4.2.17.1. Applying the maximum permissible error of the instrument to the measured values taken during the period between the scheduled date of calibration and the actual date of calibration, if the results of the delayed calibration do not show any errors in the measuring equipment, or if the error is smaller than the maximum permissible error; or	EB 111 Report Annex 2 §366a VCS Std. Version 4.1	DR	N/A (The calibration of the meters is valid ten years).	OK	OK
4.2.17.2. Applying the error identified in the delayed calibration test, if the error is beyond the maximum permissible error of the measuring equipment.	EB 111 Report Annex 2 §366b VCS Std. Version 4.1	DR	N/A (The calibration of the meters is valid ten years).	OK	OK
4.2.18. If calibration is delayed and if the calibration is implemented after the monitoring period in consideration (i.e. the results of delayed calibration are available) for the certain monitoring period, has the error been applied in following ways?	EB 111 Report Annex 2 §367 VCS Std. Version 4.1	DR	N/A (The calibration of the meters is valid ten years).	OK	OK

*DR= Document Review, I= Interview, SV=Site Visit

Question	Reference	Means of verification *	Findings, comments, references and document sources	Draft opinion	Final opinion
4.2.18.1. The adjusted measured values of the delayed calibration result in fewer claimed emission reductions?	EB 111 Report Annex 2 §367a VCS Std. Version 4.1	DR	N/A (The calibration of the meters is valid ten years).	OK	OK
4.2.18.2. For all measured values taken during the period between the scheduled date of calibration and the actual date of calibration?	EB 111 Report Annex 2 §367b VCS Std. Version 4.1	DR	N/A (The calibration of the meters is valid ten years).	OK	OK
4.2.19. If the results of the delayed calibration aren't available, have Pss calculated the emission reductions conservatively?	EB 111 Report Annex 2 §368	DR	N/A (The calibration of the meters is valid ten years).	OK	OK
4.2.20. If the results of the delayed calibration aren't available, have post registration requirements been followed by the PPs?	EB 111 Report Annex 2 §369	DR	N/A (The calibration of the meters is valid ten years).	OK	OK
4.2.21. Have any information about appropriate emission factors, IPCC default values and any other reference values that have been used in the calculation of emission reductions been given in detail in the MR?	VCS Std. Version 4.1	DR	N/A	OK	OK
4.2.22. If the data that are monitored been listed under section 4.2 using the tabular format, does the listed data include all the parameters used to calculate baseline, project and leakage emissions as well as other relevant parameters required by the approved methodology and the monitoring plan?	VCS Std. Version 4.1 EB 111 Report Annex 1 §361b	DR	EGfacility,y, CAPpj and Apj are the monitored parameters in line with the registered PD.	OK	OK
4.2.23. Is a complete set of data available for the specified monitoring period?	EB 111 Report Annex 1 §361d VCS Std. Version 4.1	DR	EGfacility,y, CAPpj and Apj are the monitored parameters in line with the registered PD.	OK	OK

*DR= Document Review, I= Interview, SV=Site Visit

Question	Reference	Means of verification *	Findings, comments, references and document sources	Draft opinion	Final opinion
4.3. Monitoring Plan					

*DR= Document Review, I= Interview, SV=Site Visit

Question	Reference	Means of verification *	Findings, comments, references and document sources	Draft opinion	Final opinion
4.3.1. Has a description of the monitoring system been provided under Section 4.3 of the MR?	EB 111 Report Annex 1 §258 VCS Std. Version 4.1	DR	The details of the monitoring system is available and in line with the registered PD but please see in below: Please check the number of employees both in the organizational structure diagram and text part of the Section 4.3 of the MR along with the relevant evidence.	CAR-21	OK
4.3.2. Has information about the data collection procedures, including following been provided under Section 4.3 of the MR?	EB 111 Report Annex 1 §258 VCS Std. Version 4.1	DR	Please see in below.	OK	OK
4.3.2.1. Information flow including data generation	EB 111 Report Annex 1 §258 VCS Std. Version 4.1	DR	The details of the data generation is available and in line with the registered PD.	OK	OK
4.3.2.2. Data aggregation	EB 111 Report Annex 1 §258 VCS Std. Version 4.1	DR	The details of the data aggregation is available and in line with the registered PD.	OK	OK
4.3.2.3. Data recording	EB 111 Report Annex 1 §258 VCS Std. Version 4.1	DR	The details of the data recording is available and in line with the registered PD.	OK	OK
4.3.2.4. Data calculation	EB 111 Report Annex 1 §258 VCS Std. Version 4.1	DR	The details of the data calculation (net electricity generation) is available and in line with the registered PD.	OK	OK

*DR= Document Review, I= Interview, SV=Site Visit

Question	Reference	Means of verification *	Findings, comments, references and document sources	Draft opinion	Final opinion
4.3.2.5. Data reporting	EB 111 Report Annex 1 §258 VCS Std. Version 4.1	DR	The details of the data reporting is available and in line with the registered PD.	OK	OK
4.3.3. Has organizational structure, roles and responsibilities of personnel, and emergency procedures for the monitoring system been provided under section 4.3 of the MR?	EB 111 Report Annex 1 §258 VCS Std. Version 4.1	DR	The brief information about the roles and responsibilities of each personnel (like project engineer and technicians etc.) has been provided in the Section 4.3 of the MR.	OK	OK
4.3.4. Regarding to the management and operational system, are the responsibilities and authorities for monitoring and reporting in accordance with the responsibilities and authorities stated in the monitoring plan?	EB 111 Report Annex 2 §361b-(iv) VCS Std. Version 4.1	DR	The brief information about the roles and responsibilities of each personnel (like project engineer and technicians etc.) has been provided in the Section 4.3 of the MR.	OK	OK
4.3.5. Have quality assurance and quality control procedures been applied in accordance with the monitoring plan?	EB 111 Report Annex 1 §361e VCS Std. Version 4.1	DR	Please clarify the main source of EGfacility,y parameter in the Section 4.3 of the MR.	CAR-22	OK
4.3.6. Are the procedures for handling internal auditing and non-conformities described?	VCS Std. Version 4.1	DR	These have been described in the Section 4.3 of the MR.	OK	OK
4.3.7. Where appropriate, are the line diagrams to display the GHG data collection and management system included?	VCS Std. Version 4.1	DR	N/A (This is explained without any diagram).	OK	OK
4.3.8. If the sampling approaches used in the monitoring plan, has the following been included?	VCS Std. Version 4.1	DR	N/A (The sampling approach hasn't been used).	OK	OK
4.3.8.1. target precision levels	VCS Std. Version 4.1	DR	N/A (The sampling approach hasn't been used).	OK	OK
4.3.8.2. sample sizes	VCS Std. Version 4.1	DR	N/A (The sampling approach hasn't been used).	OK	OK
4.3.8.3. sample site locations	VCS Std. Version 4.1	DR	N/A (The sampling approach hasn't been used).	OK	OK

*DR= Document Review, I= Interview, SV=Site Visit

Question	Reference	Means of verification *	Findings, comments, references and document sources	Draft opinion	Final opinion
4.3.8.4. stratification	VCS Std. Version 4.1	DR	N/A (The sampling approach hasn't been used).	OK	OK
4.3.8.5. frequency of measurement and	VCS Std. Version 4.1	DR	N/A (The sampling approach hasn't been used).	OK	OK
4.3.8.6. QA/QC procedures	VCS Std. Version 4.1	DR	N/A (The sampling approach hasn't been used).	OK	OK
4.3.8.7. Demonstration on whether the required confidence/precision has been met.	VCS Std. Version 4.1	DR	N/A (The sampling approach hasn't been used).	OK	OK
4.3.9. Have the monitoring plan and the applied methodology been properly implemented and followed by the PPs?	EB 111 Report Annex 2 §361a VCS Std. Version 4.1	DR	The monitoring system is available and in line with the registered PD.	OK	OK
4.3.10. Has the monitoring of parameters (baseline / project / leakage / emission reduction) in the project activity been implemented in accordance with the monitoring plan contained in the registered PD or any accepted revised monitoring plan?	EB 111 Report Annex 2 §361b-(i)-(ii)-(iii) VCS Std. Version 4.1	DR	The monitoring system is available and in line with the registered PD.	OK	OK
4.3.11. Have all parameters stated in the monitoring plan, the applied methodology and relevant VCS requirements been sufficiently monitored and updated as applicable?	EB 111 Report Annex 1 §361b VCS Std. Version 4.1	DR	The monitoring system is available and in line with the registered PD.	OK	OK
4.3.12. Are monitoring results consistently recorded and stored as per the approved frequency?	EB 111 Report Annex 1 §361d VCS Std. Version 4.1	DR	The monitoring system is available and in line with the registered PD.	OK	OK

*DR= Document Review, I= Interview, SV=Site Visit

Question	Reference	Means of verification *	Findings, comments, references and document sources	Draft opinion	Final opinion
5. QUANTIFICATION of GHG EMISSION REDUCTIONS and REMOVALS					
5.1. Baseline Emissions					
5.1.1. Has all the formulae used to calculate the baseline emissions been provided under section 5.1 of the MR?	VCS Std. Version 4.1	DR	a) Please provide EPIAS screenshots and TEIAS meter readings associated with the monitoring period. b) Please correct the monitoring start and end dates considering the end of previous monitoring period. c) Please correct the ER calculations considering above points.	CAR-23	OK
5.1.2. Has sample calculations for all formulae used and calculation of baseline emissions or baseline net GHG removals by sinks, applying actual values been provided under section 5.1 of the MR?	VCS Std. Version 4.1	DR	This is available in the Excel spreadsheet calculation but please see CAR-23.	CAR-23	OK
5.1.3. Has all electronic spread sheets to present full calculations in the monitoring report been attached?	VCS Std. Version 4.1	DR	This is available in the Excel spreadsheet calculation.	OK	OK
5.1.4. Have any assumptions used in baseline emission calculations been justified?	EB 111 Report Annex 2 §373d VCS Std. Version 4.1	DR	N/A (There haven't been any assumptions used).	OK	OK
5.1.5. If applicable, are the appropriate emission factors used for the baseline emission calculations in line with the good guidance practices? (e.g. IPCC default values and other reference values)	EB101 Report Annex 2 §373e VCS Std. Version 4.1	DR	N/A (The grid emission factor has been calculated and determined during the validation process).	OK	OK

*DR= Document Review, I= Interview, SV=Site Visit

Question	Reference	Means of verification *	Findings, comments, references and document sources	Draft opinion	Final opinion
5.2. Project Emissions					
5.2.1. Has all the formulae used to calculate the project emissions been provided under section 5.2 of the MR?	VCS Std. Version 4.1	DR	The power density calculation has been provided in the Excel spreadsheet calculation as indicated in the MR.	OK	OK
5.2.2. Has sample calculations for all formulae used and calculation of project emissions or or actual net GHG removals by sinks, applying actual values been provided under section 5.2 of the MR?	VCS Std. Version 4.1	DR	This is available in the Excel spreadsheet calculation.	OK	OK
5.2.3. Has all electronic spreadsheets to present full calculations in the monitoring report been attached?	VCS Std. Version 4.1	DR	This is available in the Excel spreadsheet calculation.	OK	OK
5.2.4. Have any assumptions used in project emission calculations been justified?	EB93 EB 111 Report Annex 2 §373d VCS Std. Version 4.1	DR	N/A (There haven't been any assumptions used).	OK	OK
5.2.5. If applicable, are the appropriate emission factors used for the project emission calculations in line with the good guidance practices? (e.g. IPCC default values and other reference values)	EB 111 Report Annex 2 §373e VCS Std. Version 4.1	DR	N/A (The grid emission factor has been calculated and determined during the validation process).	OK	OK

*DR= Document Review, I= Interview, SV=Site Visit

Question	Reference	Means of verification *	Findings, comments, references and document sources	Draft opinion	Final opinion
5.3. Leakage					
5.3.1. Has all the formulae used to calculate the leakage emissions been provided under section 5.3 of the MR?	VCS Std. Version 4.1	DR	The leakage emissions are zero and this has been explained in the MR but please correct the methodology reference in the Section 5.3 of the MR.	CAR-24	OK
5.3.2. Has sample calculations for all formulae used and calculation of leakage emissions, applying actual values been provided under section 5.3 of the MR?	VCS Std. Version 4.1	DR	Please see CAR-24.	CAR-24	OK
5.3.3. Has all electronic spread sheets to present full calculations in the monitoring report been attached?	VCS Std. Version 4.1	DR	Please see CAR-24.	CAR-24	OK
5.3.4. Have any assumptions used in leakage emission calculations been justified?	EB 111 Report Annex 2 §373d VCS Std. Version 4.1	DR	N/A (There haven't been any assumptions used).	OK	OK
5.3.5. If applicable, are the appropriate emission factors used for the leakage emission calculations in line with the good guidance practices? (e.g. IPCC default values and other reference values)	EB 111 Report Annex 2 §373e VCS Std. Version 4.1	DR	N/A (The grid emission factor has been calculated and determined during the validation process).	OK	OK

*DR= Document Review, I= Interview, SV=Site Visit

Question	Reference	Means of verification *	Findings, comments, references and document sources	Draft opinion	Final opinion
5.4. Net GHG Emission Reductions and Removals					
5.4.1. Have the total baseline emissions or baseline net GHG removals by sinks during the monitoring period been given under section 5.4 of the MR?	VCS Std. Version 4.1	DR	Please see CAR-23	CAR-23	OK
5.4.2. Has the total project emissions or actual net GHG removals by sinks during the monitoring period been given under section 5.4 of the MR?	VCS Std. Version 4.1	DR	This is available in the Section 5.4 of the MR but please correct the unnecessary wording in the Section 5.4 of the MR.	CAR-25	OK
5.4.3. Has the total leakage emissions during the monitoring period been given under section 5.4 of the MR?	VCS Std. Version 4.1	DR	This is available in the Section 5.4 of the MR.	OK	OK
5.4.4. Have the total emission reductions or net anthropogenic GHG removals by sinks during the monitoring period been given under section 5.4 of the MR?	VCS Std. Version 4.1	DR	Please see CAR-23	CAR-23	OK
5.4.5. If there is material information that can cause overestimation of emission reductions or removals of the project activity, is this equal to higher than one of the following?	EB 111 Report Annex 2 §326	DR	There hasn't been any material information detected.	OK	OK
5.4.5.1. 0.5 per cent of the emission reductions or removals for project activities achieving a total emission reduction or removal of equal to or more than 500,000 tons of carbon dioxide equivalent per year?	EB 111 Report Annex 2 §326a	DR	There hasn't been any material information detected.	OK	OK
5.4.5.2. 1 per cent of the emission reductions or removals for project activities achieving a total emission reduction or removal between 300,000 and 500,000 tons of carbon dioxide equivalent per year?	EB 111 Report Annex 2 §326b	DR	There hasn't been any material information detected.	OK	OK

*DR= Document Review, I= Interview, SV=Site Visit

Question	Reference	Means of verification *	Findings, comments, references and document sources	Draft opinion	Final opinion
5.4.5.3. 2 per cent of the emission reductions or removals for large-scale project activities achieving a total emission reduction or removal of 300,000 tons of carbon dioxide equivalent per year or less?	EB 111 Report Annex 2 §326c	DR	There hasn't been any material information detected.	OK	OK
5.4.5.4. 10 per cent of the emission reductions or removals for the microscale project activities?	EB 111 Report Annex 2 §326e	DR	There hasn't been any material information detected.	OK	OK
5.4.5.5. 5 per cent of the emission reductions or removals for small-scale project activities other than project activities covered under 5.4.5.4 above?	EB 111 Report Annex 2 §326d	DR	There hasn't been any material information detected.	OK	OK
6. APPENDICES					
6.1. If any further background information regarding any raw data from monitoring is provided, is this information correct and supported by the appropriate evidence?	VCS Std. Version 4.1	DR	There hasn't been any appendices provided in the MR.	OK	OK
6.2. If any further background information regarding additional information used in the monitoring plan is provided, is this information correct and supported by the appropriate evidence?	VCS Std. Version 4.1	DR	There hasn't been any appendices provided in the MR.	OK	OK
6.3. If any further background information regarding documentation of activities conducted from the monitoring plan and diagrams are provided, is this information correct and supported by the appropriate evidence?	VCS Std. Version 4.1	DR	There hasn't been any appendices provided in the MR.	OK	OK

*DR= Document Review, I= Interview, SV=Site Visit

Question	Reference	Means of verification *	Findings, comments, references and document sources	Draft opinion	Final opinion
7. OTHER REQUIREMENTS					
7.1. Forward Action Requests (FARs) Identified During Validation and/or Previous Verification					
7.1.1. Is there any remaining FARs from the validation and/or previous verification activities?	EB 111 Report Annex 2 §343	DR	There hasn't been any FARs in line with the provided initial monitoring period verification report.	OK	OK
7.1.2. If there any remaining FARs from the validation and/or previous verification activities, have the PPs addressed these FARs in the MR?	EB 111 Report Annex 2 §343	DR	There hasn't been any FARs in line with the provided initial monitoring period verification report.	OK	OK
7.1.3. Has the FARs been resolved?	EB 111 Report Annex 2 §343 §346	DR	There hasn't been any FARs in line with the provided initial monitoring period verification report.	OK	OK

*DR= Document Review, I= Interview, SV=Site Visit

Table 2 – Resolution of Corrective Action, Forward Action and Clarification Requests

Draft Report Clarifications, Forward Action and Corrective Action Requests By Verification Team	Ref. to Checklist Questions in Table-1	Summary of Project Participants' Response	Verification Team Conclusion
CAR-1 Please clarify whether all items in the box at the bottom of the cover page and all Sections text part using Arial 10.5 pt, black, regular (non-italic) font since the provided MR is pdf document.	1	All Sections have been revised.	Review-1: Ok Closed (MR has been revised accordingly).
CAR-2 Please check and correct the project name in line with the VCS registry, registered PDD and validation report.	2.1	Project name has been revised.	Review-1: Ok Closed (Project name has been revised in the MR).
CAR-3 Please correct the monitoring start and end dates considering the end of previous monitoring period.	2.6	Monitoring start and end dates have been corrected. Review-1: Monitoring period has been revised accordingly.	Review-1: Please correct the monitoring period considering maximum 6 year monitoring period requirement. Review-2: Ok Closed (Monitoring period has been revised throughout the MR and Excel spreadsheet).
CAR-4 a) Please correct the commissioning date of first turbine under Section 1.1 of the MR. b) Please correct the initial and second monitoring period details under Section 1.1 of the MR. c) Please provide the relevant evidence documents for the turbine properties.	1.1.1	a) It's been corrected. b) They have been corrected. c) Evidence documents for the turbine properties have been provided to the DOE. Review-1: b) MR period has been revised accordingly. c) - Ministry Acceptance Protocols are available to the DOE. - Turbine name plates and evidence documents have been provided to the DOE. d) It's been included in the Section 1.1 of the MR.	Review-1: a) Ok Closed (Section 1.1 of the MR has been revised accordingly). b) Please correct the current monitoring period considering maximum 6 year monitoring period requirement under Section 1.1 of the MR. c) - Please provide the provisional acceptance protocols along with the equipment details. - Please provide the turbine name plates and evidence documents instead of generator documents. d) Please include the project's installed capacity as MWm and MWe in the Section 1.1 of the MR. Review-2: b) Ok Closed (Monitoring period has been revised throughout the MR and Excel spreadsheet).

* CAR= Corrective Action Request, FAR= Forward Action Request, CL= Clarification Request

Draft Report Clarifications, Forward Action and Corrective Action Requests By Verification Team	Ref. to Checklist Questions in Table-1	Summary of Project Participants' Response	Verification Team Conclusion
			c) Ok Closed (The provisional acceptance protocols dated as 27/05/2010 and 07/11/2010 including the turbine and equipment details have been provided). d) Ok Closed (Section 1.1 of the MR has been revised accordingly).
CAR-5 Please provide the purpose of the project activity in the Section 1.1 of the MR.	1.1.2	Purpose of the project activity has been included in the Section 1.1 of the MR.	Review-1: Ok Closed (The purpose of the project activity has been included in the Section 1.1 of the MR).
CAR-6 Please include the brief description of the installed technology and equipment including turbine types, brand and relevant reference documents in the Section 1.1 of the MR.	1.1.3	Section 1.1 of the MR has been revised. Review-1: a) Turbine model, serial numbers and associated properties have been included. b) Turbine name plates and evidence documents have been provided to the DOE.	Review-1: a) Please include the turbine model and serial number and associated properties in the Section 1.1 of the MR. b) Please provide the turbine name plates and evidence documents instead of generator documents. Review-2: a) Ok Closed (Section 1.1 of the MR has been revised accordingly). b) Ok Closed (The provisional acceptance protocols dated as 27/05/2010 and 07/11/2010 including the turbine and equipment details have been provided).
CAR-7 Please provide the construction date of the project activity in the Section 1.1 of the MR.	1.1.4	The construction date of the project activity has been provided. Review-1: It's been provided.	Review-1: The construction date is different in the initial verification report and MR. Review-2: Ok Closed (Section 1.1 of the MR has been revised accordingly).
CAR-8 Please correct the end date of crediting period in the Section 1.6 of the MR.	1.6.1	It's been corrected. Review-1: a) The Ministry Acceptance Protocols are available to the DOE.	Review-1: a) The project start date is available as 27/05/2010 but please provide the relevant justification along with the evidence document in the Section 1.5 of the MR.

* CAR= Corrective Action Request, FAR= Forward Action Request, CL= Clarification Request

Draft Report Clarifications, Forward Action and Corrective Action Requests By Verification Team	Ref. to Checklist Questions in Table-1	Summary of Project Participants' Response	Verification Team Conclusion
		b) The crediting period type has been included in the Section 1.6 of the MR.	b) Please include the crediting period type in the Section 1.6 of the MR. Review-1: a) Ok Closed (Section 1.5 of the MR has been revised accordingly). b) Ok Closed (Section 1.6 of the MR has been revised accordingly).
CAR-9 Please include the reference document information for all provided coordinates in Section 1.7 of the MR.	1.7.1	Review-1: It's been included in Section 1.7 of the MR.	Review-1: Please include the reference document information for all provided coordinates in Section 1.7 of the MR. Review-2: Ok Closed (Section 1.7 of the MR has been revised accordingly).
CAR-10 Please correct the version number of the methodology in the Section 1.8 of the MR.	1.8.1.1	It's been corrected.	Review-1: Ok Closed (The version number of the methodology in the Section 1.8 of the MR).
CAR-11 Please correct the version number of the referred tools in the Section 1.8 of the MR.	1.8.2	It' been corrected. Review-1: All relevant tools have been included.	Review-1: Please include all relevant tools in line with the registered PD Review-2: Ok Closed (Section 1.8 of the MR has been revised accordingly).
CAR-12 It has been stated that the project hasn't been registered or seeking registration under other GHG programs but please provide a signed and sealed letter on company letterhead that the project hasn't been registered, or hasn't been seeking registration under any other GHG programs.	1.9.1	Signed and sealed letter has been provided to the DOE. Review-1: Signed and sealed letter is available to the DOE.	Review-1: It has been stated that the project hasn't been registered or seeking registration under other GHG programs but please provide a signed and sealed letter on company letterhead that the project hasn't been registered, or hasn't been seeking registration under any other GHG programs. Review-2: Ok Closed (The signed declaration by PP and dated as 26/02/2021 has been provided).

* CAR= Corrective Action Request, FAR= Forward Action Request, CL= Clarification Request

Draft Report Clarifications, Forward Action and Corrective Action Requests By Verification Team	Ref. to Checklist Questions in Table-1	Summary of Project Participants' Response	Verification Team Conclusion
CAR-13 Please provide a signed and sealed letter on company letterhead that project hasn't been created other forms of credit (e.g. renewable energy certificates).	1.10.1	Signed and sealed letter has been provided to the DOE. Review-1: Signed and sealed letter is available to the DOE.	Review-1: Please provide a signed and sealed letter on company letterhead that project hasn't been created other forms of credit (e.g. renewable energy certificates). Review-2: Ok Closed (The signed declaration by PP and dated as 26/02/2021 has been provided).
CAR-14 a) Please correct the future tense sentences in the Section 2.2 of the MR since the project is already operational. b) Please provide the current status details of the project in the Section 2.2 of the MR.	2.2.1.1	a) Section 2.2 has been revised accordingly. b) They've been provided. Review-1: b) "KARADENİZ" has been clarified in the Section 2.2 of the MR c) Section 2.2 of the MR has been revised accordingly. d) Section 2.2 of the MR has been revised accordingly. e) The actual contributions of the project have been included. f) Section 2.1 has been revised accordingly.	Review-1: a) Ok Closed (Section 2.2 of the MR has been revised accordingly). b) Please clarify the meaning of "KARADENİZ" in the Section 2.2 of the MR. c) Please check and remove unnecessary details in the Section 2.2 of the MR. d) Please include the date of mentioned announcement and relevant village name in the Section 2.2 of the MR. e) Please include the actual contribution of the project to SDG-8 in the Section 1.11 of the MR. f) Please include the precautions taken for the possible negative environmental and socio-economic impacts of the project activity in the Section 2.1 of the MR. Review-2: b) c) Ok Closed (Section 2.2 of the MR has been revised accordingly). d) Ok Closed (The signed letters by Incesu and Cataldere Mukhtars (Village Heads) and dated as 26/02/2021 have been provided). e) Ok Closed (Section 1.1 of the MR has been revised accordingly). f) Ok Closed (Section 2.1 of the MR has been revised accordingly).

* CAR= Corrective Action Request, FAR= Forward Action Request, CL= Clarification Request

Draft Report Clarifications, Forward Action and Corrective Action Requests By Verification Team	Ref. to Checklist Questions in Table-1	Summary of Project Participants' Response	Verification Team Conclusion
CAR-15 a) Please provide the signed document about the contact details of the PP relevant staff in case of any complaint by Incesu and Çataldere villages and whether there is any complaint received by the Muhktars from the local stakeholders. b) Please provide the evidence of the communication methods (announcements and meetings) with the local stakeholders during the monitoring period.	2.2.1.3	a) b) Any complaint or need from the local community could directly be received by the project owner and appropriate contributions or improvements are made to the local community. An announcement stating the contact details of the Project relevant staff in case of any complaint by close surroundings has been put up on the Mosque of the village to be seen by the villagers. Review-1: The contact information of the plant responsible exist at the Mukhtar. The project owner regularly checks with the Mukhtar if any complaint or a request exists. Any complaint or need from the local community could directly be received by the project owner and appropriate contributions or improvements are made to the local community. Regarding the monitoring period, a signed letter by the Mukhtar has been provided as declaring that the related information has been available to the villagers.	Review-1: a) Please provide the signed document about the contact details of the PP relevant staff in case of any complaint by Incesu and Çataldere villages and whether there is any complaint received by the Muhktars from the local stakeholders. b) Please provide the evidence of the communication methods (announcements and meetings) with the local stakeholders during the monitoring period Review-2: a) Ok Closed (The signed letters by Incesu and Cataldere Mukhtars (Village Heads) and dated as 26/02/2021 have been provided). b) Ok Closed (Section 2.2 of the MR has been revised accordingly).
CAR-16 All data that is determined only once for the crediting period but are used after registration of the project, has been listed under Section 4.1 of the MR but please include the values applied of FCI,y and NCVi,y parameters.	4.1.1	Values applied of Fci,y and NCVi,y parameters have been included.	Review-1: Ok Closed (Section 4.1 of the MR has been revised accordingly).
CAR-17 Please indicate for each data/parameter provided under Section 4.1 of the MR what the data/parameters are used for (baseline/project /leakage emission calculations).	4.1.9	Each data/parameter has been revised accordingly.	Review-1: Ok Closed (Section 4.1 of the MR has been revised accordingly).
CAR-18 a) Please include the meter test and calibration dates of the electricity meters.	4.2.7	a) The meter test and calibration dates of the electricity meters have been included. b) They have been provided. c) The photographic evidences of electricity meters have been provided to the DOE.	Review-1: a) Please include last two meter test dates in the Section 4.2 of the MR.

* CAR= Corrective Action Request, FAR= Forward Action Request, CL= Clarification Request

Draft Report Clarifications, Forward Action and Corrective Action Requests By Verification Team	Ref. to Checklist Questions in Table-1	Summary of Project Participants' Response	Verification Team Conclusion
b) Please provide the electricity meter test protocols including meter change ones covering the monitoring period. c) Please provide the photographic evidences of electricity meters. d) Please provide the photographic evidences of turbine name plates and turbine documents. e) Please provide the reservoir area evidence documents. f) Please provide the project capacity evidence documents. g) Please correct the future tense sentence for QA/QC procedures of CAPpj parameter since the project is operational.		d) The photographic evidences of turbine name plates and turbine documents have been provided to the DOE. e) The reservoir area evidence documents have been provided to the DOE. f) The screenshot of the project license from the website of EMRA is available to the DOE. g) It's been corrected. Review-1: a) Last two meter test dates have been included. b) They have been provided to the DOE. d) They have been provided to the DOE. e) It's been provided to the DOE. f) Ministry acceptance protocols and generation license have been provided to the DOE. g) Whole MR has been revised accordingly.	b) Please provide the electricity meter test protocols including meter change ones covering the monitoring period. c) Ok Closed (The photographic evidences of electricity meters have been provided). d) Please provide the photographic evidences of turbine name plates and turbine documents since the generator documents have been provided. e) Please provide the reservoir area evidence documents. f) Please provide the project capacity evidence documents including the generation licence of the project. g) Please correct the future tense sentences throughout the MR (e.g. Sections 1.11 and 4.2 of the MR). Review-2: a) Ok Closed (Section 4.2 of the MR has been revised accordingly). b) Ok Closed (The meter test protocols including meter change ones have been provided). d) Ok Closed (The provisional acceptance protocols dated as 27/05/2010 and 07/11/2010 including the turbine and equipment details have been provided). e) Ok Closed (The reservoir area evidence document (registered PD) has been provided). f) Ok Closed (The generation licence and provisional acceptance protocols have been provided). g) Ok Closed (MR has been revised accordingly).
CAR-19	4.2.8	Purpose for each data/parameter has been provided.	Review-1:

* CAR= Corrective Action Request, FAR= Forward Action Request, CL= Clarification Request

Draft Report Clarifications, Forward Action and Corrective Action Requests By Verification Team	Ref. to Checklist Questions in Table-1	Summary of Project Participants' Response	Verification Team Conclusion
Please provide the purpose for each data/parameter provided in the Section 4.2 of the MR.			Ok Closed (Section 4.1 of the MR has been revised accordingly and the purpose for each data/parameter has been included in the Section 4.2 of the MR).
CAR-20 Please correct the monitoring frequency of EGfacility,y parameter.	4.2.11	It's been corrected.	Review-1: Ok Closed (Section 4.2 of the MR has been revised accordingly).
CAR-21 Please check the number of employees both in the organizational structure diagram and text part of the Section 4.3 of the MR along with the relevant evidence.	4.3.1	It's been checked and revised. Review-1: a) Social security records of PP site employees are available to the DOE. b) It has been clarified.	Review-1: a) Please provide the social security records of PP site employees. b) Please clarify the reference to 120 employee in the Section 2.2 of the MR. Review-2: a) Ok Closed (The social security records of PP site employees have been provided). b) Ok Closed (Section 2.2 of the MR has been revised accordingly).
CAR-22 Please clarify the main source of EGfacility,y parameter in the Section 4.3 of the MR.	4.3.5	It's been clarified. Review-1: It has been clarified.	Review-1: Please clarify the main source of EGfacility,y parameter in the Section 4.3 of the MR. Review-2: Ok Closed (Section 4.3 of the MR has been revised accordingly).
CAR-23 a) Please provide EPIAS screenshots and TEIAS meter readings associated with the monitoring period. b) Please correct the monitoring start and end dates considering the end of previous monitoring period. c) Please correct the ER calculations considering above points.	5.1.1	a) EPIAS screenshots and TEIAS meter readings have been provided to the DOE. b) The monitoring start and end dates have been corrected. c) It's been corrected. Review-1: a) EPIAS screenshots and TEIAS meter readings associated with the monitoring period have been provided to the DOE.	Review-1: a) Please provide EPIAS screenshots and TEIAS meter readings associated with the monitoring period. b) Please correct the monitoring period considering maximum 6 year monitoring period requirement. c) Please correct the ER calculations considering above points.

* CAR= Corrective Action Request, FAR= Forward Action Request, CL= Clarification Request

Draft Report Clarifications, Forward Action and Corrective Action Requests By Verification Team	Ref. to Checklist Questions in Table-1	Summary of Project Participants' Response	Verification Team Conclusion
		b) It's been corrected. c) It's been corrected. d) Main source of Emission factor parameter has been revised accordingly throughout the MR. Review-2: c) Related sections have been revised accordingly.	d) Please include the EPIAS screenshots as the main source of Emission factor parameter throughout the MR. Review-2: a) Ok Closed (EPIAS screenshots and TEIAS meter readings have been provided). b) Ok Closed (Monitoring period has been revised throughout the MR and Excel spreadsheet). c) - Please use round down function in each vintage subtotal and total ER values. - Please correct the F10 cell in Comparison of baseline Emissions Excel spreadsheet. - Please correct the ER calculations considering above points in the Excel spreadsheet and throughout the MR. - Please correct the comparison calculation in the Excel spreadsheet and throughout the MR. d) Ok Closed (MR has been revised accordingly). Review-3: c) - Ok Closed (Round down function has been used and Excel spreadsheet has been revised accordingly). - Ok Closed (Excel spreadsheet and Section 1.1 of the MR have been revised accordingly).
CAR-24 The leakage emissions are zero and this has been explained in the MR but please correct the methodology reference in the Section 5.3 of the MR.	5.3.1	Section 5.3 has been revised accordingly.	Review-1: Ok Closed (Section 5.3 of the MR has been revised accordingly).
CAR-25	5.4.2	It's been corrected.	Review-1:

* CAR= Corrective Action Request, FAR= Forward Action Request, CL= Clarification Request

Draft Report Clarifications, Forward Action and Corrective Action Requests By Verification Team	Ref. to Checklist Questions in Table-1	Summary of Project Participants' Response	Verification Team Conclusion
Please correct the unnecessary wording in the Section 5.4 of the MR.			Ok Closed (Section 5.4 of the MR has been revised accordingly).
CL-1 Please check and clarify if the relevant person and contact details are up to date in the Section 1.3 of the MR.	1.3.1	It's been checked and clarified. Review-1: Section 1.3 of the MR has been revised accordingly.	Review-1: Please check and correct the email address of PP in the Section 1.3 of the MR. Review-2: Ok Closed (Section 1.3 of the MR has been revised accordingly).
CL-2 Please provide the following records: - The noise assessment report, if any, - The photographic evidences of hazardous waste and waste water storage areas - The hazardous waste transfer and disposal records - The waste water transfer and disposal records - Training records for PP site employees - The social security records of PP site employees	2.1.1	- The noise assessment report is available to the DOE. - The photographic evidences of hazardous waste and waste water storage areas are available to the DOE. -The hazardous waste transfer and disposal are available to the DOE. - The waste water transfer and disposal records have been provided to the DOE. - Training records for PP site employees are available to the DOE. - The social security records of PP site employees are available to the DOE. Review-1: - The photographic evidences of hazardous waste and waste water storage area are available to the DOE. - The hazardous waste transfer and disposal records are available to the DOE. - The waste water transfer and disposal records are available to the DOE. - The fish passage photographic evidences are available to the DOE. - Line line water official signed by State Hydraulic Works are available to the DOE. - The social security records of PP site employees are available to the DOE.	Review-1: - Ok Closed (The noise assessment report has been provided). - Ok Closed (Training records for PP site employees have been provided). Please provide the following records: - The photographic evidences of hazardous waste and waste water storage area - The hazardous waste transfer and disposal records - The waste water transfer and disposal records - The fish passage photographic evidences - Life line water official records signed by State Hydraulic Works - The social security records of PP site employees Review-2: - Ok Closed (The photographic evidences of hazardous waste and waste water storage area have been provided).

* CAR= Corrective Action Request, FAR= Forward Action Request, CL= Clarification Request

Draft Report Clarifications, Forward Action and Corrective Action Requests By Verification Team	Ref. to Checklist Questions in Table-1	Summary of Project Participants' Response	Verification Team Conclusion
		Review-2: -Waste-water transfer and disposals have been handled under the contract with Madenli Belediye Başkanlığı. The contracts are available to the VVB. - The photographic evidences of waste water storage area are available to the VVB.	- Ok Closed (The hazardous waste transfer and disposal records have been provided). - Please provide the waste water transfer and disposal records associated with the monitoring period. - Ok Closed (The fish passage photographic evidences have been provided). - Ok Closed (Life line water official records signed by State Hydraulic Works have been provided). - Ok Closed (The social security records of PP site employees have been provided). Review-3: - Ok Closed (The signed agreement with Madenli Municipality including the wastewater disposal process has also been provided).
CL-3 a) Please clarify the PP of the project activity whether it is Karadeniz Elektrik Uretim San. A.S. or Karadeniz HES Elektrik A.Ş. along with the relevant evidence. b) Please clarify in the Section 3.1 of the MR if there are any other entities involved in the project defined in the registered PD.	3.1.9	a) The screenshot of the project license from the website of EMRA is available to the DOE (http://lisans.epdk.gov.tr/epvys-web/faces/pages/lisans/elektrikUretim/elektrikUretimOzetSorgula.xhtml) The PP is Karadeniz HES Elektrik A.Ş. b) Section 3.1 has been revised accordingly. Review-1: a) b) Section 3.2.2 of the MR has been revised accordingly. Review-2: Generation license has been provided to the VVB.	Review-1: a) Please include PP name change details in the Section 3.2.2 of the MR along with the relevant evidence. b) The other entities involved in the project have been clarified in the Section 3.1 of the MR but please clarify the same details in the Section 3.2.2 of the MR. Review-2: a) - Section 3.2.2 of the MR has been revised but please provide the currently available generation license of the project activity. - Please clarify the reference to China in VCS registry page of the project.

* CAR= Corrective Action Request, FAR= Forward Action Request, CL= Clarification Request

Draft Report Clarifications, Forward Action and Corrective Action Requests By Verification Team	Ref. to Checklist Questions in Table-1	Summary of Project Participants' Response	Verification Team Conclusion
			b) Ok Closed (Section 3.2.2 of the MR has been revised accordingly). Review-3: - Ok Closed (The generation licence has been provided). - Ok Closed (PP has applied to VCS for the correction of the information in the registry and it is expected to be completed until the finalization of the issuance process).

* CAR= Corrective Action Request, FAR= Forward Action Request, CL= Clarification Request

ANNEX 2: VERIFICATION TEAM AND ITR COMPETENCE

Anıl SÖYLER, Bsc. in Environmental Engineering, has completed his Bachelor degree in Middle East Technical University, Turkey. He has more than 15 years of professional experience in environmental management, monitoring and auditing, waste and waste water management, environmental and social impact assessment, GHG emission report and projects' validation and verification, environmental reports, team and client relationship management and quality management systems and has been involved in the validation/verification services of more than 200 GHG emission reduction projects in total. He has also been involved in both national and international projects supported by IFC, World Bank and EBRD. He has been working as Certification Manager in the context of Re Carbon.

Sandeep KANDA holds a degree in Mechanical Engineering, Masters in Energy systems engineering from Indian Institute of Technology – Bombay and Post Graduate Diploma in Industrial Safety & Environmental Management from National Institute of Industrial Engineering in India. He has more than ten years of work experience with auditing and consultancy firms, seven years thereof with Designated Operational Entities under the CDM. He is experienced working on diversified areas of energy and environmental management, including policies, Clean Development Mechanism (CDM), Corporate Sustainability Reporting (CSR) Audits, energy audits, utility audits and product development. As CDM auditor and technical reviewer for TÜV Süd, he has audited more than 30 CDM projects as technical reviewer; 40 projects as lead auditor and 7 PoAs in various capacities; covering a broad range of sectoral scopes, such as Energy industries (renewable - / non-renewable sources), Energy distribution, Energy demand, Manufacturing industries, Chemical industries, Transport, Metal production, Waste handling & disposal and Agriculture. He has been working as a contracted team leader, technical reviewer, TA 1.1 and renewable energy expert in the context of Re Carbon.

Annex 2-1: Appointment Certificates

Re Carbon G�zetim Denetim ve Belgele�tme Ltd. �t�. Prof. Dr. Aziz Sancar Cad. 27/6 TR : 06890 �ankaya-Ankara Tel : 0390-312-287 5122 Fax: 0090-312-287 3373	Certificate of Appointment	
	Carbon Division	Page: 1/1

This Certificate of Appointment is given to **Mr. Anil S YLER** as a confirmation of compliance with internal qualification requirements as follows:

Clean Development Mechanism				
Validator	Verifier	Team leader	Technical reviewer	Technical Expert
08-02-2021	08-02-2021	N/A	N/A	08-02-2021

Verified Carbon Standard, Gold Standard, World Commission on Dams, Social Carbon				
Validator	Verifier	Team leader	Technical reviewer	Technical Expert
08-02-2021	08-02-2021	08-02-2021	N/A	08-02-2021


Speciality	Regional (Country) expertise	Financial expertise	Technical area
N/A	Turkey	N/A	1.2 and 13.1

Within the scope and in strict accordance to the appointment indicated above, the bearer can:

1. Participate in the assessments conducted by Re Carbon Ltd.
2. Take the roles within and outside of the assessment team
3. Bring specific expertise to the assessments

This Certificate of Appointment is valid unless there are changes in the related requirements for the qualification and appointment and/or the personnel's work agreement is terminated and there is no defined validity period for this Certificate.

However, The Certificate may be updated, suspended or canceled at any time, as a result of the performance assessments and/or other reasons as defined above.

APPOINTMENT IS GRANTED BY			
Mr. Christian JOHANNES	General Manager	08-02-2021	
Name	Position	Date	Signature

Re Carbon B&Sistem Gıda ve Belgelendirme Ltd. Şti. Prof. Dr. Aziz Sancar Cad. 27/3 TR / 06690 Çankaya Ankara Tel : 0312-287 5122 Fax: 0312-287 3373	Certificate of Appointment Carbon Division	 Page: 1/1
---	--	---

This Certificate of Appointment is given to **Mr. Sandeep KANDA** as a confirmation of compliance with internal qualification requirements as follows:

Clean Development Mechanism				
Validator	Verifier	Team leader	Technical reviewer	Technical Expert
08-02-2021	08-02-2021	08-02-2021	08-02-2021	08-02-2021

Verified Carbon Standard, Gold Standard, World Commission on Dams, Social Carbon				
Validator	Verifier	Team leader	Technical reviewer	Technical Expert
08-02-2021	08-02-2021	08-02-2021	08-02-2021	08-02-2021

Speciality	Regional (Country) expertise	Financial expertise	Technical area
N/A	India, Vietnam, Nepal and Turkey	N/A	1.1, 1.2, 2.1, 3.1, 4.1, 8.1, 9.2, 13.1, 13.2 & 15.1

Within the scope and in strict accordance to the appointment indicated above, the bearer can:

1. Participate in the assessments conducted by Re Carbon Ltd.
2. Take the roles within and outside of the assessment team
3. Bring specific expertise to the assessments

This Certificate of Appointment is valid unless there are changes in the related requirements for the qualification and appointment and/or the personnel's work agreement is terminated and there is no defined validity period for this Certificate.

However, The Certificate may be updated, suspended or cancelled at any time, as a result of the performance assessments and/or other reasons as defined above.

APPOINTMENT IS GRANTED BY			
Mr. Anil SÖYLER	Certification Manager	08-02-2021	
Name	Position	Date	Signature

RC-19 / 21.01.2020-02