



SINOP LANDFILL GAS TO ELECTRICITY PROJECT

VERIFICATION REPORT



Report ID	4014
Project title	Sinop Landfill Gas to Electricity Project
Project ID	4014
Verification period	01-March-2023 to 31-August-2024
Original date of issue	17-October-2024
Most recent date of issue	05-06-2025
Version	05

VCS Standard Version	4.6
Client	Biokütle Enerji Elektrik Üretim A.Ş.
Prepared by	Bureau Veritas (India) Pvt. Ltd.
Approved by	Mr. Sanjay PATANKAR (Independent Technical Reviewer) Mr. Sameer PENDSE (Technical Expert for ITR for TA 13.1)
Work carried out by	Ms. Öykü YAKUPOĞLU (Team Leader)

Summary:

“Sinop Landfill Gas to Electricity Project” is operated by “Biokütle Enerji Elektrik Üretim A.Ş.”. The project activity is located in Merkez District of Sinop Province, Turkey. The purpose of the project activity is to generate electricity and supply it into the national grid. The landfill gas is collected on the project site and the generated electricity with using this landfill gas is transmitted to Turkish National Grid. The project includes one gas engine which has the installed capacity of 1.453 MWm / 1.414 MWe as per the provisional acceptance protocol. As per the generation license, the license has been obtained for two gas engines. However, the second gas engine will be commissioned in future (expected in 2025). The amount of solid waste is 78,731.11 tonnes/monitoring period based on the calibrated weighbridge records. The total value of received waste during the monitoring period was confirmed by the VVB by examining the weighbridge records.

The commissioning date of the gas engine is 29-June-2021. However, the operation has been started in 01-July-2021. This date can be confirmed via the EPIAS records. Also, this date has been validated through validation process of the project activity.

The project comes under Sectoral Scope 1: Energy industries (renewable - / non-renewable sources) and Sectoral Scope 13: Waste handling and disposal.

The scope of the verification is the independent and objective review of the implementation of the project activity/monitoring plan and the amount of achieved GHG reductions. The verification activity also is based on VCS Program Guide version 4.4 and VCS Standard version 4.6, as well as criteria provided in the CDM methodologies (AMS-III.G, v10.0 and AMS-I.D, v18.0) and the methodological tools which reported in the VCS MR, version 05 dated 05 June 2025.

The verification conducted included three main phases which eventually led to the issuance of this final version of the VCS MR and Verification opinion, listed below:

- Desk review
- On-site visit and follow-up interviews with the relevant personnel and local stakeholders
- Resolution of outstanding issues and the issuance of final VCS MR and Verification opinion

During this verification activity, 14 Corrective Action Requests (CARs) and 04 Clarification Requests (CLs) were raised all of which were successfully closed. No Forward Action Request (FAR) has been issued during this verification activity.

Bureau Veritas (India) Pvt. Ltd. hereby confirms that the data reported and used in the quantifications of the emission reductions are accurate, complete, transparent, and free of material error and consistent with the project activity's monitoring plan and the requirements set out in the applied methodology, the applied methodological tools, and VCS Standard v4.6. The verification team did not detect any uncertainties associated with the verification.

This is the second monitoring period (01-March-2023 to 31-August-2024) of the first crediting period (01-July-2021 to 30-June-2028).

Bureau Veritas (India) Pvt. Ltd. confirms the following based on the results of document review for the period between 01 March 2023 and 31 August 2024:

Year	Achieved Baseline Emissions or Removals (tCO ₂ e)	Achieved Project Emissions or Removals (tCO ₂ e)	Achieved Leakage Emissions (tCO ₂ e)	Achieved Net GHG Emission Reductions or Removals (tCO ₂ e)
01/03/2023 – 31/12/2023	23,612	0	0	23,612
01/01/2024 – 31/08/2024	20,140	0	0	20,140
Total	43,752	0	0	43,752

CONTENTS

1	INTRODUCTION	5
1.1	Objective	5
1.2	Scope and Criteria	5
1.3	Level of Assurance.....	6
1.4	Summary Description of the Project	6
2	VERIFICATION PROCESS	8
2.1	Method and Criteria.....	9
2.2	Document Review	11
2.3	Interviews.....	14
2.4	Site Visits.....	15
2.5	Resolution of Findings	16
2.6	Eligibility for Validation Activities	17
3	VALIDATION FINDINGS	17
3.1	Methodology Deviations.....	17
3.2	Project Description Deviations.....	17
3.3	New Project Activity Instances in Grouped Projects.....	18
3.4	Baseline Reassessment	18
4	VERIFICATION FINDINGS.....	18
4.1	Project Details	18
4.2	Safeguards and Stakeholder Engagement	22
4.3	Accuracy of Reduction and Removal Calculations.....	33
4.4	Quality of Evidence to Determine Reductions and Removals.....	37
4.5	Non-Permanence Risk Analysis.....	37
5	VERIFICATION OPINION.....	37
5.1	Verification Summary	37
5.2	Verification Conclusion	39
5.3	Ex-ante vs Ex-post ERR Comparison	39
	APPENDIX 1: COMMERCIALLY SENSITIVE INFORMATION	41
	APPENDIX 2: VERIFICATION PROTOCOL	42

1 INTRODUCTION

1.1 Objective

Bureau Veritas (India) Pvt. Ltd. has been appointed by “Biokütle Enerji Elektrik Üretim A.Ş.” to perform the verification of “Sinop Landfill Gas to Electricity Project”. The objective of this verification activity are to assess, with objective evidences:

- Whether the implementation and operation of the project activity is compatible with the information provided in the registered VCS Joint PD-MR version 07 dated 04 June 2024
- Whether all physical features of the project activity indicated in the registered VCS Joint PD-MR version 07 dated 04 June 2024 (e.g. installed technology, monitoring equipment and so on) are in place
- Whether the quantifications of the emission reductions and supporting documents are accurate, complete, transparent, and free of material error and consistent with the project activity's monitoring plan and the requirements set out in the applied methodology, the applied methodological tools, and VCS Standard v4.6
- Whether the monitoring systems and processes in place are in accordance with the monitoring systems and procedures outlined in the approved methodologies and the monitoring plan in the registered VCS Joint PD-MR version 07 dated 04 June 2024
- Whether the necessary ex-ante and ex-post data are monitored correctly in accordance with the applied methodologies, tools, VCS requirements, and the registered VCS Joint PD-MR version 07 dated 04 June 2024

1.2 Scope and Criteria

The scope of this verification activity which conducted by Bureau Veritas (India) Pvt. Ltd. is the independent and objective review of the project activity and relevant achieved GHG emission reductions. In this regard, the scope is set by:

- The Article 12 of the Kyoto Protocol
- VCS Standard, v4.6
- VCS Program Guide, v4.4
- VCS Validation and Verification Manual, v3.2
- CDM Validation and Verification Standard for Project Activities, v3.3
- AMS-III.G: Landfill methane recovery, v10.0
- AMS-I.D: Grid-connected renewable electricity generation, v18.0

- All associated methodological tools
- Environmental and social issues related to the Sectoral Scope 1: Energy industries (renewable - / non-renewable sources) and Sectoral Scope 13: Waste handling and disposal
- ISO 14064-3:2019 Greenhouse Gases – Part 3: Specification with guidance for the verification validation of greenhouse gas statements

The verification is not meant to provide any consulting towards the client. However, stated requests for clarifications and/or corrective actions may provide input for improvement of the project design. Therefore, Bureau Veritas (India) Pvt. Ltd. cannot be held liable by any party for decisions made or not made based on the verification, which will go beyond that purpose.

1.3 Level of Assurance

Bureau Veritas (India) Pvt. Ltd. hereby confirms that the level of assurance of this verification report is reasonable, with respect to material errors, omissions and misrepresentations. To guarantee this level of assurance all data that is used in the GHG emission reduction calculations were reviewed without any sampling.

1.4 Summary Description of the Project

“Sinop Landfill Gas to Electricity Project” is operated by “Biokütle Enerji Elektrik Üretim A.Ş.”. The project activity is located in Merkez District of Sinop Province, Turkey. The project coordinates of the project activity have been confirmed via the generation license. Also, the KMZ file of the project activity were provided by the project owner. As per this document, the coordinates are as follows:

Corners	N	E
Corner 1	41.949269823	35.036668530
Corner 2	41.949272309	35.036911608
Corner 3	41.949194300	35.036913527
Corner 4	41.949194861	35.036979850
Corner 5	41.948934092	35.036983778
Corner 6	41.948930761	35.036673646

The purpose of the project activity is to generate electricity and supply it into the national grid. The landfill gas is collected on the project site and the generated electricity with using this landfill gas is transmitted to Turkish National Grid. The project includes one gas engine which has the installed capacity of 1.453 MWm / 1.414 MWe as per the provisional acceptance protocol. As per the generation license, the license has been obtained for two gas engines. However, the second gas engine will be commissioned in future (expected in 2025). The amount of solid waste is 78,731.11 tonnes/monitoring period based on the weighbridge records. The total value of received waste during the monitoring period was confirmed by the VVB by examining the weighbridge records.

The chronology timeline of the project activity is as follows:

Date	Action
December 2020	Feasibility Report
11-December-2020	Operation Contract Between Project Owner and Sinop Coastal Municipalities Union
16-June-2021	EIA Exemption Letter
24-June-2021	EMRA Generation License
25.-June-2021	Grid Connection Agreement
29-June- 2021	Sinop Landfill Provisional Acceptance
01-July-2021	Start of Operation and Crediting Period
18-October-2022	Local Stakeholder Consultation Meeting
01-July-2021 to 30-June-2028	First Crediting Period
01-July-2021 to 28-February-2023	First Monitoring Period
01-March-2023 to 31-August-2024	Second (Current) Monitoring Period

The project activity includes the following units:

- Chiller

Brand - Model: Ürker Chillers - UC ASH 15.1

Chilling capacity: 37.24 kW/h

Total power drawn: 13.58 kW/h
- Gas Holder

Brand - Model: Ecomembrane - 2MASTER®

Volume: 3500 m³
- Gas Engine

Brand – Model: Jenbacher – JGS 420 GS-L.L

Mechanical Output: 1453 kW

Electrical Output: 1414 kW

Gas Volume: 851 Nm³/h

Electrical Efficiency: 41.5%

- Gas Analyzer

Brand: MRU GmbH

Type: SWG 100

- Weighbridge

Brand: ABS

Type: B2

Calibration Date: 04 August 2022 and 28 October 2024

The technical details have been confirmed by the VVB via the technical specification documents of the installed technology.

The commissioning date of the gas engine is 29-June-2021. However, the operation has been started in 01-July-2021. This date can be confirmed via the EPIAS records. Also, this date has been validated through validation process of the project activity.

This is the second monitoring period (01-March-2023 to 31-August-2024) of the first crediting period (01-July-2021 to 30-June-2028). The vintage values of the emission reductions of this monitoring period are as follows:

01/03/2023 - 31/12/2023	23,612 tCO _{2e}
01/01/2024 - 31/08/2024	20,140 tCO _{2e}

2 VERIFICATION PROCESS

The key milestones of the verification activity are as follows:

Verification Milestone	Date
Kick-off Meeting	13 August 2024
Desk Review	13 August 2024 - 17 October 2024
On-site Visit	15 August 2024

Preparation of the Draft Verification Report	17 October 2024
Independent Technical Review	05 November 2024
Preparation of the Final Verification Report	05 November 2024

2.1 Method and Criteria

Bureau Veritas (India) Pvt. Ltd. has been appointed by “Biokütle Enerji Elektrik Üretim A.Ş.” to perform the verification of “Sinop Landfill Gas to Electricity Project”. Verification was conducted following the Bureau Veritas (India) Pvt. Ltd. procedures created in line with the requirements of the VCS Standard v4.6, VCS Program Guide v4.4 and standard auditing techniques.

A competent assessment team is arranged before the verification process begins. For the purpose of assessing the VCS project activities, the team is chosen to address the technical areas, sectoral scopes and relevant host country experience. To further ensure quality and completeness, a competent Independent Technical Reviewer team is also assigned. The verification team visits the site after conducting a desk review, from which a draft report and a protocol of findings are formed. The evaluation of the results by direct connection with the project owner is the following step, and the preparation of the Verification report is taken in place. This Joint Verification report and other supporting documents then undergo an internal quality before submission to VCS.

The verification process includes the following independent and objective activities:

- Select a verification team with ensuring team members are qualified to perform verification activities pertaining to the Project. The verification team consisted of the following individuals:

Team Leader: Ms. Öykü YAKUPOĞLU

- Select an Independent Technical Reviewer with ensuring qualification to perform verification activities pertaining to the Project. The Independent Technical Reviewer consisted of the following individual:

Independent Technical Reviewer: Mr. Sanjay PATANKAR

Technical Expert for TA 13.1: Mr. Sameer PENDSE

- Perform a conflict of interest assessment. There were no conflicts of interest identified between Bureau Veritas (India) Pvt. Ltd. and Biokütle Enerji Elektrik Üretim A.Ş.
- Conduct a kick-off meeting Biokütle Enerji Elektrik Üretim A.Ş. to introduce the Biokütle Enerji Elektrik Üretim A.Ş. and Bureau Veritas (India) Pvt. Ltd. teams, review the verification objectives, process, VCS requirements, and confirm the auditing schedule

- Develop a verification plan to be used throughout the verification process.
- Review the current MR (v05, dated 05 June 2025) against VCS Standard requirements and applied Methodology requirements. Information in the current MR (v05, dated 05 June 2025) was the primary focus of the verification process. Bureau Veritas (India) Pvt. Ltd. cross-checked information in the MR against supporting evidence and documents to confirm the project start date, location, selection and continuity of baseline scenario, ownership, and monitoring plan.
- Conduct a physical site visit (dated 15 August 2024) to selected project activity instances. Details about the selection of project activity instances selected and the site visit are discussed in more detail in section 2.4 of this Verification report below.
- Review the accuracy and reasonableness of the achieved emission reductions for the 2nd Monitoring Period of the 1st Crediting Period.
- Issue corrective action requests (CARs), clarification requests (CLs), and forward action requests (FARs) as necessary

- Issue a Verification report
- Hold an exit meeting with Biokütle Enerji Elektrik Üretim A.Ş.

The competence of team members and technical reviewer is as follows:

- Ms. Öykü Yakupoğlu is qualified Team Leader and auditor for scope 1.2 and 13.1-2 for validation and verification of GHG projects. She is actively working in the climate change domain for 3 years and involved in validation/ verification of around 140 projects under Gold Standard/ VERRA/ GCC and ICR. Ms. Öykü is graduate in Environmental Engineering from Middle East Technical University and in Chemistry (M.Sc.) from Gazi University and currently pursuing her PhD in Energy Systems Engineering from Ankara Yıldırım Beyazıt University.
- Mr. Sanjay Patankar, Educational qualifications: B.E. (Mech.) M.E. (Mech.). He has over 30 years of experience in various fields such as engineering manufacturing industry covering various functions like enterprise management, product design, engineering, tool & die design, improvements in the production shop, quality assurance & control and systems planning and implementation, including ISO 9001 based quality management systems. He has conducted numerous verification assignments in carbon accounting, CDM and Sustainability and certification. He has worked for 15+ years in Bureau Veritas Certification (India) Pvt. Ltd. in various functions such as Lead Auditor for ISO 9001, ISO 50001, ISO 14064-1 standards and was responsible for technical reviews, accreditation and quality management of sustainability schemes such as ISO 50001, GHG and CDM within Bureau Veritas India.
- Mr. Sameer PENDSE is the Lead auditor in Bureau Veritas Certification for Environment Management System, Quality Management System and Occupational Health and Safety Management System. He is working with BV Certification since 21 years. He has done post-graduation in the field of Environmental Science and several years of Industrial work experience in the field of environmental management systems, including various waste management and treatment techniques. He has carried out validation and verification of several projects under CDM instrument. Sameer is also a trainer for various IRCA approved training programmes.

2.2 Document Review

The basis for the verification activity is the VCS MR version 01 dated 20 August 2024 which was submitted to the verification team on the same date. This VCS MR was revised due to the issued CARs and CLs, version 05 dated 05 June 2025 being the final version.

The following actions were involved in the desk review:

- A review of the data and information presented to verify their completeness

- A review of the monitoring plan and monitoring methodology, paying particular attention to the frequency of measurements, the quality of metering equipment including calibration requirements, and the quality assurance and quality control procedures
- An evaluation of data management and the quality assurance and quality control system in the context of their influence on the generation and reporting of emission reductions

The list of the documents which were reviewed during the verification period is given in the below:

Document Number	Document Name	Version	Date (DD/MM/YYYY)
D01	Registered VCS Joint PD-MR	07	04/06/2024
D02	VCS Joint Validation-Verification Report	04	04/06/2024
D03	AMS-III.G: Landfill methane recovery	10.0	14/06/2019
D04	AMS-I.D: Grid connected renewable electricity generation	18.0	28/11/2014
D05	Monitoring Report	01	20/08/2024
D06	Monitoring Report	02	10/10/2024
D07	Monitoring Report	03	16/10/2024
D08	Monitoring Report	04	14/04/2025
D09	Monitoring Report	05	05/06/2025
D10	ER Calculation Excel Sheet	01	20/08/2024
D11	ER Calculation Excel Sheet	02	10/10/2024
D12	ER Calculation Excel Sheet	03	16/10/2024
D13	VCS Standard	4.6	21/03/2024
D14	VCS Program Guide	4.4	29/08/2023
D15	EIA Not Required Document	-	16/06/2021
D16	Generation License	-	24/06/2021
D17	Provisional Acceptance Document	-	29/06/2021
D18	EPIAS Screenshots	-	03/2023 – 08/2024

D19	OSOS Records	-	03/2023 – 08/2024
D20	First Index Protocols of Electricity Meters	-	26/05/2021
D21	Hazardous Waste Disposal Records	-	07/07/2023 13/10/2023 30/11/2023 25/12/2023 18/04/2024 30/05/2024 11/07/2024
D22	Leachate Disposal Agreement (between PO and Gerze Municipality)	-	19/03/2024
D23	Weighbridge Records		04/08/2022 28/10/2024
D24	Single Line Diagram	-	-
D25	HSE Training Records of Employees	-	17/08/2023 16/09/2024
D26	Environmental Training Records of Employees	-	03/08/2023 03/04/2024
D27	Signed Letter about Double Counting by Project Owner	-	17/09/2024
D28	Social Security Records of the Employees	-	-
D29	KMZ file of the Project Activity	-	-
D30	Weighbridge Calibration Documents	-	04/08/2022 28/10/2024
D31	CDM Tool 03	03.0	22/09/2017
D32	CDM Tool 04	08.1	24/03/2023
D33	CDM Tool 05	03.0	22/09/2017

D34	CDM Tool 07	07.0	23/11/2012
D35	CDM Tool 09	03.0	12/06/2020
D36	CDM Tool 10	01	16/10/2009
D37	CDM Tool 11	03.0.1	02/03/2012
D38	CDM Tool 16	05.0	11/03/2022
D39	CDM Tool 32	04.0	11/03/2022

2.3 Interviews

During the verification period, follow-up interviews were realized by the VVB to further analyze the correctness and accurateness of the information provided. The main topics covered during the interview are as follows:

- Installed technology and monitoring equipment (e.g. electricity meters) of the project activity
- Project implementation and operation
- Staff training procedures
- Calibration procedures of the monitoring equipment
- Monitoring system
- Data collection, recording and reporting procedure
- QA/QC procedures
- Eligibility criteria of VCS
- Emission reduction calculations
- Evaluation of values of ex-post parameter
- Comments from local stakeholders about the implementation of the project activity

The list of people who were interviewed during the physical verification site visit handled on 15 August 2024 is given below:

Reference Number	Means of Interview	Full Name	Title	Organization
I01	Site Visit	Muhsin Dugan	Business Manager	Biokütle Enerji
I02	Site Visit	Sinem Öngörü Öktem	Consultant	GAIA Climate
I03	Site Visit	Karabey Yalçın	Mukhtar	Hacıoğlu Village

I04	Site Visit	Şenol İnce	Local Stakeholder	Hacıoğlu Village
I05	Site Visit	Salim Korakçı	Local Stakeholder	Hacıoğlu Village
I06	Site Visit	Necati Kaymak	Electrical Technician	Biokütle Enerji
I07	Site Visit	İlker Akdemir	Facility Manager	Biokütle Enerji
I08	Site Visit	Aykut Erdal	HSE Specialist	Biokütle Enerji

2.4 Site Visits

As a part of the verification activities, a physical site visit was performed to the project activity site on 15 August 2024 and details of which can be seen in below:

Subject	Source of Information
Checking technical specifications of the Installed Technology and Monitoring Equipment	Physical site visit observations and interview with the power plant manager
Assessing continuity of Baseline Scenario	Physical site visit observations, interview with the local stakeholders
Location of the Project Activity	Physical site visit observations and GPS
Assessing monitoring approaches (e.g. SCADA system)	Physical site visit observations, interview with the power plant manager and the employees
Receiving comments from Local Stakeholders	Interviews with the local stakeholders
Review of information flows for generating, aggregating and reporting the monitoring parameters	Document review, physical site visit observations, interviews with the project proponent representatives
Cross-check between information provided in the VCS MR and data from other sources such as plant log books, purchase records or similar data sources	Physical site visit observations, document review
Identification of quality control and quality assurance procedures in place to prevent or identify and correct any errors or omissions in the reported monitoring parameters	Document review, physical site visit observations, interviews with the project proponent representatives

All the monitoring parameters furnished by the project proponent have been cross-checked with the electronic records and operational logbooks.

During the on-site visit, the mukhtar of Hacıoğlu Village confirmed that the local stakeholders were informed about the project activity before the implementation. Also, he stated that no complaints were received by the local stakeholders during the current monitoring period.

Furthermore, there had not been any complaint raised by the interviewed local stakeholders during the on-site visit dated 15 August 2024. The local stakeholders as stated in Section 2.3 of this verification report were interviewed about the following issues and there had not been any complaint by the interviewed local stakeholders during the on-site visit:

- Noise due to the project activity
- Odor due to the project activity
- Sufficiency of local employment (The interviewed local stakeholders were pleased about the provided local employment opportunities by the project owner)
- Waste management practices implemented by the project owner

It was also concluded that the grievance mechanism is in place and this was also confirmed by the interviewed local stakeholders during the on-site visit dated 15 August 2024. Also, the photographic evidences of the grievance book were provided to the VVB. So far, no complaints have been recorded in the grievance book.

2.5 Resolution of Findings

The verification of this VCS project activity includes the following steps:

- Assessment of the conformity of the actual project activity and its operation with respect to the registered VCS Joint PD-MR version 07 dated 04 June 2024
- A site visit was conducted on 15 August 2024 to assess that all physical features of the project activity are in place and that the project participants has operated the project activity as per the registered VCS Joint PD-MR version 07 dated 04 June 2024
- Assessment of the compliance of the monitoring plan with the monitoring methodologies AMS-III.G (v10.0) and AMS-I.D (v18.0)
- Assessment of the compliance of monitoring with the monitoring plan
- Assessment of data and calculation of greenhouse gas emission reductions
- Issuance of the Verification Report
- Independent technical review

- Approval of the Verification Report and request of issuance
 - In order to ensure transparency a verification protocol, which shows in a transparent manner criteria (requirements), means of verification and VVB findings and final VVB conclusions, is customized for the project activity. All findings and outstanding issues, identified during the desk review and discussed during the site observation, are included in a list of CARs, CLs and FARs.
 - During this verification activity, 14 Corrective Action Requests (CARs) and 04 Clarification Requests (CLs) were raised all of which were successfully closed. All CARs/CLs which are organized in Appendix 2, have been resolved by the project proponent via provision of additional supporting evidence and appropriate revision of the VCS MR. No FAR has been issued. For the purpose of completeness, the completed Verification protocol is also enclosed to the Verification report in Appendix 2.

2.5.1 Forward Action Requests

The verification team raises a FAR during the verification for actions if the monitoring and reporting require attention and/or adjustment in the next verification period.

According to these principles no FAR has been issued during this verification process.

2.6 Eligibility for Validation Activities

Bureau Veritas (India) Pvt. Ltd. holds accreditation for the validation and verification activities in Scope 1: “Energy Industries – Renewable/Non-renewable Sources” and Scope 13: “Waste handling and disposal” in which the project activity falls into.

3 VALIDATION FINDINGS

3.1 Methodology Deviations

N/A (There are no methodology deviations.)

3.2 Project Description Deviations

The other entity involved in the project was Life İklim ve Enerji Ltd. Şti. in the project description. However, it has been changed as Gaia Climate Finansal Danışmanlık Hizmetleri ve Ticaret A.Ş. after the 1st monitoring period.

As per registered VCS Joint PD-MR, installation of second generator is planned to be completed as of 2024. However, currently, still only one-unit gas engine is in operation and the second unit is planned to start operation in 2025.

Bureau Veritas (India) Pvt. Ltd. hereby confirms that such changes have no impact on the applicability of the methodology, additionality and the appropriateness of the baseline scenario.

3.3 New Project Activity Instances in Grouped Projects

N/A (The project activity is not a grouped project.)

3.4 Baseline Reassessment

Did the project undergo baseline reassessment during the monitoring period?

☐ Yes

☒ No

4 VERIFICATION FINDINGS

4.1 Project Details

Item	Evidence gathering activities, evidence checked, and assessment conclusion:				
Audit history	The desk review of the project activity was started on 13 August 2024. On 15 August 2024, the physical site visit was conducted. During the verification activity, 14 Corrective Action Requests (CARs) and 04 Clarification Requests (CLs) were raised all of which were successfully closed. All findings and conclusions are indicated in Appendix 2. No Forward Action Request (FAR) has been issued during this verification activity. The desk review was concluded on 17 October 2024. Moreover, the previous audits of the project activity are as follows:				
	Audit type	Period	Program	VVB name	Number of years
	Joint Validation & Verification	01-July-2021 to 30-June-2028 (Validation)	VCS	Applus+ Certification	7 years (Validation) 1 year 8 months (Verification)

	01-July-2021 to 28-February-2023 (Verification)			
2nd Verification	01-March-2023 to 31-August-2024	VCS	Bureau Veritas (India) Pvt. Ltd.	1 year and 6 months
Double counting and participation under other GHG programs	A signed declaration dated 17/09/2024 was provided by the project proponent to the VVB about double counting. Moreover, the verification team also checked the I-REC Registry (https://evident.services/device-register) and this project is not available within I-REC Registry database. Similarly, GS project database (https://registry.goldstandard.org/projects?q=&page=1), ICR project database (https://www.carbonregistry.com/explore/projects), BCR project database (https://biocarbonregistry.com/en/projects/) and GCC project database (https://projects.globalcarboncouncil.com/pages/submitted_projects) were checked and this project is not available within GS, ICR, BCR and GCC projects' databases, either. Given that CDM projects are not applicable in Turkey and the project does not appear on domestic REC scheme, I-REC, GS, ICR, BCR and GCC registries, it could be confirmed that no RECs and other VER carbon credits are being issued for the project at the time of this verification.			
No double claiming with emissions trading programs or binding emission limits	As a host country in Turkey such any programme like a government-regulated system or programme for the constraint and monetization of GHG emissions (such as emissions trading scheme, cap and trade or carbon tax mechanisms) has not been implemented. The project does not participate under any emission trading program and other GHG Programs including renewable energy certificates (RECs) and this is also confirmed by the PP through the signed and sealed letter by PP dated as 17/09/2024.			
No double claiming with other forms of environmental credit	Turkey has a voluntarily market. There are no environmental credit schemes implemented in Turkey. Therefore, there is no double claiming with other forms of environmental credit.			
Supply chain (scope 3) emissions double claiming	The project activity utilizes LFG to produce electricity. Therefore, the project activities does not affect the emissions footprint of any product(s) (goods or services) that are part of a supply chain.			

Sustainable development contributions	The project makes a positive impact on SDG 7 (Affordable and Clean Energy) through the generation of 8,788.376 MWh of net electricity. It also contributes to SDG 8 (Decent Work and Economic Growth) by employing a total of 12 staff members during the most recent year of operation. Furthermore, the project supports SDG 13 (Climate Action) by achieving an emission reduction of 43,752 tCO₂e throughout the monitoring period. The documents reviewed by the VVB to confirm these SDG contributions are as follows: • For SDG 7: Official EPIAS electricity records • For SDG 8: Social security records of the employees • For SDG 13: Official EPIAS electricity records and the emission factor which was determined during the validation process The estimated emission reductions for this monitoring period is 56,014 tCO₂e. Therefore, there is -28.03% difference between the estimated and achieved GHG emission reduction amounts. Ex-ante calculations are higher than ex-post emission reductions. For ex-ante emissions, there are many assumptions to calculate emission reductions, so the difference is acceptable such project. Also, during the ex-ante calculations, it was planned to commission the second gas engine in 2024. However, the second gas engine was not commissioned in 2024. The monitoring parameters are selected in line with the applied methodologies (AMS-III.G, v10.0 and AMS-I.D, v18.0) and the registered VCS Joint PD-MR (v07 dated 04 June 2024): • $EG_{PJ,y}$: Quantity of net electricity supplied by the project activity to the grid in year y (MWh) • $F_{CH_4,BL,R,y}$: Amount of methane in the LFG which is flared due to a requirement in year y (tCH₄/yr) • $p_{reg,y}$: Fraction of LFG that is required to be flared due to a requirement in year y • EG_y: Quantity of gross electricity generation (MWh) • EE_y: Energy Conversion Efficiency of the project equipment (%)
--	---

The applied methodologies and tools refer this monitoring parameter. Bureau Veritas (India) Pvt. Ltd. has checked Data Unit, Description, Source of Data, Value Applied, Justification of choice of data or description of measurement methods and procedures applied and Purpose of Data of this parameter in the applied methodologies and tools. All information for the monitoring parameter has been indicated correctly in the VCS MR, version 05 dated 05 June 2025.

For EG_{PJ,y} monitoring parameter, there are two electricity meters at the project site. The electricity meters were checked during the on-site visit dated 15 August 2024. One is the main meter and the other one is the back-up meter. The electricity generation/consumption values read on the meters constitute the EPIAS records. EPIAS records have been used as the main source. All EPIAS records between March 2023 – August 2024 were provided to the VVB at the time of the verification. For the cross-check purposes OSOS records have been used. The periodical calibration or maintenance is under the responsibility of TEIAS and is fixed as once in 10 years¹. However, the meters can be replaced by the decision of TEIAS staff.

During the current monitoring period, there is no meter change process. The technical details of the current electricity meters are as follows:

Equipment	Serial Number	Brand Model	Accuracy Class	Date of Calibration
Main meter	80341274	Makel-C520KMT2556	C Class (0.5)	26 May 2021
Backup meter	80272124	Makel-CC20KMT2556	C Class (0.5)	26 May 2021

The technical details of the electricity meters have been checked via the first index protocols of the meters. The calibrations dated 26 May 2021 were provided by the PP.

Internal reviews of the metered data are consistently performed. A SCADA system is in place, generating daily reports. The data collected daily is stored in the plant manager's computer and backed up.

¹ <https://www.resmigazete.gov.tr/eskiler/2016/06/20160629-22.htm>

	All data collected as part of monitoring will be archived electronically by the project owner and be kept at least for 2 years after the end of the last crediting period. For $F_{CH_4,BL,R,y}$, there is no regulation in Türkiye that mandates the flaring of LFG. Please refer to Regulation on Landfill of Waste². Besides this, there is a gas holder at the project site. No gas has been flared during the monitoring period For $p_{reg,y}$, as per regulation of the country there is no obligation to utilize or destroy methane. Please refer to Regulation on Landfill of Waste³. For EG_y, the quantity of generated electricity monitored by SCADA meter on generator with PLC system. Measurements are monitored continuously and recorded by project staff monthly basis. As per these records, during the current monitoring period, 9,183.85 MWh electricity was consumed by the project activity. For EE_y, default value in AMS-III.G v 10 has been used. 40% is taken for this parameter.
Additional information relevant to the project	N/A (There is no additional information relevant to the project.)

4.2 Safeguards and Stakeholder Engagement

4.2.1 Stakeholder Identification

Item	Evidence gathering activities, evidence checked, and assessment conclusion
Stakeholder identification	The nearest settlement to the project activity is Hacıoğlu Village. The stakeholders likely to be impacted by the project activity are from this location. Additionally, relevant stakeholders such as non-governmental organizations (NGOs), ministries, and government bodies were recognized.

² <https://www.mevzuat.gov.tr/mevzuat?MevzuatNo=13887&MevzuatTur=7&MevzuatTertip=5>

³ <https://www.mevzuat.gov.tr/mevzuat?MevzuatNo=13887&MevzuatTur=7&MevzuatTertip=5>

	The local community was notified about the stakeholder meeting through announcements posted on 05 October 2022. These announcements were displayed in densely populated parts of the neighborhood to ensure visibility. In addition, potential stakeholders received formal invitations via official emails sent on 06 October 2022. During that meeting, no negative comments were recorded. Moreover, local stakeholders from Hacıoğlu Village were interviewed during the physical site visit dated 15 August 2024. Also, during this interview, no negative comments were received by the VVB.
Legal or customary tenure/access rights	Article 9 of the Environmental Impact Assessment Regulation. EIA approval was obtained by the PP. During the validation period, necessary permits were acquired.
Stakeholder diversity and changes over time	Local stakeholders from different sectors and ages were interviewed during the physical site visit held on 15 August 2024. They have positive opinions for the project activity. The interviews with the local stakeholders, which consists of a diverse group of people, is important for the project to appeal to all segments of society. Most of the stakeholders are villagers from Hacıoğlu Village, Merkez District, Sinop Province, Turkey.
Expected changes in well-being	The project activity has positive contributions to the local stakeholders such as: • Employment opportunities • Providing security • Some aids such as road construction and some equipment assistance • Clear signs of climate change in the region in recent years The contact information of the plant responsible exist at the Mukhtar. The project owner and local community are always in touch. The project owner regularly checks with the Mukhtar if any complaint or a request exists. There were no negative comments received from the local stakeholders during the physical site visit. In summary, local communities are supporting the project and they believe that it creates a momentum for local sustainable development.

	All related information confirmed during the physical interviews.
Location of stakeholders	Hacioğlu Village, Merkez District, Sinop Province, Turkey
Location of resources	Hacioğlu Village, Merkez District, Sinop Province, Turkey

4.2.2 Stakeholder Consultation and Ongoing Communication

Item	Evidence gathering activities, evidence checked, and assessment conclusion
Ongoing consultation	The contact information of the plant responsible exist at the Mukhtar. The project owner and local community are always in touch. The project owner regularly checks with the Mukhtar if any complaint or a request exists. Any complaint or need from the local community could directly be received by the project owner and appropriate contributions or improvements are made to the local community. All related information confirmed during the physical interviews. The project proponent has established the on-going communication mechanism with the stakeholders involved, who can reach them in case of any grievances through: Direct communication: Contact information of the authorized person from the owner company is available at village head's office so that the local stakeholders can reach these people whenever they have any complaints, suggestions, or ideas about the project. Any complaints or needs of the local community can be addressed directly to the project proponent. Also, during the on-site visit, local stakeholders were interviewed about the ongoing consultation and grievance mechanism, and it has been confirmed that the locals have knowledge about the same. Moreover, there is a logbook for the grievance mechanism at the Mukhtar. So far, no comments were recorded in the logbook.
Date(s) of stakeholder consultation	Physical site visit date for the joint validation-verification process: 14-15 May 2023 Physical site visit date for the current monitoring period: 15 August 2024

Communication of monitored results	There had not been any complaint raised by the interviewed local stakeholders during the on-site visit dated 15 August 2024. The local stakeholders as stated in Section 2.3 of this verification report were interviewed about the following issues and there had not been any complaint by the interviewed local stakeholders during the on-site visit: - Noise due to the project activity - Odor due to the project activity - Sufficiency of local employment (The interviewed local stakeholders were pleased about the provided local employment opportunities by the project owner) - Waste management practices implemented by the project owner It was also concluded that the grievance mechanism is in place and this was also confirmed by the interviewed local stakeholders during the on-site visit dated 15 August 2024. Also, the photographic evidences of the grievance book were provided to the VVB. So far, no complaints have been recorded in the grievance book. Any complaints or needs of the local community can be addressed directly to the project proponent either.
Consultation records	8 people participated on the site visit dated 15 August 2024 and 4 of them from Biokütle Enerji employees, 1 of them as the carbon consultant and 3 of them from Hacıoğlu Village local stakeholders were interviewed. Comments received from the local stakeholders were recorded. Contact information of the authorized person from the owner company is available at village head's office so that the local stakeholders can reach these people whenever they have any complaints, suggestions, or ideas about the project. Any complaints or needs of the local community can be addressed directly to the project proponent.
Stakeholder input	There were no negative comments received from the local stakeholders during the physical site visit. Overall, the local stakeholders expressed strong support for the project. The majority believed that the initiative would enhance the livelihoods of local residents and contribute positively to the local economy, with minimal negative environmental impact. As a result,

most stakeholders viewed the project implementation as advantageous.

4.2.3 Free, Prior, and Informed Consent

Item	Evidence gathering activities, evidence checked, and assessment conclusion
Consent	During the validation period, necessary permits were acquired. Through extensive community engagements with NGOs, Local Communities, and Indigenous Peoples (IPs), the project was able to obtain agreement. The most important factors were widespread participation, open information exchange, and recognition of customary rights. Constant observation and assessment show the dedication to openness and constructive community results. The project's ability to successfully balance stakeholder interests and keep a cordial relationship with the community is demonstrated by the lack of recurring conflicts.
Outcome of FPIC discussion	The project's implementation did not cause encroachment on land, relocation of people without consent, or forced physical or economic displacement. The land was approved for non-agricultural use by the Ministry of Agriculture and Forestry.

4.2.4 Grievance Redress Procedure

Item	Evidence gathering activities, evidence checked, and assessment conclusion
Grievance received and steps taken to resolve the grievance including the outcomes of the resolution	No grievance received during the current monitoring period. During the on-site visit local stakeholders were interviewed and they have no negative inputs regarding the project activity. Moreover, there is a logbook for the grievance mechanism at the Mukhtar. So far, no comments were recorded in the logbook.
Grievance redress procedure	During the current verification, it was communicated by PP and confirmed by assessment team that there is no grievance registered. The project proponent has established the on-going communication mechanism with the stakeholders involved, who can reach them in case of any grievances through:

	Direct communication: Contact information of the authorized person from the owner company is available at village head's office so that the local stakeholders can reach these people whenever they have any complaints, suggestions, or ideas about the project. Any complaints or needs of the local community can be addressed directly to the project proponent. Also, during the on-site visit, local stakeholders were interviewed about the ongoing consultation and grievance mechanism, and it has been confirmed that the locals have knowledge about the same. Moreover, there is a logbook for the grievance mechanism at the Mukhtar. So far, no comments were recorded in the logbook.
--	--

4.2.5 Public Comments

Comments received	Actions taken by the project proponent	Evidence gathering activities, evidence checked, and assessment conclusion
There is no public comments.	N/A	N/A

4.2.6 Risks to Local Stakeholders and the Environment

4.2.6.1 Management Experience

Biokütle Enerji Elektrik Üretim Anonim Şirketi has several landfill plants in Türkiye. Also, a qualified management team with experience of building and running landfill power plants and interacting with local communities is part of the organizational chart.

Moreover, workers have undergone extensive training in environmental management, technical operations, and health and safety regulations. Partnerships with local groups and consultants offer supplementary knowledge where required, and a plan for hiring and training fills in any gaps.

4.2.6.2 Risk Assessment

Item	Evidence gathering activities, evidence checked, and assessment conclusion
Natural and human induced risks to	There has never been an earthquake, flood, or landslide at the project site, making it a low-risk location. To protect workers and stakeholders, it conforms with all applicable national and international safety laws,

stakeholders' wellbeing	including those pertaining to occupational health and safety. Furthermore, there are no hazardous chemicals or procedures used in the project that could present concerns for accidents, pollution, or health issues. To further protect stakeholders, emergency reaction plans and routine monitoring mechanisms have been put in place to handle any unforeseen circumstances. After conducting stakeholder meetings and community engagement initiatives, no safety or wellness issues were found. This assessment leads to the conclusion that there are no substantial hazards to the project's stakeholders' well-being, either from natural or man-made sources. Also, sanitary conditions in the power plant have been thoughtfully designed to comply with health and safety standards. Workers have access to clean water, sufficient bathrooms, and washing stations. Waste management practices have been established to reduce dangers to the environment and human health, and regular maintenance and cleaning schedules are used to uphold hygienic standards. A safe and hygienic working environment has also been ensured by the integration of appropriate drainage and wastewater disposal systems. All these have been confirmed by the VVB during the on-site visit. Therefore, no risk identified.
Risks to stakeholder participation	Work conditions are in line with the scope of Turkey legal regulations and social security records has been provided for all employees. HSE trainings are given to the employees in each year and for the current monitoring period, training records for each year were provided to the VVB.
Working conditions	Turkey is the host country and Turkey as a part of Human Rights Conventions under the UN framework, thus guaranteeing women's rights and safety.
Safety of women and girls	Turkey is the host country and Turkey as a part of Human Rights Conventions under the UN framework, thus guaranteeing minority and marginalized group including children.
Safety of minority and marginalized groups, including children	Waste storage tanks were seen during the on-site visit dated 15 August 2024. Also, hazardous waste disposal records dated as 07/07/2023, 13/10/2023, 30/11/2023, 25/12/2023, 18/04/2024, 30/05/2024 and 11/07/2024 were provided to the VVB.

Pollutants (air, noise, discharges to water, generation and release of hazardous materials and chemical pesticides and fertilizers)	Work conditions are in line with the scope of Turkey legal regulations and social security records has been provided for all employees. HSE trainings are given to the employees in each year and for the current monitoring period, training records for each year were provided to the VVB.
---	---

4.2.7 Respect for Human Rights and Equity

4.2.7.1 Labor and Work

Item	Evidence gathering activities, evidence checked, and assessment conclusion
Discrimination	During the on-site visit, no complaints were received about discrimination and sexual harassment.
Sexual harassment	The Turkish Penal Code (TCK), Articles 122 and 105, criminalizes discrimination and sexual harassment, ensuring equality and protection in workplaces and public spaces. On an international level, Türkiye ratified the ILO Convention No. 111 – Discrimination (Employment and Occupation) in 1966. This convention prohibits discrimination based on gender, race, religion, or other factors in employment.
Gender equity in labor and work	Due to the cultural the background of local people, women in the region are less likely to work in the energy sector. Because of that, there are no female employees in the project activity. In case of female applicant applied, the Project Owner would guarantee equal opportunities with regard to gender equity and labor and work compensation.
Forced labor	Child labor is prohibited. The PP guarantees that no forced labor occurs and that all employment complies with national labor and occupational health and safety regulations, international legal obligations, and the values and norms enshrined in the fundamental conventions of the International Labour Organization (ILO).

	The Turkish Labor Law No. 4857's Articles 71–73 govern the employment of children, establishing a minimum age of 15 and providing safe working conditions for young employees. The ILO Convention No. 138, Minimum Age, established a minimum working age of 15 and was ratified by Türkiye in 1998. The ILO Convention No. 182-Worst Forms of Child Labour, which aims to end dangerous and exploitative child labor, was also approved by Türkiye in 2001. It has been confirmed during the on-site visit that project activity does not use victims of forced labor.
Child labor	Child labor is prohibited. The PP guarantees that no forced labor occurs and that all employment complies with national labor and occupational health and safety regulations, international legal obligations, and the values and norms enshrined in the fundamental conventions of the International Labour Organization (ILO). The Turkish Labor Law No. 4857's Articles 71–73 govern the employment of children, establishing a minimum age of 15 and providing safe working conditions for young employees. The ILO Convention No. 138, Minimum Age, established a minimum working age of 15 and was ratified by Türkiye in 1998. The ILO Convention No. 182-Worst Forms of Child Labour, which aims to end dangerous and exploitative child labor, was also approved by Türkiye in 2001. It has been confirmed during the on-site visit that project activity does not use victims of child labor.
Human trafficking	Child labor, forced labor, or victims of human trafficking are not used in this project. Article 71 of the Turkish Labor Law, which forbids child labor in any form, is followed when conducting recruitment. Turkish Labor Law provides protection for workers.

4.2.7.2 Human Rights

Risks identified	Evidence gathering activities, evidence checked, and assessment conclusion
No risks are identified.	Turkey is dedicated to upholding the values outlined in the United Nations Convention on Human Rights as a signatory to the convention. The project owner respects internationally proclaimed human rights

including dignity, cultural property and uniqueness of indigenous people. The project is not complicit in Human Rights abuses.

4.2.7.3 Indigenous Peoples and Cultural Heritage

Risks identified	Evidence gathering activities, evidence checked, and assessment conclusion
No risks are identified.	There were no houses in the project area, thus the project did not cause any resettlement. This information was confirmed by the local stakeholders during the on-site visit dated 15 August 2024.

4.2.7.4 Property Rights

Risks identified	Evidence gathering activities, evidence checked, and assessment conclusion
No risks are identified.	N/A. The project has all tenure and access rights.

4.2.7.5 Benefit Sharing

Item	Evidence gathering activities, evidence checked, and assessment conclusion
Summary of the benefit sharing plan	The project activity is a private power plant. VER revenues are not subject to benefit sharing.
Benefit sharing during the monitoring period	N/A

4.2.8 Ecosystem Health

Item	Evidence gathering activities, evidence checked, and assessment conclusion
Impacts on biodiversity and ecosystems	The project activity has “EIA Not Required” decision dated 16 June 2021. Therefore, it can be concluded that the project activity does not have any negative impacts on biodiversity and ecosystems.
Soil degradation and soil erosion	N/A

Water consumption and stress	N/A
------------------------------	-----

4.2.8.1 Rare, Threatened, and Endangered species

Item	Evidence gathering activities, evidence checked, and assessment conclusion
Species or habitat	The project activity has “EIA Not Required” decision dated 16 June 2021. Therefore, it can be concluded that the project activity does not have any negative impacts on biodiversity and ecosystems.
Areas needed for habitat connectivity	N/A

	Evidence gathering activities, evidence checked, and assessment conclusion
Habitats for rare, threatened, and endangered species	N/A
Areas for habitat connectivity	N/A

4.2.8.2 Introduction of Species

Species introduced	Evidence gathering activities, evidence checked, and assessment conclusion
N/A	N/A

Existing invasive species	Evidence gathering activities, evidence checked, and assessment conclusion
N/A	N/A

Evidence gathering activities, evidence checked, and assessment conclusion	
Invasive species	N/A

4.2.8.3 Ecosystem conversion

Item	Evidence gathering activities and evidence checked
Ecosystem conversion	N/A (The project is not an “Afforestation, Reforestation and Revegetation” (ARR), “Agricultural Land Management” (ALM), “Wetlands Restoration and Conservation” (WRC) or “Avoided Conversion of Grasslands and Shrublands” (ACoGS) project.)

4.3 Accuracy of Reduction and Removal Calculations

According to the applied methodologies AMS-III.G (v10.0), AMS-I.D (v18.0) and the registered VCS Joint PD-MR, the GHG emission reductions are calculated as follows:

$$ER_y = BE_y - PE_y - LE_y$$

where:

ER_y = Emission reductions in year y (tCO₂/yr)

BE_y = Baseline emissions in year y (tCO₂/yr)

PE_y = Project emission in year y (tCO₂/yr)

LE_y = Leakage emissions in year y (tCO₂/yr)

Baseline Emissions

The baseline emissions in the monitoring period are calculated using the following formula:

$$BE_y = BE_{CH_4,y} + BE_{electricity,y}$$

where:

$BE_{CH_4,y}$ = Baseline emissions of methane from the SWDS in year y (tCO₂/y)

$BE_{electricity,y}$ = Baseline emissions associated with electricity displacement y (tCO₂/y)

As per AMS-III.G (v18.0), the actual emission reduction achieved for Type III component of the project is calculated as follows:

$$ER_{y,calculated} = (1-OX) \times (F_{CH_4,PJ,y} - F_{CH_4,BL,y}) \times GWP_{CH_4} - PE_y - LE_y$$

To calculate $F_{CH_4,PJ,y}$, the following equation is chosen:

$$F_{CH4,PJ,y} = ((EG_y \times 3600) / (NCV_{CH4} \times EE_y)) \times D_{CH4} \times GWP_{CH4}$$

Except EG_y value (it is taken from official EPIAS records), all parameters are determined at the validation of the project activity:

$$NCV_{CH4} = 35.9 \text{ MJ/Nm}^3$$

$$EE_y = 40\%$$

$$D_{CH4} = 0.00067 \text{ tCH}_4 / \text{m}^3 \text{ CH}_4$$

$$GWP_{CH4} = 28 \text{ tCO}_2\text{e} / \text{tCH}_4$$

There is no mandatory regulatory requirement on landfill gas destruction/combustion that has been systematically enforced in Turkey which means there is no contractual requirement on methane destruction that the project owner is bound to. Therefore, $F_{CH4,BL,y}$ is zero.

After the necessary calculations, $ER_{y,calculated}$ is found as 38,873 tCO₂e for the current monitoring period.

For $BE_{electricity,y}$, the following equation is used:

$$BE_{electricity,y} = EG_{PJ,y} \times EF_{grid,y}$$

where:

$EG_{PJ,y}$: Quantity of net electricity supplied to the grid as a result of the implementation of the CDM project activity in year y (MWh)

$EF_{grid,y}$: Combined margin CO₂ emission factor for grid connected power generation in year y calculated by using the latest version of the “Tool to calculate the emission factor for an electricity system” (tCO₂/MWh)

EPIAS records are presented for all months of the monitoring period. All data in emission reductions table are checked with EPIAS records as the main source and crosschecked with OSOS records. The net electricity generated during the current monitoring period was as follows:

Period	Export Electricity to the Grid (MWh)	Import Electricity from the Grid (MWh)	Net Electricity Generation Supplied to the Grid

01/03/2023 – 31/12/2023	4,956.36	213.43	4,742.92
01/01/2024 – 31/08/2024	4,227.50	182.05	4,045.45
Total (01/03/2023 – 31/12/2024)	9,183.85	395.48	8,788.376

Emission factor (0.5552 tCO₂/MWh) available during the validation is also applied in line with the registered VCS Joint PD-MR.

After the necessary calculations, BE_{electricity,y} is found as 4,879 tCO₂e for the current monitoring period.

Hence,

$$BE_y = BE_{CH_4,y} + BE_{electricity,y} = 38,873 \text{ tCO}_2\text{e} + 4,879 \text{ tCO}_2\text{e} = 43,752 \text{ tCO}_2\text{e}$$

Project Emissions

Project emissions are calculated as follows as per AMS-III.G, v10:

$$PE_y = PE_{power,y} + PE_{flare,y} + PE_{process,y}$$

Where:

- PE_y = Project emissions in year y (t CO₂/yr)
- PE_{Power,y} = Emissions from the use of fossil fuel or electricity for the operation of the installed facilities in the year y (t CO₂e)
- PE_{flare,y} = Emissions from flaring or combustion of the landfill gas stream in the year y (t CO₂e)
- PE_{process,y} = Emissions from the landfill gas upgrading process in the year y (t CO₂e), determined by following the relevant procedures described in annex 1 of AMS-III.H.

The power plant meets its required electricity needs from electricity generation at the site. Therefore, PE_{power,y} is zero.

In the project site, there is gas holder to retain extra gas, there is no flare unit. Therefore, $PE_{flare,y}$ is zero.

The project does not involve landfill gas upgrading process. Therefore, $PE_{process,y}$ is zero.

As per the paragraph 39 of AMS-I.D., version 18.0., for most renewable energy project activities, $PE_y = 0$. However, for the following categories of project activities, project emissions have to be considered following the procedure described in ACM0002 v21.0:

- (a) Emissions related to the operation of geothermal power plants (e.g. non condensable gases, electricity/fossil fuel consumption);
- (b) Emissions from water reservoirs of hydro power plants.

As per the paragraph 40 of AMS-I.D., CO_2 emissions from on-site consumption of fossil fuels due to the project activity shall be calculated using the latest version of the “Tool to calculate project or leakage CO_2 emissions from fossil fuel combustion”. Also, the paragraph 41 of AMS-I.D. states that in case biomass is sourced from dedicated plantations, the procedures in the tool “Project emissions from cultivation of biomass” shall be used

Since none of the exception stated in the relevant paragraphs of AMS-I.D. mentioned above is applicable to the proposed project activity, PE_y as per AMS-I.D., version 18.0., shall be accounted as 0.

In conclusion, PE_y for the project activity is 0.

Leakage Emissions

No leakage effects are accounted for under AMS-III.G. (Version 10.0) and AMS-I.D. (Version 18.0).

Therefore, LE_y for the project activity is 0.

Emission Reductions

The emission reduction values of the current monitoring period are as follows:

Period	Emission Reduction Value (tCO _{2e})
01/03/2023 – 31/12/2023	23,612
01/01/2024 – 31/08/2024	20,140
Total (01/03/2023 – 31/08/2024)	43,752

Calculations have been reproduced by VVB and the source data (EPIAS screenshots) are presented by PP.

Bureau Veritas (India) Pvt. Ltd. hereby confirms that the above mentioned electricity generation figures and GHG emission reduction calculations are presented and quantified correctly and are in accordance with the monitoring methodologies AMS-III.G (v10.0) and AMS-I.D (v18.0) and the monitoring plan given in the registered VCS Joint PD-MR.

4.4 Quality of Evidence to Determine Reductions and Removals

The power plant is equipped with two electricity meters, one serving as the main meter and the other as a back-up, to measure the generated electricity. These meters, installed in the power house, adhere to the requirements set by the Energy Market Regulatory Authority (EMRA) for electricity meters. Both meters are designed to measure energy in two directions—consumption and production. If a measuring difference arises between these meters and either TEIAS or the Project Proponent requests calibration, the meters will undergo calibration promptly without waiting for the regular check (i.e. 10 years). The calibration process is conducted by an accredited entity under the supervision of TEIAS, and the PP is not responsible for the calibration of meters in Turkey, following local standards and requirements.

Level of materiality is ensured by application of “Guideline on the Application of Materiality in Verifications” version 02. To guarantee this level of assurance, all data that is used in the GHG emission reduction calculations have been reviewed without any sampling.

Therefore, Bureau Veritas (India) Pvt. Ltd. hereby confirms that the evidence used to determine the GHG emission reductions are sufficient in quantity and appropriate in quality.

4.5 Non-Permanence Risk Analysis

N/A (The project activity is not an AFOLU.)

5 VERIFICATION OPINION

5.1 Verification Summary

Bureau Veritas (India) Pvt. Ltd. has performed the verification activity of “Sinop Landfill Gas to Electricity Project” which is a VCS project with the reference number “4014” for the 2nd verification of the 1st crediting period between 01 March 2023 – 31 August 2024 (both days included). The scope of the activities covers the verification and certification of GHG emissions reductions reported in the VCS MR version 05 dated 05 June 2025.

Gaia Climate Finansal Danışmanlık Hizmetleri ve Ticaret A.Ş. is responsible for the preparation of the GHG emissions data and the reported GHG emissions reductions of the project on the basis set out within the project Monitoring Plan indicated in the final VCS MR, version 05 dated 05 June 2025. The development and maintenance of records and reporting procedures in

accordance with that plan, including the calculation and determination of GHG emission reductions from the project, is the responsibility of the management of the Responsibility Party. The development and maintenance of the records and the related monitoring procedures are in accordance with the VCS MR, version 05 dated 05 June 2025.

Bureau Veritas (India) Pvt. Ltd. concludes that the GHG assertion is free of material misstatement. The emission reductions calculated can be considered in conformance with the:

- The Article 12 of the Kyoto Protocol
- VCS Standard, v4.6
- VCS Program Guide, v4.4
- VCS Validation and Verification Manual, v3.2
- CDM Validation and Verification Standard for Project Activities, v3.3
- AMS-III.G: Landfill methane recovery, v10.0
- AMS-I.D: Grid-connected renewable electricity generation, v18.0
- All associated methodological tools
- Environmental and social issues related to the Sectoral Scope 1: Energy industries (renewable - / non-renewable sources) and Sectoral Scope 13: Waste handling and disposal
- ISO 14064-3:2019 Greenhouse Gases – Part 3: Specification with guidance for the verification validation of greenhouse gas statements

The verification has been performed by a verification team consisting of Öykü YAKUPOĞLU as the Team Leader. The Independent Technical Review was performed by Sanjay PATANKAR and Sameer PENDSE and the project activity was checked against the applicable rules and regulations of VCS Standard, v4.6.

The verification activity can confirm that:

- the project is implemented and operated as per the registered capacity indicated in the VCS Joint PD-MR (version 07 dated 04 June 2024)
- the monitoring complies with the monitoring plan in the registered VCS Joint PD-MR (version 07 dated 04 June 2024)
- the VCS MR (version 05 dated 05 June 2025) and other supporting documents provided are complete and verifiable and in accordance with the applicable VCS requirements
- the installed equipment being essential for generating emission reduction runs reliably and is calibrated appropriately
- the monitoring system is in place and generates GHG emission reductions data
- the emission factor is taken correctly as per the registered VCS Joint PD-MR (v07 dated 04 June 2024)

- the GHG emission reductions are calculated without material misstatements

Bureau Veritas (India) Pvt. Ltd. hereby confirms that the project activity “Sinop Landfill Gas to Electricity Project” in Turkey, is implemented as per the registered capacity indicated in the VCS Joint PD-MR version 07 dated 04 June 2024. The monitoring system is in place and the emission reductions are achieved without material misstatements as per the applied approved methodologies, which are AMS-III.G: Landfill methane recovery, v10.0 and AMS-I.D: Grid-connected renewable electricity generation, v18.0.

5.2 Verification Conclusion

Bureau Veritas (India) Pvt. Ltd. confirms that the level of assurance of this verification report is reasonable, with respect to material errors, omissions and misrepresentations. To guarantee this level of assurance all data that is used in the GHG emission reduction calculations have been reviewed without any sampling.

Verification period: From 01-March-2023 to 31-August-2024

Verified GHG emission reductions and carbon dioxide removals in the above verification period:

Vintage period	Baseline emissions (tCO ₂ e)	Project emissions (tCO ₂ e)	Leakage emissions (tCO ₂ e)	Reduction VCUs (tCO ₂ e)	Removal VCUs (tCO ₂ e)	Total VCUs (tCO ₂ e)
01/March/2023 – 31/December/2023	23,612	0	0		0	23,612
01/January/2024 – 31/August/2024	20,140	0	0		0	20,140
Total	43,752	0	0		0	43,752

5.3 Ex-ante vs Ex-post ERR Comparison

Vintage period	Ex-ante estimated reductions / removals	Achieved reductions/ removals	Percent difference	Explanation for the difference
01/March/2023 – 31/December/2023	27,821	23,612	-17.83%	Ex-ante calculations are higher than ex-post emission reductions. For ex-ante emissions, there are many assumptions to calculate emission reductions, so the
01/January/2024 – 31/August/2024	28,192	20,140	-39.98%	
Total	56,014	43,752	-28.03%	

				difference is acceptable such project. Also, during the ex-ante calculations, it was planned to commission the second gas engine in 2024. However, the second gas engine was not commissioned in 2024.
--	--	--	--	---

Team Leader Signature


Ms. Öykü YAKUPOĞLU



Independent Technical Reviewer's and Technical Expert's Signatures

Mr. Sanjay PATANKAR

Mr. Sameer PENDSE

APPENDIX 1: COMMERCIALY SENSITIVE INFORMATION

<i>Section</i>	<i>Information</i>	<i>Justification</i>	<i>Assessment method and conclusion</i>
N/A	N/A	N/A	N/A

APPENDIX 2: VERIFICATION PROTOCOL

Table 1. Verification requirements based on VCS Standard (v4.6), VCS Program Guide (v4.4), VCS Registration and Issuance Process (v4.4), and VCS MR Template (v4.3)

CHECKLIST QUESTION	Ref.	§	COMMENTS	Draft Concl	Final Concl
Part I Cover Page					
(a) Are all items in the VCS MR in compliance with the rules indicated in “Instructions for completing the monitoring report template” section?	VCS MR Template Version 4.3		a) Please include the upper headers of the VCS MR Template. b) Please include the page numbers.	CAR-1	OK
(b) Is the title of the Project provided?	VCS MR Template Version 4.3		This is available as “Sinop Landfill Gas to Electricity Project”.	OK	OK
(c) Is the Project ID of the Project provided?	VCS MR Template Version 4.3		This is available as “VCS 4014”.	OK	OK
(d) Is the Monitoring Period provided correctly in DD-Month-YYYY format?	VCS MR Template Version 4.3		This is available as “01-March-2023 to 31-August-2024”.	OK	OK
(e) Are the original date of issue and most recent date of issue provided in the VCS MR?	VCS MR Template		Please indicate “Original date of issue” and “Most recent date of issue” on the cover page in every version of the MR.	CAR-2	OK

CHECKLIST QUESTION	Ref.	§	COMMENTS	Draft Concl	Final Concl
	Version 4.3				
(f) Is the version number of the VCS MR provided?	VCS MR Template Version 4.3		This is available as “01” for the first submission.	OK	OK
(g) Is the VCS Standard version provided correctly in the VCS MR?	VCS MR Template Version 4.3		Since VCS MR Template v4.3 is used, please revise the “VCS Standard Version” to “v4.6” on the cover page.	CAR-3	OK
(h) Is it stated who prepared the VCS MR along with contact information?	VCS MR Template Version 4.3		Please indicate the contact information (e.g. address, mail, phone number and so on) of “Gaia Climate Finansal Danışmanlık Hizmetleri ve Ticaret A.Ş.” in “Prepared by” row on the cover page.	CAR-4	OK
(i) Is there “Table of Contents” in the VCS MR?	VCS MR Template Version 4.3		a) Please update the page numbers in “Table of Contents”. b) Please update the sections of “Table of Contents” (e.g. Appendix X is not used in the MR.)	CAR-5	OK
Part II MR					
1. Project Details					
1.1. Summary Description of the Implementation Status of the Project					

CHECKLIST QUESTION	Ref.	§	COMMENTS	Draft Concl	Final Concl
1.1.1 Is a brief description of the project activity provided, including a summary of the scope of activities/ measures that are to be implemented within the project activity?	VCS MR Template Version 4.3		a) Footnote numbers are specified in some parts of the report, but footnotes are not added. Please correct this issue (Also, footnote numbers are not listed in order too.). b) Since this is a verification process, please indicate how many tons of waste have been accepted by the power plant during the current monitoring period, not the estimated waste amount, in Section 1.1. Please also provide the relevant evidence document. c) As per guidance of “VCS MR Template v4.3”, Section 1.1 shall not exceed one page. Therefore, please revise Section 1.1 with keeping the important information of the project (For example, installed technology can be stated in Section 3.1.). d) Since this is a verification process, please remove all future tense sentences throughout the MR. e) During the site visit, it was learned that currently there is only 1 gas engine and the installation of the other gas engine is not considered in the near future. Please add this information to relevant sections of the MR, especially in Section 1.1. f) The electricity generation and emission reduction specified in Section 1.1 are different from the	CAR-6	OK

CHECKLIST QUESTION	Ref.	§	COMMENTS	Draft Concl	Final Concl
			values specified in ER Calculation Excel sheet. Please correct the contradiction. g) Please indicate the Project Owner in Section 1.1. h) Please indicate the commissioning date of the project activity in Section 1.1 (Please also indicate how long the landfill site has been in the area.) i) Please include the monitoring period in Section 1.1. j) Please indicate the purpose of the project activity in Section 1.1. k) Please indicate from which districts of Sinop waste is collected in Section 1.1. l) Please provide the generation license of the project activity.		
1.1.2 Does it explain how the project activity reduces GHG emissions or increase GHG removals?	VCS MR Template Version 4.3		It is explained how the project activity reduces GHG emissions in Section 1.1.	OK	OK
1.1.3 Is the achieved of total GHG emission reductions for the chosen monitoring period provided?	VCS MR Template Version 4.3		Please refer to CAR-6.	CAR-6	OK
1.1.4 Is the purpose of the Project Activity provided?	VCS MR Template		Please refer to CAR-6.	CAR-6	OK

CHECKLIST QUESTION	Ref.	§	COMMENTS	Draft Concl	Final Concl
	Version 4.3				
1.1.5 Is the installed technology of the Project Activity briefly explained?	VCS MR Template Version 4.3		Please refer to CAR-6.	CAR-6	OK
1.1.6 Are the milestones of the Project Activity included?	VCS MR Template Version 4.3		This is available in Section 3.1.	OK	OK
1.1.7 If the proposed VCS project activity involves the alteration of an existing installation or process, does the project description state the differences resulting from the project activity compared to the pre-project situation?	VCS MR Template Version 4.3		N/A	OK	OK
1.2 Audit History					
1.2.1 Is Audit History provided correctly in the VCS MR?	VCS MR Template Version 4.3		Audit History is provided correctly in Section 1.2.	OK	OK
1.3 Sectoral Scope and Project Type					
1.3.1 Is the sectoral scope applicable to the project indicated?	VCS MR Template Version 4.3		Sectoral scopes (1 and 13) are indicated correctly in Section 1.3.	OK	OK

CHECKLIST QUESTION	Ref.	§	COMMENTS	Draft Concl	Final Concl
1.3.2 Is the project activity type applicable to the project indicated?	VCS MR Template Version 4.3		Project types are indicated correctly in Section 1.3.	OK	OK
1.3.3 If the project activity is an AFOLU, is AFOLU project category indicated?	VCS MR Template Version 4.3		N/A	OK	OK
1.4 Project Proponent					
1.4.1 Are the contact information of the project proponent provided in the tabular format?	VCS MR Template Version 4.3		Please remove the instruction part from Section 1.4.	CAR-7	OK
1.5 Other Entities Involved in the Project					
1.5.1 Are the contact information and roles/responsibilities of any other entities involved in the development of the project provided?	VCS MR Template Version 4.3		The contact information of other entities is available in Section 1.5.	OK	OK
1.6 Project Start Date					
1.6.1 Are the project start date and its justification provided correctly with considering the date on which the project began reducing or removing GHG emissions?	VCS MR Template Version 4.3		The project start date and its justification are indicated in Section 1.6.	OK	OK

CHECKLIST QUESTION	Ref.	§	COMMENTS	Draft Concl	Final Concl
1.7 Project Crediting Period					
1.7.1 Are the total crediting period including the start and end dates (in DD-Month-YYYY format) and renewable period type indicated correctly?	VCS MR Template Version 4.3		The first crediting period is from 01-July-2021 to 30-June-2028.	OK	OK
1.8 Project Location					
1.8.1 Is the host party indicated?	VCS MR Template Version 4.3		Turkey	OK	OK
1.8.2 Is region/state/province etc. indicated?	VCS MR Template Version 4.3		Sinop Province	OK	OK
1.8.3 Is City/Town/Community indicated?	VCS MR Template Version 4.3		Merkez District	OK	OK
1.8.4 Are the project coordinates of the project activity and the relevant KML file provided?	VCS MR Template Version 4.3		The project coordinates are included in Section 1.8.	OK	OK
1.9 Title and Reference of Methodology					

CHECKLIST QUESTION	Ref.	§	COMMENTS	Draft Concl	Final Concl
1.9.1 Is the title of the applied methodology provided correctly?	VCS MR Template Version 4.3		Titles of the applied methodologies are indicated correctly in Section 1.9.	OK	OK
1.9.2 Is the reference ID of the applied methodology provided correctly?	VCS MR Template Version 4.3		Reference IDs of the applied methodologies are indicated correctly in Section 1.9.	OK	OK
1.9.3 Is the version of the applied methodology provided correctly?	VCS MR Template Version 4.3		The version numbers of the applied methodologies are indicated correctly in Section 1.9.	OK	OK
1.9.4 Are the titles of the applied tools provided correctly?	VCS MR Template Version 4.3		Titles of the applied tools are indicated correctly in Section 1.9.	OK	OK
1.9.5 Are the reference IDs of the applied tools provided correctly?	VCS MR Template Version 4.3		Reference IDs of the applied tools are indicated correctly in Section 1.9.	OK	OK
1.9.6 Are the versions of the applied tools provided correctly?	VCS MR Template Version 4.3		The version numbers of the applied tools are indicated correctly in Section 1.9.	OK	OK

CHECKLIST QUESTION	Ref.	§	COMMENTS	Draft Concl	Final Concl
1.9.7 If any modules are used, are the titles, reference IDs and versions provided correctly?	VCS MR Template Version 4.3		N/A	OK	OK
1.10 Double Counting and Participation under Other GHG Programs					
1.10.1 Is it indicated whether the project has been registered or seeking registration under any other GHG programs? If yes, are the evidence of no double issuance, registration number and all other relevant details provided?	VCS MR Template Version 4.3		Please provide the signed and sealed letter on company letterhead that the project has not been registered, or has not been seeking registration under any other GHG programs.	CL-1	OK
1.11 Double Claiming, Other Forms of Credit, and Scope 3 Emissions					
1.11.1 Does the project reduce GHG emissions from activities that are included in an emissions trading program; or any other mechanism that includes GHG allowance trading? If yes, is the evidence of no double claiming provided?	VCS MR Template Version 4.3		Please provide the signed and sealed letter on company letterhead that project has not been included in an emissions trading program; or any other mechanism that includes GHG allowance trading.	CL-2	OK
1.11.2 Is the project created other forms of environmental credit? If yes, is the evidence of no double claiming provided?	VCS MR Template Version 4.3		N/A	OK	OK
1.11.3 Does the project activity affect the emissions footprint of any product(s) (goods or services) that are part of a supply chain? If yes, are the details	VCS MR Template		N/A	OK	OK

CHECKLIST QUESTION	Ref.	§	COMMENTS	Draft Concl	Final Concl
about this satiation stated correctly with providing the relevant evidence documents?	Version 4.3				
1.12 Sustainable Development Contributions					
1.12.1 Does the brief description related to the SDG contributions exceed the 100-word limit?	VCS MR Template Version 4.3		a) Please indicate the achieved emission reduction of the current monitoring period in Section 1.12 (on page 14). b) Please correct “Net impact on SDG indicator” of “SDG 8.8” in Section 1.12. c) Please revise the current number of employees (i.e. 12 employees) throughout the MR. d) Please complete “Current project contributions” and “Contributions over project lifetime” columns of “SDG 7.2” and “SDG 13.0” in Section 1.12.	CAR-8	OK
1.12.2 Is a summary description of project activities implemented during the monitoring period that result in SDG contributions (i.e., technologies/measures implemented, activity location) provided?	VCS MR Template Version 4.3		Please refer to CAR-8.	CAR-8	OK
1.12.3 Is an explanation of how project activities result in the SDG contributions described in Table 1 of MR provided?	VCS MR Template Version 4.3		Please refer to CAR-8.	CAR-8	OK
1.12.4 Is it identified of which SDG contributions described in Table 1 of MR contributes to achieving any nationally stated sustainable	VCS MR Template		Please refer to CAR-8.	CAR-8	OK

CHECKLIST QUESTION	Ref.	§	COMMENTS	Draft Concl	Final Concl
development priorities, including any provisions for monitoring and reporting same?	Version 4.3				
1.12.5 Are the evidences of the project's SDG contributions provided as appendices to the VCS MR?	VCS MR Template Version 4.3		Please refer to CAR-8.	CAR-8	OK
1.12.6 Are the activities implemented during previous monitoring periods described in the VCS MR? If no activities were implemented, is this situation also stated?	VCS MR Template Version 4.3		Please refer to CAR-8.	CAR-8	OK
1.12.7 Are the project's quantifiable contributions to specific targets and indicators of the SDGs for the monitoring period provided using Table 1?	VCS MR Template Version 4.3		Please refer to CAR-8.	CAR-8	OK
1.12.8 Is the official list of SDG Targets and Indicators used to identify the SDG Targets to which the project has contributed? Moreover, are the relevant evidences for each contribution identified?	VCS MR Template Version 4.3		Please refer to CAR-8.	CAR-8	OK
1.12.9 Are indicated contributions aligned with the SDGs? (For climate change mitigation impacts, is "13.0" written in the SDG target column of Table 1 and is the indicator "Tonnes of greenhouse gas emissions avoided or removed" used?)	VCS MR Template Version 4.3		Please refer to CAR-8.	CAR-8	OK
1.12.10 Are total project contributions since the project start date, previous SDG contribution monitoring period, or VCS monitoring period in the "Current Project Contributions" column and the	VCS MR Template		Please refer to CAR-8.	CAR-8	OK

CHECKLIST QUESTION	Ref.	§	COMMENTS	Draft Concl	Final Concl
cumulative contributions over the project lifetime documented in the “Contributions Over the Project Lifetime” column in Table 1 of the VCS MR?	Version 4.3				
1.13 Commercially Sensitive Information					
1.13.1 If there are any commercially sensitive information which has been excluded from the public version of the monitoring report using Appendix 1, are the relevant items indicated and briefly described?	VCS MR Template Version 4.3		N/A	OK	OK
1.13.2 If there are any commercially sensitive information, are the relevant justification provided for why the information is commercially sensitive?	VCS MR Template Version 4.3		N/A	OK	OK
2. Safeguards and Stakeholder Engagement					
2.1. Stakeholder Engagement and Consultation					
2.1.1. Where the stakeholder make up has changed since validation, or stakeholders were not identified at verification, is the table indicated in Section 2.1.1 used properly?	VCS MR Template Version 4.3		The table indicated in Section 2.1.1 is used properly.	OK	OK
2.1.2. Are the process for, and the outcomes from, ongoing communication with stakeholders conducted prior to verification described properly with using the table indicated in Section 2.1.2?	VCS MR Template Version 4.3		The table indicated in Section 2.1.2 is used properly.	OK	OK

CHECKLIST QUESTION	Ref.	§	COMMENTS	Draft Concl	Final Concl
2.1.3. Is “Free, Prior, and Informed Consent (FPIC)”, which took place as part of the stakeholder consultation, indicated with using the table in Section 2.1.3?	VCS MR Template Version 4.3		The table indicated in Section 2.1.3 is used properly.	OK	OK
2.1.4. Is the Grievance Procedure of the Project Activity indicated in Section 2.1.4 and if any grievances were raised during the monitoring period, are the steps which were taken by the project proponent indicated?	VCS MR Template Version 4.3		The table indicated in Section 2.1.4 is used properly.	OK	OK
2.1.5. Is the Public Comment period specified and whether any comments were received during this period?	VCS MR Template Version 4.3		Public Comment period is relevant to VCS. Therefore, please revise Section 2.1.5 of the MR.	CAR-9	OK
2.2. Risks to Stakeholders and the Environment					
2.2.1. Are there any risks identified at validation? If yes, are these risks indicated in the VCS MR and are the mitigation or preventative measures to address the identified risk during the monitoring period stated?	VCS MR Template Version 4.3		Please remove the instruction part from Section 2.2.	CAR-10	OK
2.3. Respect for Human Rights and Equity					
2.3.1. Are the project’s respect for rights related to work and labor during the monitoring period demonstrated with using the tabular format in Section 2.3.1?	VCS MR Template Version 4.3		The table indicated in Section 2.3.1 is used properly.	OK	OK

CHECKLIST QUESTION	Ref.	§	COMMENTS	Draft Concl	Final Concl
2.3.2. Is it demonstrated how the project continues to recognize, respect, and promote the protection of the rights of IPs, LCs, and customary rights holders in line with applicable international human rights law, and the United Nations Declaration on the Rights of Indigenous Peoples and ILO Convention 169 on Indigenous and Tribal Peoples in Section 2.3.2?	VCS MR Template Version 4.3		The project activity follows all relevant national laws and legislations that are based on international laws.	OK	OK
2.3.3. Is it demonstrated that the project continues to preserve and protect cultural heritage as part of project activities in Section 2.3.3?	VCS MR Template Version 4.3		The project will encourage employees to preserve and protect cultural heritage as part of project activities.	OK	OK
2.3.4. Is it demonstrated that the property rights of IPs, LCs and customary rights holders are respected during the monitoring period with using the tabular format in Section 2.3.4?	VCS MR Template Version 4.3		N/A	OK	OK
2.3.5. Where the project impacts property rights, is the benefit sharing that occurred during the monitoring period, in accordance with the validated agreement described with using the tabular format in Section 2.3.5?	VCS MR Template Version 4.3		N/A	OK	OK
2.4. Risks to Stakeholders and the Environment					
2.4.1. If there are any risks to the environment identified at validation, are these risks identified and are the steps taken to mitigate them during the monitoring period stated with using the tabular format in Section 2.4?	VCS MR Template Version 4.3		The table indicated in Section 2.4 is used properly.	OK	OK

CHECKLIST QUESTION	Ref.	§	COMMENTS	Draft Concl	Final Concl
2.4.2. If the project located in, or adjacent to habitats for rare, threatened, or endangered species, are these species listed and are the evidences provided to demonstrate that the project has not adversely impacted these areas during the monitoring period with using tabular format in Section 2.4.1?	VCS MR Template Version 4.3		N/A	OK	OK
2.4.3. For projects with planting or species introduction, is it demonstrated that adverse effects from the introduction of species identified at validation are being mitigated with using the tabular format in Section 2.4.2?	VCS MR Template Version 4.3		N/A	OK	OK
2.4.4. Where invasive species exist in the project area, are these species listed and is it demonstrated that the project activity will not allow the species to thrive with using the tabular format in Section 2.4.2?	VCS MR Template Version 4.3		N/A	OK	OK
2.4.5. For ARR, ALM, WRC or ACoGS projects, is the relevant evidence provided to demonstrate that the project area was not cleared of existing ecosystems, unless such clearing took place at least 10 years prior, or the dominant land cover was invasive?	VCS MR Template Version 4.3		N/A	OK	OK
3. Implementation Status					
3.1. Implementation Status of the Project Activity					
3.1.1 Is a description of the implementation and operational status of the project including any information on events that may impact the GHG emission reductions or carbon dioxide	VCS MR Template Version 4.3		In Table 6 in Section 3.1, "Sinop Landfill Provisional Acceptance" date is stated as "29 June 2021". However, the project start date is indicated as "01 July 2021".	CL-3	OK

CHECKLIST QUESTION	Ref.	§	COMMENTS	Draft Concl	Final Concl
removals and monitoring provided in section 3.1 of the VCS MR?			Please state the reason for this situation in Section 3.1.		
3.1.2 If there are any other changes (e.g., to project proponent or other entities) during the monitoring period, are these changes indicated in Section 3.1 of the VCS MR?	VCS MR Template Version 4.3		The changes are indicated in Section 3.2.2.	OK	OK
3.1.3 For AFOLU projects, where no new project activities have been implemented during the current monitoring period, is it demonstrated that previously implemented project activities continued to be implemented during the current monitoring period?	VCS MR Template Version 4.3		N/A	OK	OK
3.1.4 For AFOLU projects, is any loss of carbon stock that occurred during the monitoring period and the relevant details (date of the loss(es), date of discovery(s), size and extent of the loss) reported?	VCS MR Template Version 4.3		N/A	OK	OK
3.2. Deviations					
3.2.1 Are there any deviations from the methodology?	VCS MR Template Version 4.3		N/A	OK	OK
3.2.2 If there are any deviations from the methodology, are these deviations described and justified properly?	VCS MR Template Version 4.3		N/A	OK	OK

CHECKLIST QUESTION	Ref.	§	COMMENTS	Draft Concl	Final Concl
3.2.3 Are there any deviations from the registered project description?	VCS MR Template Version 4.3		Since the project carbon consultancy has changed, please indicate this in Section 3.2.2. Please also note in this section that the gas engine planned for 2024 has been postponed to a later date.	CAR-11	OK
3.2.4 If there are any deviations from the registered project description, are these deviations described and justified properly?	VCS MR Template Version 4.3		Please refer to CAR-11.	CAR-11	OK
3.2.5 Is the outcome of the deviation from the project description provided?	VCS MR Template Version 4.3		Please refer to CAR-11.	CAR-11	OK
3.2.6 If any project description deviations applied in previous monitoring reports, are these deviations reported?	VCS MR Template Version 4.3		N/A	OK	OK
3.3. Grouped Projects					
3.3.1 Is the project activity is a grouped project?	VCS MR Template Version 4.3		The project activity is not a grouped project.	OK	OK
3.3.2 If the project activity is a grouped project, is the relevant information about new instances of the project activity provided?	VCS MR Template		N/A	OK	OK

CHECKLIST QUESTION	Ref.	§	COMMENTS	Draft Concl	Final Concl
	Version 4.3				
3.3.3 If the project activity is a grouped project, is it demonstrated that each new instance of the project activity meets the eligibility criteria set out in the project description?	VCS MR Template Version 4.3		N/A	OK	OK
3.4. Baseline Reassessment					
3.4.1 Did the project undergo baseline reassessment during the monitoring period?	VCS MR Template Version 4.3		N/A	OK	OK
3.4.2 If yes, is a summary of the baseline reassessment applied during the monitoring period provided including the following: - Details of the use and applicability of the latest approved version of the methodology or its replacement, where relevant. - Sections in the project description that have been updated to reflect changes in the new baseline. - Indicate whether the baseline scenario is still valid. If the previous baseline scenario is no longer valid, summarize the new baseline scenario as described in the updated project description. - Describe the impact of new relevant national and/or sectoral policies and	VCS MR Template Version 4.3		N/A	OK	OK

CHECKLIST QUESTION	Ref.	§	COMMENTS	Draft Concl	Final Concl
circumstances on the validity of the baseline scenario, where relevant. - Include the percentage change between the revised baseline emissions provided in the updated project description and the previous baseline emissions.					
4 Data and Parameters					
4.1 Data and Parameters Available at Validation					
4.1.1 Are all the data that is determined only once for the crediting period but are used after registration of the project, listed in Section 4.1?	VCS MR Template Version 4.3		Please use the emission factor value which is indicated in the registered VCS Joint PD-MR throughout the MR and in the ER Calculation Excel Sheet.	CAR-12	OK
4.1.2 Does the listed data include all the parameters used to calculate baseline, project and leakage emissions as well as other relevant parameters required by the approved methodology and the monitoring plan?	VCS MR Template Version 4.3		All ex-ante parameters are included in Section 4.1.	OK	OK
4.1.3 For each data is the name of data/parameters given in accordance with the approved PD and the applied approved methodology?	VCS MR Template Version 4.3		Name of each data is indicated correctly in Section 4.1.	OK	OK
4.1.4 For each data is the unit of the data/parameters given in accordance with the approved PD and the applied approved methodology?	VCS MR Template Version 4.3		Unit of each data is indicated correctly in Section 4.1.	OK	OK

CHECKLIST QUESTION	Ref.	§	COMMENTS	Draft Concl	Final Concl
4.1.5 For each data is the description of the data/parameters given in accordance with the approved PD and the applied approved methodology?	VCS MR Template Version 4.3		Description of each data is indicated correctly in Section 4.1.	OK	OK
4.1.6 For each data is the source of the data/parameters given in accordance with the approved PD and the applied approved methodology?	VCS MR Template Version 4.3		Please refer to CAR-12.	CAR-12	OK
4.1.7 For each data are the values applied of the data/parameters given in accordance with the approved PD and the applied approved methodology?	VCS MR Template Version 4.3		Please refer to CAR-12.	CAR-12	OK
4.1.8 For each data is it justified the choice of data or description of measurement methods and procedures applied?	VCS MR Template Version 4.3		Choice of each data is indicated correctly in Section 4.1.	OK	OK
4.1.9 For each data is it indicated what the data/parameters are used for (baseline/project/leakage emission calculations)?	VCS MR Template Version 4.3		Purpose of each data is indicated correctly in Section 4.1.	OK	OK
4.2 Data and Parameters Monitored					
4.2.1 Are all the data that are monitored listed under section 4.2 of the VCS MR?	VCS MR Template		a) Please complete Section 4.2 using the information in the registered VCS Joint PD-MR (e.g. source of	CAR-13	OK

CHECKLIST QUESTION	Ref.	§	COMMENTS	Draft Concl	Final Concl
	Version 4.3		data, description of data and so on). b) The serial number of the main meter in the electricity meters seen during the site visit was different from the serial number stated in Section 4.2 of the MR. Moreover, again during the site visit, it was learned that the electricity meters were changed in 2021. Please add this information to Section 4.2 and provide the relevant meter change document. c) Please indicate the calibration frequency of the electricity meters in Section 4.2. d) Please indicate the cross-checked method for the electricity generation in Section 4.2. e) Please include all ex-post parameters specified in the registered VCS PD-MR in Section 4.2 (i.e. EG_y). f) Please provide the hazardous waste and waste water disposal records covering the current monitoring period. g) Please provide the HSE training records covering the current monitoring period.		
4.2.2 For each data is the name of data/parameters given in accordance with the approved PD and the applied approved methodology?	VCS MR Template		Please refer to CAR-13.	CAR-13	OK

CHECKLIST QUESTION	Ref.	§	COMMENTS	Draft Concl	Final Concl
	Version 4.3				
4.2.3 For each data is the unit of the data/parameters given in accordance with the approved PD and the applied approved methodology?	VCS MR Template Version 4.3		Please refer to CAR-13.	CAR-13	OK
4.2.4 For each data is the description of the data/parameters given in accordance with the approved PD and the applied approved methodology?	VCS MR Template Version 4.3		Please refer to CAR-13.	CAR-13	OK
4.2.5 For each data is the source of the data/parameters given in accordance with the approved PD and the applied approved methodology?	VCS MR Template Version 4.3		Please refer to CAR-13.	CAR-13	OK
4.2.6 For each data, are the description of measurement methods and procedures to be applied indicated?	VCS MR Template Version 4.3		Please refer to CAR-13.	CAR-13	OK
4.2.7 For each data is the measurement and recording frequency indicated?	VCS MR Template Version 4.3		Please refer to CAR-13.	CAR-13	OK
4.2.8 Is the calibration frequency for measuring equipment specified in the monitoring methodology or in the monitoring plan?	VCS MR Template		Please refer to CAR-13.	CAR-13	OK

CHECKLIST QUESTION	Ref.	§	COMMENTS	Draft Concl	Final Concl
	Version 4.3				
4.2.9 For each data are the values applied of the data/parameters given in accordance with the approved PD and the applied approved methodology?	VCS MR Template Version 4.3		Please refer to CAR-13.	CAR-13	OK
4.2.10 For each data has it been indicated what types of equipment are used to monitor each parameter?	VCS MR Template Version 4.3		Please refer to CAR-13.	CAR-13	OK
4.2.11 For each data are the QA/QC procedures applied of the data/parameters given in accordance with the approved PD and the applied approved methodology?	VCS MR Template Version 4.3		Please refer to CAR-13.	CAR-13	OK
4.2.12 For each data is it indicated what the data/parameters are used for (baseline/project/leakage emission calculations)?	VCS MR Template Version 4.3		Please refer to CAR-13.	CAR-13	OK
4.2.13 For each data, is the relevant calculation method indicated, if any?	VCS MR Template Version 4.3		Please refer to CAR-13.	CAR-13	OK
4.2.14 Does the listed data include all parameters used to calculate baseline, project and leakage emissions as well as other relevant parameters required by the approved	VCS MR Template		Please refer to CAR-13.	CAR-13	OK

CHECKLIST QUESTION	Ref.	§	COMMENTS	Draft Concl	Final Concl
methodology and, where applicable, the applied standardized baseline and the monitoring plan?	Version 4.3				
4.3 Monitoring Plan					
4.3.1 Is a description of the monitoring plan provided in Section 4.3 and does it comply with the registered PD?	VCS MR Template Version 4.3		a) Please include the statement “All data collected as part of monitoring is being archived electronically by the Project Proponent and be kept at least for 2 years after the end of the last crediting period.” in Section 4.3. b) Please include the organizational chart in Section 4.3. c) Please explain leakage management in Section 4.3 with providing the relevant evidence document (i.e. signed contract between the PO and Gerze Municipality).	CL-4	OK
4.3.2 Are the information flow including data aggregation, data recording, data calculation, and data reporting provided in Section 4.3?	VCS MR Template Version 4.3		The information flow including data aggregation, data recording, data calculation, and data reporting are indicated in Section 4.3.	OK	OK
4.3.3 Are the organizational structure and the roles and responsibilities of the employees provided in Section 4.3?	VCS MR Template Version 4.3		Please refer to CL-4.	CL-4	OK
4.3.4 Are the QA/QC procedures included in Section 4.3?	VCS MR Template		QA/QC procedures are included in Section 4.3.	OK	OK

CHECKLIST QUESTION	Ref.	§	COMMENTS	Draft Concl	Final Concl
	Version 4.3				
4.3.5 Are all parameters indicated in the monitoring plan sufficiently monitored?	VCS MR Template Version 4.3		All parameters indicated in the monitoring plan are sufficiently monitored.	OK	OK
4.3.6 Are monitored data properly recorded and stored?	VCS MR Template Version 4.3		Monitored data are properly recorded and stored.	OK	OK
5 Quantification of GHG Emission Reductions and Removals					
5.1 Baseline Emissions					
5.1.1 Are all necessary equations used to calculate the baseline emissions provided in Section 5.1?	VCS MR Template Version 4.3		a) Please include definitions of the symbols ($BE_y = BE_{CH4,y} + BE_{electricity}$) in the formulas in Section 5.1. b) Please correct the formula $BE_{y,electricity} = EGP_{J,y} + EF_{grid,y}$ in Section 5.1. c) Please correct OM, BM and CM values in Section 5.1. d) Please provide all EPIAS records and OSOS records covering the monitoring period.	CAR-14	OK

CHECKLIST QUESTION	Ref.	§	COMMENTS	Draft Concl	Final Concl
5.1.2 Are sample calculations for the equations provided in Section 5.1?	VCS MR Template Version 4.3		Please refer to CAR-14.	CAR-14	OK
5.1.3 Are all necessary electronic spreadsheets provided properly?	VCS MR Template Version 4.3		Please refer to CAR-14.	CAR-14	OK
5.2 Project Emissions					
5.2.1 Are all necessary equations used to calculate the project emissions provided in Section 5.2?	VCS MR Template Version 4.3		The project emissions are taken as zero.	OK	OK
5.2.2 Are sample calculations for the equations provided in Section 5.2?	VCS MR Template Version 4.3		The project emissions are taken as zero.	OK	OK
5.2.3 Are all necessary electronic spreadsheets provided properly?	VCS MR Template Version 4.3		The project emissions are taken as zero.	OK	OK
5.3 Leakage Emissions					

CHECKLIST QUESTION	Ref.	§	COMMENTS	Draft Concl	Final Concl
5.3.1 Are all necessary equations used to calculate the leakage emissions provided in Section 5.3?	VCS MR Template Version 4.3		The leakage emissions are taken as zero.	OK	OK
5.3.2 Are sample calculations for the equations provided in Section 5.3?	VCS MR Template Version 4.3		The leakage emissions are taken as zero.	OK	OK
5.3.3 Are all necessary electronic spreadsheets provided properly?	VCS MR Template Version 4.3		The leakage emissions are taken as zero.	OK	OK
5.4 GHG Emission Reductions and Carbon Dioxide Removals					
5.4.1 Are the GHG emission reductions and carbon dioxide removals for the monitoring period calculated and demonstrated correctly in Section 5.4?	VCS MR Template Version 4.3		Please refer to CAR-14.	CAR-14	OK
5.4.2 Is the relevant vintage period tables in Section 5.4 filled in correctly?	VCS MR Template Version 4.3		Please refer to CAR-14.	CAR-14	OK
5.4.3 Are the percentage difference and any difference between ex-ante GHG emission reductions and ex-post GHG emission reductions stated in Section 5.4?	VCS MR Template		Please refer to CAR-14.	CAR-14	OK

CHECKLIST QUESTION	Ref.	§	COMMENTS	Draft Concl	Final Concl
	Version 4.3				
6 Appendixes					
6.1.1 If there are any commercially sensitive information, is the relevant information stated and justified clearly in Appendix 1?	VCS MR Template Version 4.3		N/A	OK	OK
6.1.2 If another appendix is added, is the information provided correctly stated?	VCS MR Template Version 4.3		N/A	OK	OK

Table 2 – Resolution of Corrective Action Requests (CARs), Clarification Requests (CLs) and Forward Action Requests (FARs)

Draft report CARs, CLs and FARs by verification team	Reference checklist question to in Periodic Verification Checklist	Summary of project owner response	Verification team conclusion
CAR-1 a) Please include the upper headers of the VCS MR Template. b) Please include the page numbers.	(a)	a) Revised. b) Page numbers are added to PDD. Response-1; a) Revised.	Review-1: a) Between pages 3-9, the upper header is to be applied. b) Ok Closed (Page numbers were included.) Review-2: a) Ok Closed (The MR template was revised.)
CAR-2	(e)	Date information are added to the PDD.	Review-1:

Draft report CARs, CLs and FARs by verification team	Reference checklist question Periodic Verification Checklist	to in	Summary of project owner response	Verification team conclusion
Please indicate “Original date of issue” and “Most recent date of issue” on the cover page in every version of the MR.				Ok Closed (The dates were included on the cover page.)
CAR-3 Since VCS MR Template v4.3 is used, please revise the “VCS Standard Version” to “v4.6” on the cover page.	(g)		It is updated as v4.6 in the cover page.	Review-1: Ok Closed (VCS standard was revised accordingly.)
CAR-4 Please indicate the contact information (e.g. address, mail, phone number and so on) of “Gaia Climate Finansal Danışmanlık Hizmetleri ve Ticaret A.Ş.” in “Prepared by” row on the cover page.	(h)		The relevant information is added to the cover page.	Review-1: Ok Closed (Contact information was included on the cover page.)
CAR-5 a) Please update the page numbers in “Table of Contents”. b) Please update the sections of “Table of Contents” (e.g. Appendix X is not used in the MR.)	(i)		a) Revised. b) It is updated accordingly. Revised.	Review-1: a) Ok Closed (Page numbers were updated accordingly.) b) The Table of Contents is out of order (page 2). Please revise it as per the VCS MR Template. Review-2: b) Ok Closed (The MR template was revised.)
CAR-6	1.1.1		a) Revised	Review-1:

Draft report CARs, CLs and FARs by verification team	Reference checklist question Periodic Verification Checklist	to in	Summary of project owner response	Verification team conclusion
a) Footnote numbers are specified in some parts of the report, but footnotes are not added. Please correct this issue (Also, footnote numbers are not listed in order too.). b) Since this is a verification process, please indicate how many tons of waste have been accepted by the power plant during the current monitoring period, not the estimated waste amount, in Section 1.1. Please also provide the relevant evidence document. c) As per guidance of “VCS MR Template v4.3”, Section 1.1 shall not exceed one page. Therefore, please revise Section 1.1 with keeping the important information of the project (For example, installed technology can be stated in Section 3.1.). d) Since this is a verification process, please remove all future tense sentences throughout the MR. e) During the site visit, it was learned that currently there is only 1 gas engine and the installation of the other gas engine is not considered in the near future. Please add this information to relevant sections of the MR, especially in Section 1.1. f) The electricity generation and emission reduction specified in Section 1.1 are different from the			b) Total waste amount is mentioned in section 1.1 of the PDD. Weighbridge records and example of weighbridge documents are provided. Kindly see the supportive documents file. c) Section 1.1 is updated accordingly. Information of installed technology is transferred to section 3.1 of the PDD. d)TBC e) The relevant information is added to the section 1.1 of the PDD. f) It is fixed. It is fixed. g) Project owner is Biokütle Enerji Elektrik Üretim A.Ş and mentioned in updated section 1.1 of the PDD. h) Commissioning date is mentioned in section 1.1 of the PDD. The landfill site has been in this area since 2012.This information is added to the PDD. i) The relevant information is added to the section 1.1 of the PDD.	a) Ok Closed (The order of footnotes was corrected.) b) Ok Closed (Total amount of waste was included in Section 1.1 and the relevant evidence document was provided.) c) Ok Closed (Section 1.1 was revised accordingly.) d) Since this is a verification process, please remove all future tense sentences throughout the MR. e) Ok Closed (The relevant information was included in Section 1.1.) f) The net electricity generation is 8,788 MWh as per the Excel sheet. However, it is indicated as 9,183.85 MWh in Section 1.1. Please correct the contradiction (Also, the net value shall be indicated throughout the MR.). g) Ok Closed (The Project Owner was included in Section 1.1.)

Draft report CARs, CLs and FARs by verification team	Reference checklist question Periodic Verification Checklist	to in	Summary of project owner response	Verification team conclusion
values specified in ER Calculation Excel sheet. Please correct the contradiction. g) Please indicate the Project Owner in Section 1.1. h) Please indicate the commissioning date of the project activity in Section 1.1 (Please also indicate how long the landfill site has been in the area.) i) Please include the monitoring period in Section 1.1. j) Please indicate the purpose of the project activity in Section 1.1. k) Please indicate from which districts of Sinop waste is collected in Section 1.1. l) Please provide the generation license of the project activity.			j) The relevant information is added to the section 1.1 of the PDD. k) The name of districts are added to the section 1.1 of the PDD. l) The relevant information is added to the section 1.1 of the PDD. Kindly see the supportive document file.	h) Ok Closed (The commissioning date was included in Section 1.1.) i) Ok Closed (The monitoring period was included in Section 1.1.) j) Ok Closed (The purpose of the project activity was included in Section 1.1.) k) Ok Closed (The districts were included in Section 1.1.) l) Please provide the generation license of the project activity. Review-2: d) Ok Closed (All future tense sentences were removed from the MR.) f) Ok Closed (The electricity generation value was revised throughout the MR.) l) Ok Closed (Generation license was provided.)
CAR-7 Please remove the instruction part from Section 1.4.	1.4.1		It is fixed.	Review-1:

Draft report CARs, CLs and FARs by verification team	Reference checklist question Periodic Verification Checklist	to in	Summary of project owner response	Verification team conclusion
				Ok Closed (Section 1.4 was revised accordingly.)
CAR-8 a) Please indicate the achieved emission reduction of the current monitoring period in Section 1.12 (on page 14). b) Please correct “Net impact on SDG indicator” of “SDG 8.8” in Section 1.12. c) Please revise the current number of employees (i.e. 12 employees) throughout the MR. d) Please complete “Current project contributions” and “Contributions over project lifetime” columns of “SDG 7.2” and “SDG 13.0” in Section 1.12.	1.12.1	a) The relevant details are added to the section 1.12 of the PDD. b) Revised. c) Updated. d) Completed. Contributions over project lifetime is updated accordingly. The net electricity generation value is used for current project contributions.	Review-1: a) Ok Closed (The achieved emission reduction value was included in Section 1.12.) b) Ok Closed (Section 1.12 was revised accordingly.) c) Ok Closed (Number of employees was corrected throughout the MR.) d) Please correct the values of “Contributions over project lifetime” in Section 1.12 (First monitoring period is to be considered as well). Also, for “Current project contributions”, the net electricity generation value shall be used. Review-2: d) Ok Closed (The values in Section 1.12 were corrected.)	
CAR-9	2.1.5		It is revised.	Review-1:

Draft report CARs, CLs and FARs by verification team	Reference checklist question Periodic Verification Checklist	to in	Summary of project owner response	Verification team conclusion
Public Comment period is relevant to VCS. Therefore, please revise Section 2.1.5 of the MR.				Ok Closed (Section 2.1.5 was revised accordingly.)
CAR-10 Please remove the instruction part from Section 2.2.	2.2.1		It is removed	Review-1: Ok Closed (Section 2.2 was revised accordingly.)
CAR-11 Since the project carbon consultancy has changed, please indicate this in Section 3.2.2. Please also note in this section that the gas engine planned for 2024 has been postponed to a later date.	3.2.3		The relevant details are added to the section 3.2.2 of the PDD.	Review-1: Ok Closed (Relevant information was included in Section 3.2.2.)
CAR-12 Please use the emission factor value which is indicated in the registered VCS Joint PD-MR throughout the MR and in the ER Calculation Excel Sheet.	4.1.1		Emission factor is changed as 0.5552 as per the registered VCS Joint PD-MR throughout the MR and in the ER Calculation Excel Sheet.	Review-1: Ok Closed (The emission factor was corrected.)
CAR-13 a) Please complete Section 4.2 using the information in the registered VCS Joint PD-MR (e.g. source of data, description of data and so on). b) The serial number of the main meter in the electricity meters seen during the site visit was different from the serial number stated in Section	4.2.1		a) Revised. The net electricity generation is 8,788.376. Excel sheet updated accordingly. b) The relevant details are added to the section 4.2 of the PDD. Electricity	Review-1: a) In the Excel sheet, the net electricity generation value is indicated as 8,788.00 MWh. However, in Section 4.2, it is indicated as 8,788.376 MWh. Please correct the contradiction.

Draft report CARs, CLs and FARs by verification team	Reference checklist question Periodic Verification Checklist	to in	Summary of project owner response	Verification team conclusion
4.2 of the MR. Moreover, again during the site visit, it was learned that the electricity meters were changed in 2021. Please add this information to Section 4.2 and provide the relevant meter change document. c) Please indicate the calibration frequency of the electricity meters in Section 4.2. d) Please indicate the cross-checked method for the electricity generation in Section 4.2. e) Please include all ex-post parameters specified in the registered VCS PD-MR in Section 4.2 (i.e. EG_y). f) Please provide the hazardous waste and waste water disposal records covering the current monitoring period. g) Please provide the HSE training records covering the current monitoring period.			change document is provided, kindly see the supportive document file. Calibration date is updated. c) The relevant information is added to the section 4.2 of the PDD. The net electricity parameter is shown in $EG_{PJ,y}$ parameter table. EG_y parameter is taken as gross electricity generation in registered project document too. d) <i>EPIAS data is the main data and YEDAS readings (OSAS records) used for cross-check. This information is mentioned in section 4.2 of the PDD.</i> e) <i>EG_y parameter is added to the section 4.2 of the PDD.</i> f) <i>Kindly see the supportive documents file</i>	b) Please correct the date of calibration of the meters in Section 4.2. c) Ok Closed (The calibration frequency of the meters was included in Section 4.2.) d) Ok Closed (The cross-checked method was included in Section 4.2.) e) Please indicate the net electricity generation value in EG_y parameter table in Section 4.2. f) Ok Closed (The documents were provided.) g) Ok Closed (Training records were provided.) Review-2: a) Ok Closed (The electricity generation value was revised throughout the MR.) b) Ok Closed (The date was corrected in Section 4.2.) e) Ok Closed (The clarification was made.)

Draft report CARs, CLs and FARs by verification team	Reference checklist question Periodic Verification Checklist	to in	Summary of project owner response	Verification team conclusion
			<i>g) Kindly see the supportive documents file</i>	
CAR-14 a) Please include definitions of the symbols ($BE_y = BE_{CH4,y} + BE_{electricity}$) in the formulas in Section 5.1. b) Please correct the formula “ $BE_{y,electricity} = EG_{PJ,y} + EF_{grid,y}$ ” in Section 5.1. c) Please correct OM, BM and CM values in Section 5.1. d) Please provide all EPIAS records and OSOS records covering the monitoring period.	5.1.1	a) The relevant information is added to the section 5.1 of the PDD. b) The relevant formula is updated accordingly. c) It is fixed. d) Kindly see the supportive document file.	Review-1: a) Ok Closed (Definitions were included in Section 5.1.) b) Ok Closed (The formula was corrected in Section 5.1.) c) Ok Closed (The values were corrected in Section 5.1.) d) Ok Closed (EPIAS and OSOS records were provided.)	
CL-1 Please provide the signed and sealed letter on company letterhead that the project has not been registered, or has not been seeking registration under any other GHG programs.	1.10.1	Kindly see the supportive documents file.	Review-1: Ok Closed (The signed letter was provided.)	
CL-2 Please provide the signed and sealed letter on company letterhead that project has not been included in an emissions trading program; or any	1.11.1	Kindly see the supportive documents file.	Review-1: Ok Closed (The signed letter was provided.)	

Draft report CARs, CLs and FARs by verification team	Reference checklist question Periodic Verification Checklist	to in Summary of project owner response	Verification team conclusion
other mechanism that includes GHG allowance trading.			
CL-3 In Table 6 in Section 3.1, “Sinop Landfill Provisional Acceptance” date is stated as “29 June 2021”. However, the project start date is indicated as “01 July 2021”. Please state the reason for this situation in Section 3.1.	3.1.1	The relevant information is added to the section 3.1 of the PDD.	Review-1: Ok Closed (Relevant information was included in Section 3.1.)
CL-4 a) Please include the statement “All data collected as part of monitoring is being archived electronically by the Project Proponent and be kept at least for 2 years after the end of the last crediting period.” in Section 4.3. b) Please include the organizational chart in Section 4.3. c) Please explain leakage management in Section 4.3 with providing the relevant evidence document (i.e. signed contract between the PO and Gerze Municipality).	4.3.1	a) The relevant information is added to section 4.3 of the PDD. b) Organization chart is added to the section 4.3 of the PDD. c) The relevant detail is added to the PDD. Records of the leachate is provided. Kindly see the supportive document file.	Review-1: a) Ok Closed (Relevant information was included in Section 4.3.) b) Ok Closed (The organizational chart was included in Section 4.3.) c) Ok Closed (Relevant information was included in Section 4.3 and the relevant evidence document was provided.)